

F.A. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
74	(72-7)R-3	PEORIA	1360	92
STA.		TO STA.		
FED. ROAD DIST. NO.		ILLINOIS FED. AID PROJECT		

INTERSTATE I-74				MODULAR GLARE SCREEN SYSTEM	IMPACT ATTENUATORS TEMPORARY (NON-REDIRECTIVE) TEST LEVEL 3	STAGE 3-1			STAGE 3-2		STAGE 3-4	
LOCATIONS	STA	TO	STA			TEMPORARY CONCRETE BARRIER (STATE OWNED)	RELOCATE TEMPORARY CONCRETE BARRIER (STATE OWNED)	REMOVAL & DISPOSAL OF TEMPORARY CONCRETE BARRIER	RELOCATE TEMPORARY CONCRETE BARRIER (STATE OWNED)	REMOVAL & DISPOSAL OF TEMPORARY CONCRETE BARRIER	RELOCATE TEMPORARY CONCRETE BARRIER (STATE OWNED)	REMOVAL & DISPOSAL OF TEMPORARY CONCRETE BARRIER
				M	EA	M	M	M	M	M	M	
WB I-74	141+450.000	TO	141+600.000				61.0				61.0	
	141+600.000	TO	141+950.000			343.0	7.0				7.0	343.0
	141+950.000	TO	142+300.000			350.0						350.0
	142+300.000	TO	142+650.000		1.0	350.0	150.0		150.0			500.0
	142+650.000	TO	143+000.000	122.0		350.0			250.0			350.0
	143+000.000	TO	143+300.000	300.0	2.0	331.0		160.0				331.0
	143+300.000	TO	143+650.000	350.0		514.0						514.0
	143+650.000	TO	143+950.000	300.0		300.0						300.0
	143+950.000	TO	144+250.000	300.0		300.0		150.0				300.0
	144+250.000	TO	144+325.000	75.0		75.0		75.0				75.0
	144+325.000	TO	144+600.000	275.0		275.0		275.0				275.0
	144+600.000	TO	144+718.000	118.0		118.0		118.0				118.0
SUBTOTAL, 2-LANE				1,372.0	3.0	2,838.0	218.0	310.0	150.0	250.0	68.0	2,988.0
SUBTOTAL, 3-LANE				468.0	0.0	468.0	0.0	468.0	0.0	0.0	0.0	468.0
SUBTOTAL				1,840.0	3.0	3,306.0	218.0	778.0	150.0	250.0	68.0	3,456.0
TOTAL, ALL STAGES 2-LANE				1,372.0	3.0	2,838.0	436.0	3,548.0				
TOTAL, ALL STAGES 3-LANE				468.0	0.0	468.0	0.0	936.0				
TOTALS				1,840.0	3.0	3,306.0	436.0	4,484.0				



REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION
 TEMPORARY CONCRETE BARRIER
 FAI ROUTE 74 (I-74) (WB)
 SCHEDULES
 DATE 11/12/04
 DRAWN BY CADD
 CHECKED BY