

F.A. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
74	(72-7)R-3	PEORIA	1360	100
STA.		TO STA.		
FED. ROAD DIST. NO.		ILLINOIS	FED. AID PROJECT	

PERMANENT PAVEMENT MARKINGS SCHEDULE						
FAI ROUTE 74					RAISED REFLECTIVE MARKERS	
LOCATIONS	STA	TO	STA	L	2- WAY EACH	1- WAY EACH
I-74 & RAMPS						
	141+900.00	TO	141+950.00			
I74 EB	141+900.000		141+950.000	50		2
I74 WB	141+900.000		141+950.000	50		2
	141+950.00	TO	142+300.000			
I74 EB	141+950.000		142+300.000	350		14
I74 WB	141+950.000		142+205.000	255		10
I74 WB	142+205.000		142+300.000	95		4
	142+300.00	TO	142+650.000			
I-74 EB	142+300.000		142+328.000	28		1
I-74 EB	142+326.000		142+400.000	74		9
I-74 EB	142+400.000		142+526.000	126		5
I-74 EB	142+526.000		142+650.000	124		5
I74 WB	142+300.000		142+460.000	160		7
I74 WB	142+460.000		142+610.000	150		6
I74 WB	142+610.000		142+650.000	40		2
RAMP A-1	10+000.000		10+072.000	72		12
RAMP A-1	10+072.000		10+199.000	127		31
RAMP A-1	10+199.000		10+326.000	127		21
	142+650.00	TO	143+000.000			
I-74 EB	142+650.000		143+000.000	350		14
I74 WB	142+650.000		142+880.000	230		9
I74 WB	142+880.000		143+000.000	120		5
RAMP A-1	10+326.000		10+375.000	49		8
	143+000.00	TO	143+300.000			
I-74 EB	143+000.000		143+145.000	145		6
I-74 EB	143+145.000		143+300.000	155		6
I-74WB	143+000.000		143+140.000	140		6
I-74WB	143+140.000		143+300.000	160		7
	143+300.00	TO	143+650.000			
I-74 EB	143+300.000		143+325.000	25		1
I-74 EB	143+325.000		143+375.000	50		4
I-74 EB	143+375.000		143+650.000	275		23
I-74 WB	143+300.000		143+325.000	25		1
I-74 WB	143+325.000		143+621.000	296		12
I-74 WB	143+621.000		143+650.000	29		4
RAMPA-3	10+172.000		10+221.000	49		12
SUBTOTAL, I-74 & RAMPS					0.00	249.37

PERMANENT PAVEMENT MARKINGS SCHEDULE						
FAI ROUTE 74					RAISED REFLECTIVE MARKERS	
LOCATIONS	STA	TO	STA	L	2- WAY EACH	1- WAY EACH
I-74 & RAMPS						
	143+650.00	TO	143+950.000			
I74EB	143+650.000		143+670.000	20		2
I74EB	143+670.000		143+690.000	20		2
I74EB	143+690.000		143+811.000	121		15
I74EB	143+811.000		143+950.000	139		6
I74WB	143+650.000		143+730.000	80		10
I74WB	143+730.000		143+820.000	90		4
I74WB	143+820.000		143+950.000	130		5
RAMP A-3	10+000.000		10+090.000	90		15
RAMP A-3	10+090.000		10+172.000	82		20
RAMP B-1	10+000.000		10+020.000	20		3
RAMP B-1	10+020.000		10+138.000	118		29
RAMP B-1	10+138.000		10+175.000	37		3
RAMP B-2	10+325.000		10+430.000	105		17
RAMP B-2	10+430.000		10+550.000	120		30
RAMP B-2	10+550.000		10+583.000	33		3
RAMP B-3	10+000.000		10+122.000	122		10
	10+175.000	TO	10+700.000			
RAMP B-1	10+175.000		10+490.000	315		26
	143+950.00	TO	144+250.000			
I74EB	143+950.000		144+178.000	228		9
I74EB	144+178.000		144+250.000	72		3
I74WB	143+950.000		144+030.000	80		3
I74WB	144+030.000		144+147.000	117		14
I74WB	144+147.000		144+220.000	73		3
I74WB	144+220.000		144+250.000	30		1
RAMP B-2	10+000.000		10+075.000	75		12
RAMP B-2	10+075.000		10+193.000	118		29
	144+250.00	TO	144+600.000			
I74EB	144+250.000		144+440.000	190		8
I74EB	144+440.000		144+600.000	160		13
I74WB	144+250.000		144+600.000	350		29
	144+600.00	TO	144+718.000			
I74EB	144+600.000		144+718.000	118		10
I74WB	144+600.000		144+718.000	118		10
SUBTOTAL, I-74 & RAMPS					0.00	342.86
TOTAL, I-74 & RAMPS					0.00	592.22

REVISIONS		ILLINOIS DEPARTMENT OF TRANSPORTATION PERMANENT PAVEMENT MARKING FAI ROUTE 74 (I-74) (WB) SCHEDULES
NAME	DATE	



DATE 11/12/04
DRAWN BY CADD
CHECKED BY RSC