F.A.I. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
74	(72-7)R-3	PEORIA	1360	910
STA.		TO STA.		
FED. ROAD DIST. NO.		ILLINOIS	FED. AID PROJECT	

TREE REMOVAL SCHEDULE

LOCATION				TREE REMOVAL (6 TO 15 UNITS DIAMETER) UNIT	TREE REMOVAL (OVER 15 UNITS DIAMETER) UNIT	TREE REMOVAL, HECTARES HA
FAI ROUTE 74 WESTBOUND						
STA. 144+836.180	OFF	25.140 m	LT	15		
STA. 144+856.750	TO	STA. 145+050.000	LT			0.054
STA. 145+050.000	TO	STA. 145+154.750	LT			0.029
STA. 145+425.200	TO	STA. 145+694.854	LT			0.134
STA. 145+714.702	OFF	21.292 m	LT	8		
STA. 145+708.855	OFF	23.230 m	LT	10		
STA. 145+971.983	TO	STA. 146+063.553	LT			0.032
STA. 146+088.045	OFF	20.785 m	LT	11		
STA. 146+120.025	OFF	21.160 m	LT	13		
STA. 146+335.910	OFF	21.315 m	LT	10		
STA. 146+345.365	OFF	24.490 m	LT	12		
STA. 146+097.530	TO	STA. 146+122.420	LT			0.006
STA. 146+153.000	TO	STA. 146+410.000	LT			0.330
RAMP C-3						
STA. 10+162.450	TO	STA. 10+358.960				0.090
STA. 10+413.490	OFF	31.300 m	RT	15		
STA. 10+487.410	OFF	39.970 m	RT	15		
STA. 10+571.585	OFF	11.625 m	LT	14		
STA. 10+405.445	OFF	7.335 m	LT		51	
STA. 10+457.985	OFF	3.325 m	RT		58	
STA. 10+437.975	OFF	2.455 m	RT		33	
STA. 10+502.665	OFF	6.635 m	LT		51	
STA. 10+503.315	OFF	0.210 m	LT		23	
STA. 10+370.000	TO	STA. 10+383.125	RT			0.007
STA. 10+421.800	TO	STA. 10+598.650	RT			0.176
STA. 10+310.425	OFF	5.710 m	LT	14		
STA. 10+319.390	OFF	15.995 m	RT	14		
STA. 10+343.440	OFF	16.485 m	RT		20	
STA. 10+358.255	OFF	3.435 m	RT		74	
STA. 10+327.050	TO	STA. 10+370.000	RT			0.021
			SUBTOTAL	151	310	0.879
			TOTAL	151	310	0.9

COMBINATION CONCRETE CURB AND GUTTER REMOVAL SCHEDULE

LOCATION				COMB. CONC. CURB AND GUTTER REMOVAL M
RAMP C-3				
STA. 10+282.120	TO	STA. 10+370.000	LT	89.30
STA. 10+370.000	TO	STA. 10+371.890	LT	1.87
			SUBTOTAL	91.17
			TOTAL	92

PAVEMENT REMOVAL SCHEDULE

LOCATION			PAVEMENT REMOVAL SQ M
FAI ROUTE 74 WESTBOUND			
STA. 144+718.000	TO	STA. 145+050.000	5,141.05
STA. 145+050.000	TO	STA. 145+390.000	5,786.20
STA. 145+390.000	TO	STA. 145+730.000	5,081.85
STA. 145+730.000	TO	STA. 146+070.000	5,115.90
STA. 146+070.000	TO	STA. 146+410.000	4,674.95
RAMP C-3			
STA. 10+370.000	TO	STA. 10+598.650	1,313.30
STA. 10+472.230	TO	STA. 10+575.000	697.75
STA. 10+276.120	TO	STA. 10+370.000	332.80
		SUBTOTAL	28,143.80
		TOTAL	28,144

GUARDRAIL REMOVAL SCHEDULE

LOCATION				GUARDRAIL REMOVAL M
RAMP C-3				
STA. 10+370.000	TO	STA. 10+598.650	LT/RT	235.25
STA. 10+438.840	TO	STA. 10+472.265	RT	33.14
STA. 10+292.555	TO	STA. 10+349.540	LT	57.40
STA. 10+353.795	TO	STA. 10+370.000	LT	17.20
STA. 10+575.000	TO	STA. 10+598.650	RT	22.89
		SUBTOTAL		365.88
		TOTAL		366

PAVED SHOULDER REMOVAL SCHEDULE

LOCATION			PAVED SHOULDER REMOVAL SQ M
RAMP C-3			
STA. 10+370.000	TO	STA. 10+573.730	258.45
STA. 10+370.000	TO	STA. 10+875.000	519.45
STA. 10+234.933	TO	STA. 10+370.000	319.50
STA. 10+327.293	TO	STA. 10+370.000	48.95
		SUBTOTAL	1,146.35
		TOTAL	1,147

STORM SEWER REMOVAL SCHEDULE

LOCATION							STORM SEWER REMOVAL 600MM M	STORM SEWER REMOVAL 1200MM M	CONCRETE HEADWALL REMOVAL EACH
FAI ROUTE 74 WESTBOUND									
STA. 145+793.097	3.500 m	RT	TO	STA. 145+797.179	31.904 m	LT	35.600		
STA. 146+220.574	19.825 m	LT							1
STA. 146+220.574	19.825 m	LT	TO	STA. 146+220.477	10.295 m	LT		9.531	
						SUBTOTAL	35.600	9.531	1
						TOTAL	36.0	10.0	1

FENCE REMOVAL SCHEDULE

LOCATION				FENCE REMOVAL M
FAI ROUTE 74 WESTBOUND				
STA. 144+808.410	TO	STA. 144+812.410	LT	4.100
STA. 145+416.847	TO	STA. 145+422.500	LT	5.650
STA. 145+659.925	TO	STA. 145+671.005	LT	11.200
STA. 145+659.925	TO	STA. 145+689.525	LT	29.500
STA. 145+671.005	TO	STA. 145+689.525	LT	21.400
STA. 145+987.506	TO	STA. 146+070.000	LT	102.500
STA. 146+070.000	TO	STA. 146+187.265	LT	117.500
STA. 146+252.910	TO	STA. 146+299.320	LT	46.500
RAMP C-3				
STA. 10+370.000	TO	STA. 10+387.285	RT	20.500
STA. 10+275.000	TO	STA. 10+350.655	RT	77.400
STA. 10+275.000	TO	STA. 10+350.400	RT	75.900
STA. 10+292.950	TO	STA. 10+370.000	RT	78.900
STA. 10+350.400	TO	STA. 10+350.655	RT	2.770
		SUBTOTAL		593.820
		TOTAL		594.0

TEMPORARY CONCRETE BARRIER SCHEDULE

LOCATION					RELOCATE TEMPORARY CONCRETE BARRIER (STATE OWNED) M	REMOVAL AND DISPOSAL OF TEMPORARY CONCRETE BARRIER (STATE OWNED) M	IMPACT ATTENUATOR REMOVAL EACH
FAI ROUTE 74 WESTBOUND							
STAGE 3-1							
STA. 144+718.000	LT	TO	STA. 145+050.000	LT		332.45	
STA. 144+718.000	LT	TO	STA. 145+050.000	LT	332.45		
STA. 145+050.000	LT	TO	STA. 145+230.926	LT		183.00	
STA. 145+050.000	LT	TO	STA. 145+390.000	LT	341.60		
STA. 145+390.000	LT	TO	STA. 145+730.000	LT	341.60		
STA. 145+730.000	LT	TO	STA. 146+070.000	LT	341.60		
STA. 145+805.913	LT	TO	STA. 146+070.000	LT		265.35	
STA. 146+070.000	LT	TO	STA. 146+104.656	LT		36.60	
STA. 146+070.000	LT	TO	STA. 146+410.000	LT	341.60		
STA. 146+102.500	LT						1
STAGE 3-4							
STA. 144+718.000	RT	TO	STA. 145+050.000	RT		332.45	
STA. 145+050.000	RT	TO	STA. 145+390.000	RT		341.60	
STA. 145+390.000	RT	TO	STA. 145+730.000	RT		341.60	
STA. 145+730.000	RT	TO	STA. 146+070.000	RT		341.60	
STA. 146+070.000	RT	TO	STA. 146+410.000	RT		341.60	
RAMP C-3							
STAGE 3-1							
STA. 10+472.265	RT	TO	STA. 10+575.000	RT		109.80	
				SUBTOTAL	1,698.85	2,626.05	1
				TOTAL	1,698.85	2,626.05	1

PAVED DITCH REMOVAL SCHEDULE

LOCATION				PAVED DITCH REMOVAL M
FAI ROUTE 74 WESTBOUND				
STA. 145+688.703	TO	STA. 145+730.000	LT	42.50
STA. 145+730.000	TO	STA. 145+731.840	LT	1.90
STA. 146+130.300	TO	STA. 146+150.791	LT	20.60
RAMP C-3				
STA. 10+370.000	TO	STA. 10+403.035	RT	36.00
STA. 10+531.355	TO	STA. 10+640.515	LT	114.05
STA. 10+307.022	TO	STA. 10+308.031	LT/RT	9.40
STA. 10+338.050	TO	STA. 10+370.000	RT	32.00
		SUBTOTAL		256.45
		TOTAL		257

REVISIONS	
NAME	DATE

CLARK ENGINEERS, INC.

ILLINOIS DEPARTMENT OF TRANSPORTATION

SCHEDULE OF QUANTITIES
FAI ROUTE 74 (I-74)

DRAWN BY CAM

DATE 11/23/04

CHECKED BY LSA