F.A.I. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
74	*	PEORIA	1360	1014
STA.		TO STA.		
FED. ROAD DIST. NO.		ILLINOIS	FED. AID PROJECT	

SIGN NUMBER	DS2-19	
WIDTH x HGHT.	1190mm x 2990mm	
BORDER WIDTH		
CORNER RADIUS		
MOUNTING	Ground	
BACKGROUND	TYPE:	Reflective
	COLOR:	Orange
LEGEND/BORDER	TYPE:	N/A
	COLOR:	N/A

SYMBOL	X	Y	WID	HT

Dimensions are in mm

Letter spacings are to start of next letter

LETTER POSITIONS (X)	LENGTH	SERIES/SIZE

DS2-19
SIGN PANEL OVERLAY, SPECIAL, 3.56 SQ M.
WB RT. STA. 146+300.000.

SIGN NUMBER	DS2-20	
WIDTH x HGHT.	1211mm x 301mm	
BORDER WIDTH		
CORNER RADIUS		
MOUNTING		
BACKGROUND	TYPE:	Reflective
	COLOR:	Orange
LEGEND/BORDER	TYPE:	Reflective
	COLOR:	Black

SYMBOL	X	Y	WID	HT

Dimensions are in mm

Letter spacings are to start of next letter

LETTER POSITIONS (X)								LENGTH	SERIES/SIZE
	C	L	O	S	E	D			D200
105	175	162	181	185	162	136	105	1001	

DS2-20
COMPOSITE TEMPORARY SIGN OVERLAY, 0.36 SQ M.
WB RT. STA. 146+380.000.

REVISIONS	
NAME	DATE

CLARK ENGINEERS, INC.

ILLINOIS DEPARTMENT OF TRANSPORTATION

SIGN PANEL DETAILS

DRAWN BY RDY

DATE 11/23/04

CHECKED BY LSA

...sign\phase1\cat1206-2s.dgn 12/14/04 10:23:27 AM