

F.A.I. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
74	(72-7)R-3	PEORIA	1360	1183
STA.		TO STA.		
FED. ROAD DIST. NO.		ILLINOIS	FED. AID PROJECT	
CONTRACT NO. 68200				

FOR INFORMATION ONLY

SET #3 TOTAL BILL OF MATERIALS
LIGHTING, SIGNING & ITS

					URBAN																
					IM																
					90% FED 10% STATE							90% FED 5% STATE 5% CITY			90% FED 10% STATE						
CODE NO.	PAY ITEM	UNIT	TOTAL QUANTITY		ROADWAY 1000-2A	ROADWAY J000-2A	BRIDGE (1) X271-2A	BRIDGE (2) X281-2A	BRIDGE (3) X781-2A	BRIDGE (4) X028-2A	MINOR STRUCTURES (5) Y007	OVERHEAD SIGNS Y002-1C	LIGHTING Y030-1E	ITS Y035	TRAFFIC SIGNAL INTER- CONNECT Y031-1F	TRAFFIC SIGNALS Y031-1F	TRAFFIC SIGNAL INTER- CONNECT Y031-1F	TRAFFIC SIGNALS Y031-1F	TRAFFIC SIGNAL INTER- CONNECT Y031-1F	TRAFFIC SIGNALS Y031-1F	
					BIT	CONC	A3	B3/B5	B1/B4	CULVERT >20	CULVERT<20, R WALL				WAR MEMORIAL DR/ STERLING/GLEN	WAR MEMORIAL DR/ SCENIC DR	SCENIC DR/ MALL ENTRANCE				
M7200300	SIGN PANEL - TYPE 3	SQ M	262		92	16															
M7270100	STRUCTURAL STEEL SIGN SUPPORT - BREAKAWAY	KG	3450		3050	400															
M7290100	METAL POST - TYPE A	METER	8.5		8.5																
M7290200	METAL POST - TYPE B	METER	17.0		13.0	4.0															
M7300100	WOOD SIGN SUPPORT	METER	265.5		239.5	26.0															
M7330050	OVERHEAD SIGN STRUCTURE - SPAN, TYPE I-S (1.22M X 1.37M)	METER	63.5									63.5									
M7330255	OVERHEAD SIGN STRUCTURE - CANTILEVER, TYPE III-C-A (0.90M x 2.14M)	METER	22.6									22.6									
M7340100	CONCRETE FOUNDATIONS	CU M	11.9		9.8	2.1															
M7340200	DRILLED SHAFT CONCRETE FOUNDATIONS	CU M	64.4									64.4									
M8080150	TEMPORARY WOOD POLE, 15.24M, CLASS 4	EACH	10										10								
M8100260	CONDUIT IN TRENCH, 50MM DIA., PVC	METER	1927.0										1723.0	204.0							
M8100280	CONDUIT IN TRENCH, 75MM DIA., PVC	METER	4069.0										4069.0								
M8101450	CONDUIT PUSHED, 50MM DIA., PVC	METER	173.0											173.0							
M8101470	CONDUIT PUSHED, 75MM DIA., PVC	METER	17.0										17.0								
M8110130	CONDUIT ATTACHED TO STRUCTURE, 25MM DIA. GALVANIZED STEEL	METER	436.0										436.0								
M8120230	CONDUIT EMBEDDED IN STRUCTURE, 50MM DIA. PVC	METER	179.0										179.0								
M8120250	CONDUIT EMBEDDED IN STRUCTURE, 75MM DIA. PVC	METER	494.0										494.0								
M8130120	JUNCTION BOX, STAINLESS STEEL, ATTACHED TO STRUCTURE, 150MM X 150MM X 100MM	EACH	46										46								
M8130415	JUNCTION BOX, STAINLESS STEEL, EMBEDDED IN STRUCTURE, 300MM X 300MM X 200MM	EACH	13										13								
M8131500	JUNCTION BOX, NON-METALLIC, EMBEDDED IN STRUCTURE, 675MM X 400MM X 300MM	EACH	3										3								
M8150200	TRENCH AND BACKFILL FOR ELECTRICAL WORK	METER	5495.5										5373.0	122.5							
M8170030	ELECTRIC CABLE IN CONDUIT, 600V (XLP-TYPE USE) 1/C NO.8	METER	2927.0										2927.0								
M8170040	ELECTRIC CABLE IN CONDUIT, 600V (XLP-TYPE USE) 1/C NO.6	METER	5120.0										5120.0								

- * SPECIALTY ITEMS
- + FUND CODE SFTY-3N
- ++ FUND CODE YO80
- +++ FUND CODE SFTY-3C
- D NON PARTICIPATING

- (1) RAMP A-3 OVER RAMP B-5, SN 072-0172
- (2) RAMPS B-3 & B-5 OVER US 150 & RAMP B-6, SN 072-0190
- (3) RAMPS B-1 & B-4 OVER RAMPS A-3, B-3 & I-74, SN 072-0183

SET 3 SHEET 4

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION

SET 3
TOTAL BILL OF MATERIALS

ab **alfred benesch & company**
CONSULTING ENGINEERS
205 NORTH MICHIGAN AVENUE, CHICAGO, ILLINOIS 60601

DATE: 11/15/04

DRAWN BY DJK
CHECKED BY DPA

J:\projects\data\3573\contract 10_packing\PS&E\Set for DS7 comb\neq\Plans\Sheets\set\002-Ta.dgn 2:57:49 PM 11/15/2004