

F.A.I. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
74	(72-71R-3)	PEORIA	1360	1189
STA.		TO STA.		
FED. ROAD DIST. NO.		ILLINOIS FED. AID PROJECT		

CONTRACT NO. 68200

POLE AND LUMINAIRE SCHEDULE

POLE									LUMINAIRE				
LOCATION		TYPE	HEIGHT (M)	FOUNDATION *		IDENTIFICATION			QUANTITY	DISTRIBUTION TYPE	SHIELD SIZE (MM)		WATT/VOLT
STATION (BASE LINE)	OFFSET			TYPE	DEPTH (M)	CONTROLLER	CIRCUIT	NUMBER			HOUSE SIDE	STREET SIDE	
142+388.1 (I-74 EB)	MEDIAN	HIGH MAST	24	1	**	S	AB	4	4	M-C-III	300	300	400/240
142+487.2 (I-74 EB)	MEDIAN	HIGH MAST	24	1	**	S	AB	3	6	M-C-III	200	200	400/240
142+902.6 (I-74 EB)	29.4 L	HIGH MAST	30	2	**	S	HI	1	5	M-C-III	200	200	400/240
143+067.5 (I-74 EB)	27.0 L	HIGH MAST	30	2	**	S	HI	2	5	M-C-V	200	200	400/240
143+206.0 (I-74 EB)	32.5 L	HIGH MAST	30	2	**	S	HI	3	5	M-C-V	200	200	400/240
143+290.0 (I-74 EB)	32.0 L	HIGH MAST	30	2	**	S	HI	4	6	M-C-III	200	200	400/240
143+415.0 (I-74 EB)	28.0 L	HIGH MAST	30	2	**	S	HI	5	6	M-C-II	300	300	400/240
143+581.5 (I-74 EB)	50.0 L	HIGH MAST	30	2	**	W	CD	2	8	M-C-V	200	200	400/240
143+704.0 (I-74 EB)	55.0 L	HIGH MAST	30	2	**	W	CD	1	4	M-C-II	300	300	400/240
145+554.2 (I-74 EB)	66.6 L	HIGH MAST	30	2	**	G	CD	1	5	M-C-II	400	N.A.	400/240
145+715.2 (I-74 EB)	57.6 L	HIGH MAST	30	2	**	G	CD	2	5	M-C-II	400	N.A.	400/240
39+716.0 (WM)	35.0 L	HIGH MAST	24	2	**	J	CD	4	8	M-C-II	400	N.A.	400/240
39+807.0 (WM)	31.0 R	HIGH MAST	24	2	**	J	CD	5	4	M-C-V	200	200	400/240
39+898.0 (WM)	26.0 L	HIGH MAST	24	2	**	J	AB	1	6	M-C-II	200	200	400/240
40+000.0 (WM)	27.0 R	HIGH MAST	24	2	**	J	AB	2	4	M-C-III	200	200	400/240
40+123.0 (WM)	23.0 L	HIGH MAST	24	2	**	J	EF	1	4	M-C-III	200	200	400/240


- FOR TYPE 1 FOUNDATION DETAILS SEE SHEET #49
FOR TYPE 2 FOUNDATION DETAILS SEE SHEET #50
- ** FOR TYPE 1 FOUNDATION DEPTHS SEE SHEET #49
FOR TYPE 2 FOUNDATION DEPTHS SEE SHEET #51

LIGHTING SHEET 5 OF 64

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION

POLE AND LUMINAIRE SCHEDULE


alfred benesch & company
 CONSULTING ENGINEERS
 205 NORTH MICHIGAN AVENUE, CHICAGO, ILLINOIS 60601

DATE: 11/12/04
 DRAWN BY DJK
 CHECKED BY MKR

m:\proj\357\3\lighting\7\contract\01\1000-7a_luminaire_schedule.dgn

4/3/08 PM

11/12/2004