

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
693	*	TAZEWELL	...	5
STA.		TO STA.		
FED. ROAD DIST. NO.		ILLINOIS	FED. AID PROJECT	
* D4 CULVERT EXT. / REPAIR 2005-2				

SUMMARY OF QUANTITIES

SUMMARY OF QUANTITIES			Y007 CONSTRUCTION TYPE CODE				
CODE NO.	ITEM	UNITS	TOTAL QUANTITY	LOCATION 1	LOCATION 2	LOCATION 3	LOCATION 4
54248510	CONCRETE COLLAR	CU YD	4.4		0.7	0.7	3.0
542D0223	PIPE CULVERTS, CLASS D, TYPE 1 18"	FOOT	48	48			
* 63200310	GUARDRAIL REMOVAL	FOOT	1,900	200	800	400	500
* 63301210	REMOVE AND RE-ERECT SPBG, TYPE A	FOOT	263	263			
67000400	ENGINEER'S FIELD OFFICE, TYPE A	CAL MO	3	1	0.5	0.5	1
67100100	MOBILIZATION	L. SUM	1	0.25	0.25	0.25	0.25
70100450	TRAFFIC CONTROL AND PROTECTION, STANDARD 701201	L.SUM	1	0.25	0.25	0.25	0.25
78200410	GUARDRAIL MARKER TYPE A	EACH	4	4			
78201000	TERMINAR MARKER - DIRECT APPLIED	EACH	2	2			
* B2001164	TREE, CERCIS CANADENSIS (EASTERN REDBUD) 5' HEIGHT, CLUMP FORM, BALLED AND BURLAPPED	EACH	5				5
X0301512	GUARDRAIL AGGREGATE EROSION CONTROL	TON	36	36			
XX002909	CLASS SI CONCRETE	CU YD	83	37.8			45.2
Z0013798	CONSTRUCTION LAYOUT	L. SUM	1	0.25	0.25	0.25	0.25
Z0054500	ROCK FILL	TON	228	136			92
X0324936	GALVANIZED STEEL PIPE 3 1/2"	FOOT	209	209			
66600105	FURNISHING AND ERECTING RIGHT OF WAY MARKERS	EACH	45	4	16	16	9

*SPECIALTY ITEMS