

# SCHEDULE OF QUANTITIES

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
693	*	TAZEWELL	...	10
STA.		TO STA.		
FED. ROAD DIST. NO.		ILLINOIS	FED. AID PROJECT	

\* D4 CULVERT EXT. / REPAIR 2005-2

CODE NO.25100630

EROSION CONTROL BLANKET	
	UNIT SQ YD
<b>LOCATION 1</b>	
Lt. Sta. 582+53.65 to Sta. 583+28.65	47
Lt. Sta. 583+66.15 to Sta. 585+54.10	161
<b>LOCATION 2</b>	
Lt. Sta. 721+00 to Sta. 723+93.26	196
Lt. Sta. 724+13.24 to Sta. 725+50	91
<b>LOCATION 3</b>	
Lt. Sta. 736+50 to Sta. 737+50	67
<b>LOCATION 4</b>	
Lt. Sta. 860+10 to Sta. 860+50	27
<b>TOTAL = 589</b>	

CODE NO.28000400

PERIMETER EROSION BARRIER	
	UNIT FOOT
<b>LOCATION 1</b>	
Rt. Sta. 581+00 to Sta. 586+00	409
Lt. Sta. 582+80 to Sta. 583+28	50
Lt. Sta. 583+66.15 to Sta. 585+32	170
<b>LOCATION 2</b>	
Rt. Sta. 720+00 to Sta. 726+00	645
<b>LOCATION 3</b>	
Rt. Sta. 733+00 to Sta. 739+00	621
<b>LOCATION 4</b>	
Lt. Sta. 857+50 to Sta. 859+00	150
Lt. Sta. 861+50 to Sta. 862+25	75
Rt. Sta. 858+50 to Sta. 859+50	100
Rt. Sta. 860+90 to Sta. 862+50	135
<b>TOTAL = 2,355</b>	

CODE NO.44004250

PAVED SHOULDER REMOVAL	
	UNIT SQ YD
<b>LOCATION 1</b>	
Rt. Sta. 581+75.60 to Sta. 582+11.79	12
<b>TOTAL = 12</b>	

CODE NO.28000300

TEMPORARY DITCH CHECK		
	Spacing	UNIT EACH
<b>LOCATION 1</b>		
Rt. Sta. 582+25 to Sta. 583+45	40 ft	3
<b>LOCATION 2</b>		
Lt. Sta. 720+50 to Sta. 723+00	200 ft	1
Lt. Sta. 723+00 to Sta. 724+00	100 ft	2
Lt. Sta. 724+00 to Sta. 726+00	200 ft	3
<b>LOCATION 3</b>		
Lt. Sta. 735+50 to Sta. 736+00	50 ft	1
Lt. Sta. 736+00 to Sta. 736+50	26 ft	2
Lt. Sta. 736+50 to Sta. 738+00	100 ft	2
<b>LOCATION 4</b>		
Lt. Sta. 859+00 to Sta. 859+70	30 ft	3
Lt. Sta. 859+83 to Sta. 860+50	30 ft	3
Rt. Sta. 859+50 to Sta. 860+50	30 ft	4
<b>TOTAL = 24</b>		

CODE NO.40200800

AGGREGATE SURFACE COURSE TYPE "B"	
Note: 8" deep	
	UNIT TON
<b>LOCATION 1</b>	
Rt. Sta. 581+95	76
<b>TOTAL = 76</b>	

CODE NO.48101200

AGGREGATE SHOULDER TYPE B	
	UNIT TON
<b>LOCATION 1</b>	
Rt. Sta. 581+00 to Sta. 585+75	60
<b>LOCATION 2</b>	
Lt. Sta. 720+30 to Sta. 725+70	68.5
Rt. Sta. 720+30 to Sta. 726+00	72.5
<b>LOCATION 3</b>	
Lt. Sta. 734+00 to Sta. 738+00	50.5
Rt. Sta. 734+00 to Sta. 738+00	50.5
<b>LOCATION 4</b>	
Lt. Sta. 857+30 to Sta. 862+11.40	60.3
Rt. Sta. 858+30.08 to Sta. 862+33.99	50.7
<b>TOTAL = 413</b>	

CODE NO.44000800

BITUMINOUS CONCRETE CURB REMOVAL	
	UNIT FOOT
<b>LOCATION 1</b>	
Rt. Sta. 583+15 to Sta. 584+16	101
<b>TOTAL = 101</b>	

CODE NO.50105220

PIPE CULVERT REMOVAL	
	UNIT FOOT
<b>LOCATION 1</b>	
Rt. Sta. 581+95	32
Rt. Sta. 583+33	19
<b>TOTAL = 51</b>	