

SCHEDULE OF QUANTITIES

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
693	*	TAZEWELL	---	11
STA.		TO STA.		
FED. ROAD DIST. NO.	ILLINOIS	FED. AID PROJECT		
* D4 CULVERT EXT. / REPAIR 2005-2				

CODE NO.	XX002909	54248510	50800105	50800205	54002020
	CLASS SI CONCRETE	CONCRETE COLLAR	REINFORCEMENT BARS	REINFORCEMENT BARS, EPOXY COATED	EXPANSION BOLTS 3/4 INCH
	CU YD	CU YD	LBS	LBS	EACH
LOCATION 1					
Lt. Sta. 583+51.04	37.8		5,919		26
LOCATION 2					
Rt. Sta. 723+98.29		0.35	20		4
Rt. Sta. 723+98.29		0.35	20		4
LOCATION 3					
Rt. Sta. 735+97.11		0.35	20		4
Lt. Sta. 735+99.45		0.35	20		4
LOCATION 4					
Lt. Sta. 860+23	22.6	1.50	2,525.5	127	14
Rt. Sta. 860+23	22.6	1.50	2,525.5	127	14
TOTAL =	83.0	4.40	11,050	254	70

CODE NO.54213675

PRCF END SECTIONS 30"	
	UNIT EACH
LOCATION 2	
Rt. Sta. 723+98.24	1
Lt. Sta. 724+02.72	1
LOCATION 3	
Rt. Sta. 735+98	1
Lt. Sta. 735+98	1
TOTAL = 4	

CODE NO.542D0223

PIPE CULVERTS, CLASS D, TYPE I, 18"	
	UNIT FOOT
LOCATION 1	
Rt. Sta. 581+95	48
TOTAL = 48	

CODE NO.50102400

CONCRETE REMOVAL	
	UNIT CU YD
LOCATION 1	
Lt. Sta. 582+53.65 to Sta. 583+28.65	8
LOCATION 4	
Lt. Sta. 860+23.21	7
Rt. Sta. 860+23.21	8
TOTAL = 23	

CODE NO.54201285

PIPE CULVERTS, TYPE 2 RCCP 30"	
	UNIT FOOT
LOCATION 2	
Rt. Sta. 724+00	26.5
Lt. Sta. 724+00	26
LOCATION 3	
Rt. Sta. 735+98	26.1
Lt. Sta. 735+98	25.2
TOTAL = 104	

CODE NO.63200310

GUARDRAIL REMOVAL	
	UNIT FOOT
LOCATION 1	
Rt. Sta. 583+27.48 to Sta. 584+29.83	200
LOCATION 2	
Rt. Sta. 721+00.41 to Sta. 725+00.68	400
Lt. Sta. 721+00.75 to Sta. 725+01.50	400
LOCATION 3	
Rt. Sta. 734+99.34 to Sta. 737+01.38	200
Lt. Sta. 735+01.15 to Sta. 737+01.90	200
LOCATION 4	
Lt. Sta. 858+97.90 to Sta. 861+47.90	250
Rt. Sta. 858+97.60 to Sta. 861+47.60	250
TOTAL = 1,900	

CODE NO.#4001595

GALVANIZED STEEL PIPE, 3 1/2"	
	UNIT L. FOOT
LOCATION 1	
Rt. Sta. 583+51.04	209
TOTAL = 209	

CODE NO.54215553

METAL END SECTIONS 18"	
	UNIT EACH
LOCATION 1	
Rt. Sta. 581+95	2
TOTAL = 2	