

68383

F.A.P. RTE. 693	SECTION •	COUNTY TAZEWELL	TOTAL SHEETS ---	SHEET NO. 12
STA.		TO STA.		
FED. ROAD DIST. NO.	ILLINOIS	FED. AID PROJECT		
* D4 CULVERT EXT. / REPAIR 2005-2				

SCHEDULE OF QUANTITIES

CODE NO.66600105

FURNISHING AND ERECTING RIGHT OF WAY MARKERS			
LOCATION 1	UNIT EACH	LOCATION 3	UNIT EACH
Sta. 582+50, 51.01' Rt	1	Sta. 733+00, 40.00' Rt	1
Sta. 583+40, 90.00' Rt	1	Sta. 734+00, 70.00' Rt	1
Sta. 583+65, 90.00' Rt	1	Sta. 735+50, 70.00' Rt	1
Sta. 584+00, 55.78' Rt	1	Sta. 735+75, 80.00' Rt	1
LOCATION 2		Sta. 736+25, 80.00' Rt	1
Sta. 720+00, 40.00' Rt	1	Sta. 736+50, 70.00' Rt	1
Sta. 720+50, 75.00' Rt	1	Sta. 738+00, 70.00' Rt	1
Sta. 723+50, 67.00' Rt	1	Sta. 739+00, 33.00' Rt	1
Sta. 723+79, 85.00' Rt	1	Sta. 734+00, 43.481' Lt	1
Sta. 724+10, 85.00' Rt	1	Sta. 735+00, 70.00' Lt	1
Sta. 724+50, 65.00' Rt	1	Sta. 735+50, 70.00' Lt	1
Sta. 725+50, 60.00' Rt	1	Sta. 735+75, 90.00' Lt	1
Sta. 726+00, 40.00' Rt	1	Sta. 736+25, 90.00' Lt	1
Sta. 720+00, 48.52' Lt	1	Sta. 736+50, 60.00' Lt	1
Sta. 721+00, 65.00' Lt	1	Sta. 738+00, 60.00' Lt	1
Sta. 723+50, 65.00' Lt	1	Sta. 738+50, 40.82' Lt	1
Sta. 723+90, 95.00' Lt	1	LOCATION 4	
Sta. 724+17, 95.00' Lt	1	Sta. 858+50, 33.00' Rt	1
Sta. 724+50, 70.00' Lt	1	Sta. 860+50, 75.00' Rt	1
Sta. 725+50, 65.00' Lt	1	Sta. 861+00, 75.00' Rt	1
Sta. 726+00, 48.20' Lt	1	Sta. 862+50, 33.00' Rt	1
		Sta. 858+50, 33.00' Lt	1
		Sta. 859+35, 79.00' Lt	1
		Sta. 859+75, 79.00' Lt	1
		Sta. 860+00, 67.00' Lt	1
		Sta. 861+50, 33.00' Lt	1
SUB-TOTAL	20	SUB-TOTAL	25
TOTAL = 45			

CODE NO.63301210

REMOVE & RE-ERECT SPBG, TYPE A	
LOCATION 1	UNIT FOOT
Lt. Sta. 582+53.65 to Sta. 583+28.65	75
Lt. Sta. 583+66.15 to Sta. 585+53.65	188
TOTAL = 263	

CODE NO.70100450

TRAFFIC CONTROL AND PROTECTION STANDARD 701201	
LOCATION 1	UNIT L.SUM
Sta. 581+00 to Sta. 587+00	0.25
LOCATION 2	
Sta. 720+00 to Sta. 726+00	0.25
LOCATION 3	
Sta. 733+00 to Sta. 739+00	0.25
LOCATION 4	
Sta. 856+50 to Sta. 862+50	0.25
TOTAL = 1.0	

CODE NO.78200410

GUARDRAIL MARKER TYPE A	
LOCATION 1	UNIT EACH
Lt. Sta. 581+78.65 to Sta. 586+29.10	4
TOTAL = 4	

CODE NO.78201000

TERMINAR MARKER - DIRECT APPLIED	
LOCATION 1	UNIT EACH
Lt. Sta. 581+78.65	1
Lt. Sta. 586+29.10	1
TOTAL = 2	

CODE NO.X0301512

GUARDRAIL AGGREGATE EROSION CONTROL	
LOCATION 1	UNIT TON
Lt. Sta. 582+53.65 to Sta. 583+28.65	10
Lt. Sta. 583+66.15 to Sta. 585+53.65	26
TOTAL = 36	

CODE NO.67000400

ENGINEER'S FIELD OFFICE, TYPE A	
LOCATION	UNIT CAL MO
JOBSITE	3
TOTAL = 3	

CODE NO.67100100

MOBILIZATION	
LOCATION	UNIT L SUM
JOBSITE	1
TOTAL = 1	

CODE NO. B2001164

TREE, CERCIS CANADENSIS (EASTERN REDBUD) 5' HEIGHT, CLUMP FORM, BALLED AND BURLAPPED	
LOCATION	UNIT EACH
JOBSITE	5
TOTAL = 5	

CODE NO. Z0013798

CONSTRUCTION LAYOUT	
LOCATION	UNIT L SUM
JOBSITE	1
TOTAL = 1	