

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
320	1351	MACON	5	3

CONTRACT NO. 70416

SUMMARY OF QUANTITIES

LOCATION OF WORK:

FAP 320  
IL. 121  
&  
WESTLAWN AVE.  
90% FED  
10% STATE

CONSTRUCTION TYPE CODE:

Y031-1F

<u>CODE NO</u>	<u>ITEM</u>	<u>UNIT</u>	<u>TOTAL QUANTITY</u>	<u>Y031-1F QUANTITY</u>
67100100	MOBILIZATION	L SUM	1.0	1.0
70102630	TRAFFIC CONTROL AND PROTECTION, STANDARD 701601	L SUM	1.0	1.0
70102635	TRAFFIC CONTROL AND PROTECTION, STANDARD 701701	L SUM	1.0	1.0
80500200	SERVICE INSTALLATION, TYPE B	EACH	1.0	1.0
80802100	WOOD POLE, 35 FT., CLASS 4	EACH	1.0	1.0
81012500	CONDUIT IN TRENCH, 1 1/2" DIA., PVC	FOOT	1,147.0	1,147.0
81021540	CONDUIT, AUGERED 1 1/2" DIA., PVC	FOOT	214.0	214.0
81100500	CONDUIT ATTACHED TO STRUCTURE, 1 1/2" DIA., GALVANIZED STEEL	FOOT	53.0	53.0
81400100	HANDHOLE	EACH	2.0	2.0
81500200	TRENCH AND BACKFILL FOR ELECTRICAL WORK	FOOT	1,147.0	1,147.0
85800100	FLASHER CONTROLLER	EACH	1.0	1.0
87301215	ELECTRIC CABLE IN CONDUIT, SIGNAL NO. 14 2C	FOOT	161.0	161.0
87301225	ELECTRIC CABLE IN CONDUIT, SIGNAL NO. 14 3C	FOOT	1,328.0	1,328.0
87301805	ELECTRIC CABLE IN CONDUIT, SERVICE, NO. 6 2 C	FOOT	5.0	5.0
X0359600	REMOVE AND REINSTALL WOOD SIGN POST	EACH	1.0	1.0
X8801100	SIGNAL HEAD ,POLYCARBONATE, LED, 1-FACE, 1-SECTION, POST MOUNTED	EACH	4.0	4.0
XX001003	SIGN AND POST	EACH	2.0	2.0
XX003925	RELOCATE SIGN PANEL	EACH	1.0	1.0
Z0048665	RAILROAD PROTECTIVE LIABILITY INSURANCE	L SUM	1.0	1.0