

SCHEDULE OF QUANTITIES

PAVEMENT MARKING REMOVAL SCHEDULE

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
811	(2250)I	CHAMPAIGN	22	9

CONTRACT NO. 70437

STATION	OFFSET	STATION	OFFSET	LENGTH	WIDTH	AREA SQ. FT.
52+64	45.8' RT	52+66	30.5' RT.	14.5'	6"	7.3
52+68	43.5' RT	52+73	27.5' RT	17.0'	6"	8.5
52+68	43.5' RT	53+27.19(AH)	44.5' RT	53.5'	6"	26.8
0+00(BK)	44.5' RT	0+46.5	49.5' RT	48.0'	6"	24.0
52+68	49.5' RT	53+27.19(AH)	50.0' RT	54.0'	6"	27.0
0+00(BK)	50.0' RT	0+45	54.5' RT	46.5'	6"	23.0
53+20	55.0' RT	53+27.19(AH)	55.0' RT	7.2'	24"	14.4
0+46.5	27.5' RT	0+46.5	49.0' RT	22.0'	6"	11.0
0+52.5	27.5' RT	0+52.5	48.8' RT	20.0'	6"	10.0
52+63.3	42.3' LT	52+70	26.5' LT	14.5'	6"	7.3
52+68	26.5' LT	52+70	39.5' LT	13.5'	6"	6.8
52+68	39.5' LT	53+27.19(AH)	38.5' LT	56.0'	6"	28.0
52+70	47.1' LT	53+27.19(AH)	45.5' LT	56.0'	6"	28.0
52+81	57.8' LT	53+27.19(AH)	49.0' LT	46.5'	24"	93.0
0+00(BK)	49.0' LT	0+05	49.0' LT	4.8'	24"	9.6
0+00(BK)	39.9' LT	0+58.3	61.0' LT	58.0'	6"	29.0
0+00(BK)	38.5' LT	0+57.5	52.5' LT	57.5'	6"	28.8
0+30.5	27.0' LT	0+31.2	65.0' LT	31.0'	6"	15.5
0+31.2	65.0' LT	0+52.0	40.5' LT	24.0'	6"	12.0
0+29.5	55.0' LT	0+39.5	45.0' LT	6.0'	12"	6.0
0+39.5	45.0' LT	0+42	44.0' LT	3.5'	12"	3.5
0+29.5	36.0' LT	0+39.5	35.5' LT	13.0'	12"	13.0
0+39.5	26.0' LT	0+46.5	43.5' LT	10.5'	12"	10.5
0+29.5	36.0' LT	0+39.5	26.5' LT	13.5'	12"	13.5
0+39.5	26.0' LT	0+50.5	40.5' LT	16.5'	12"	16.5

TOTAL = 473.00

TEMPORARY RAMP

STATION	OFFSET	STATION	OFFSET	SQ. YDS.
5+55.00	28.00' LT.	5+55.00	28.00' RT.	37.33
0+65.70	57.60' LT.	0+43.20	27.00' LT.	23.97
0+43.20	27.00' LT.	0+00.00	27.00' LT. (AH)	28.80
53+27.19	27.00' LT. (BK)	52+23.00	27.00' LT.	69.46
1+20.00	28.40' RT.	0+00.00	28.40' RT. (AH)	80.00
53+27.19	28.40' RT. (BK)	52+70.00	28.40' RT.	38.13
52+70.00	28.40' RT.	52+59.60	45.10' RT.	13.26
48+71.00	28.00' LT.	48+71.00	28.00' LT.	37.33

TOTAL = 328.28

USE = 329