

F.A.P. RITE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
116	-	**	14	6

CONTRACT NO. 7044T  
 \* D-5 CONTRACT MAINTENANCE 2005-8  
 \*\* COLES COUNTY

## SCHEDULE OF QUANTITIES

### BITUMINOUS SURFACE REMOVAL (VARIABLE DEPTH) - 4400030

STATION	LENGTH (FT)	WIDTH (FT)	AREA (SQ YD)
254+35.00 TO 279+35.00	2,500.00	26.00	7,222.22
TOTAL =			7,222.22 SQ YD
USE =			7,222.00 SQ YD

### BITUMINOUS SURFACE REMOVAL - BUTT JOINT - 40600980

STATION	LENGTH (FT)	WIDTH (FT)	AREA (SQ YD)
254+35.00 TO 254+65.00	30.00	26.00	86.67 SQ YD
279+05.00 TO 279+35.00	30.00	26.00	86.67 SQ YD
TOTAL =			173.34 SQ YD
USE =			174.00 SQ YD

### TEMPORARY RAMP - 40600990

STATION	LENGTH (FT)	WIDTH (FT)	AREA (SQ YD)
254+35.00 TO 254+40.00	5.00	26.00	14.44 SQ YD
279+30.00 TO 279+35.00	5.00	26.00	14.44 SQ YD
TOTAL =			28.88 SQ YD
USE =			30.00 SQ YD

### AGGREGATE SHOULDER, TYPE B - 48101200

STATION	LENGTH (FT)	WIDTH (FT)	TON
254+35.00 TO 279+35.00 NORTHBOUND	2,600.00	4.00	84.25 TON
254+35.00 TO 279+35.00 SOUTHBOUND	2,700.00	4.00	87.50 TON
TOTAL =			171.75 TON
USE =			175.0 TON

### SHORT TERM PAVEMENT MARKING - 70300100

YELLOW:  
 1,000.00 LIN. FT. LINE 4 INCH

---

TOTAL:  
 1,000.00 LIN. FT. LINE 4 INCH

### PAINT PAVEMENT MARKING LINE 4 INCH - 78001110

YELLOW:  
 625.00 LIN. FT. LINE 4 INCH

WHITE:  
 5,000.00 LIN. FT. LINE 4 INCH

---

TOTAL:  
 5,625.00 LIN. FT. LINE 4 INCH

### RAISED REFLECTIVE PAVEMENT MARKER REMOVAL - 78300200

LOCATION	STATION	TO	STATION	QUANTITY (EACH)
CENTERLINE	254+35.00		279+35.00	32.0
TOTAL =				32.0 EACH

### RAISED REFLECTIVE PAVEMENT MARKERS - 78100100

LOCATION	STATION	TO	STATION	QUANTITY (EACH)	TYPE
CENTERLINE	254+35.00		279+35.00	32.0	AMBER (BIDIRECTIONAL)
TOTAL =				32.0 EACH	