

F.A. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
VAR.	*	VARIOUS	25	8

* D-5 CONTRACT MAINT 2005-11
CONTRACT NO. 70450

SUMMARY OF QUANTITIES

LOCATION OF WORK: VARIOUS ROUTES
D-5 CONTRACT MAINT 2005-11
VARIOUS COUNTIES

VARIOUS COUNTIES
RURAL
100% STATE
ROUT & SEAL

VARIOUS COUNTIES
URBAN
100% STATE
ROUT & SEAL

CONSTRUCTION TYPE CODE:

F000

F000

CODE NO	ITEM	UNIT	TOTAL QUANTITY	QUANTITY	QUANTITY
45100100	CRACK ROUTING (PAVEMENT)	FOOT	549,250.0	375,114.0	174,136.0
45100200	CRACK FILLING	POUND	219,700.0	150,040.0	69,660.0
67100100	MOBILIZATION	L SUM	1.0	0.7	0.3
70100460	TRAFFIC CONTROL AND PROTECTION, STANDARD 701306	L SUM	1.0	0.7	0.3
70102620	TRAFFIC CONTROL AND PROTECTION, STANDARD 701501	L SUM	1.0	1.0	0.0
70102622	TRAFFIC CONTROL AND PROTECTION, STANDARD 701502	L SUM	1.0	0.7	0.3
70102630	TRAFFIC CONTROL AND PROTECTION, STANDARD 701601	L SUM	1.0	0.0	1.0
* 78001110	PAINT PAVEMENT MARKING - LINE 4"	FOOT	53,841.0	53,841.0	0.0
Z0048665	RAILROAD PROTECTIVE LIABILITY INSURANCE	L SUM	1.0	0.2	0.8

* SPECIALTY ITEMS