

GENERAL NOTES

G. N. -100
 ENGLISH UNITS OF MEASUREMENT SHALL GOVERN OVER AND SUPERSEDE ANY METRIC UNITS SHOWN IN THIS CONTRACT. WHERE INCLUDED, METRIC UNITS ARE FOR INFORMATION ONLY.

G. N. -442B -- PATCHING SCHEDULES
 THE PATCHING SCHEDULES INCLUDED IN THE PLANS REPRESENT THE BEST INFORMATION AVAILABLE AT THE TIME OF COMPLETION OF THE PLANS FOR LETTING. VARIATIONS IN LOCATION AND SIZES OF BOTH FULL-DEPTH AND PARTIAL-DEPTH PATCHES MAY OCCUR.

SUMMARY OF QUANTITIES

CONSTRUCTION TYPE CODE:

CODE NO	ITEM	UNIT	TOTAL QUANTITY
44200525	CLASS A PATCHES, TYPE I, 8"	SQ. YD.	64.0
44200529	CLASS A PATCHES, TYPE II, 8"	SQ. YD.	234.0
44200533	CLASS A PATCHES, TYPE III, 8"	SQ. YD.	212.0
44200535	CLASS A PATCHES, TYPE IV, 8"	SQ. YD.	552.0
44213000	PATCHING REINFORCEMENT	SQ. YD.	1,062.0
44213200	SAW CUTS	FOOT	4,613.0
67100100	MOBILIZATION	L. SUM	1.0
70100305	TRAFFIC CONTROL & PROTECTION STANDARD 701400	L. SUM	1.0
70100420	TRAFFIC CONTROL & PROTECTION STANDARD 701411	EACH	6.0
70100800	TRAFFIC CONTROL & PROTECTION STANDARD 701401	L. SUM	1.0
X7015005	CHANGEABLE MESSAGE SIGN	CAL. DAY	28.0
Z0075300	TIE BARS	EACH	482.0

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
322	*	MACON	6	3

CONTRACT NO. 70452
 • D-5 ANNUAL PATCHING 2005-1

MACON COUNTY
 URBAN MULTI-LANE
 100% STATE
 J000

TOTAL QUANTITY