

PATCHING SCHEDULE

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
322	*	MACON	6	5

CONTRACT NO. 70452
• D-5 ANNUAL PATCHING 2005-1

US-51 NORTHBOUND			TABULATION OF CLASS A PAVEMENT PATCHING									
STATION	DIRECTION	LANE	LENGTH (ft)	WIDTH (ft)	DEPTH (in)	PATCH AREA				SAW CUTS 44213200 (ft)	TIE BARS Z0075300 (Each)	PATCHING REINFORCEMENT 44213000 (sq. yd)
						TYPE I (sq. yd)	TYPE II (sq. yd)	TYPE III (sq. yd)	TYPE IV (sq. yd)			
141+20	NB	DL	4.5	12	8	0.0	6.0	0.0	0.0	57.0	0	6.0
145+88	NB	DL	6	12	8	0.0	8.0	0.0	0.0	60.0	0	8.0
194+50	NB	DL	12	12	8	0.0	0.0	16.0	0.0	72.0	0	16.0
209+50	NB	DL	30	6	8	0.0	0.0	20.0	0.0	84.0	15	20.0
214+60	NB	DL	34	6	8	0.0	0.0	22.7	0.0	92.0	17	22.7
215+50	NB	DL	25	6	8	0.0	0.0	16.7	0.0	74.0	13	16.7
215+95	NB	DL	20	6	8	0.0	13.3	0.0	0.0	64.0	10	13.3
227+70	NB	DL	12	6	8	0.0	8.0	0.0	0.0	48.0	0	8.0
229+75	NB	DL	40	12	8	0.0	0.0	0.0	53.3	128.0	20	53.3
238+95	NB	DL	100	6	8	0.0	0.0	0.0	66.7	224.0	50	66.7
279+50	NB	DL	6	12	8	0.0	8.0	0.0	0.0	60.0	0	8.0
287+20	NB	DL	6	6	8	4.0	0.0	0.0	0.0	36.0	0	4.0
297+00	NB	DL	10	12	8	0.0	13.3	0.0	0.0	68.0	0	13.3
322+95	NB	DL	10	6	8	0.0	6.7	0.0	0.0	44.0	0	6.7
324+86	NB	DL	8	6	8	0.0	5.3	0.0	0.0	40.0	0	5.3
326+80	NB	DL	60	12	8	0.0	0.0	0.0	80.0	168.0	30	80.0
338+10	NB	DL	6	6	8	4.0	0.0	0.0	0.0	36.0	0	4.0
342+10	NB	DL	12	6	8	0.0	8.0	0.0	0.0	48.0	0	8.0
358+00	NB	DL	6	6	8	4.0	0.0	0.0	0.0	36.0	0	4.0
369+65	NB	DL	6	6	8	4.0	0.0	0.0	0.0	36.0	0	4.0
369+80	NB	DL	6	6	8	4.0	0.0	0.0	0.0	36.0	0	4.0
NORTHBOUND TOTALS						20.0 (sq. yd)	76.7 (sq. yd)	75.3 (sq. yd)	200.0 (sq. yd)	1,511.0 (ft)	155.0 (Each)	372.0 (sq. yd)