

### PATCHING SCHEDULE

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
322	*	MACON	6	6

US-51 SOUTHBOUND

TABULATION OF CLASS A PAVEMENT PATCHING

CONTRACT NO. 70452  
D-5 ANNUAL PATCHING 2005-1

STATION	DIRECTION	LANE	LENGTH (ft)	WIDTH (ft)	DEPTH (in)	PATCH AREA				SAW CUTS 44213200 (ft)	TIE BARS Z0075300 (Each)	PATCHING REINFORCEMENT 44213000 (sq. yd)
						TYPE I (sq. yd)	TYPE II (sq. yd)	TYPE III (sq. yd)	TYPE IV (sq. yd)			
122+70	SB	DL	6	6	8	4.0	0.0	0.0	0.0	36.0	0	4.0
123+50	SB	DL	12	6	8	0.0	8.0	0.0	0.0	48.0	0	8.0
124+00	SB	DL	6	12	8	0.0	8.0	0.0	0.0	60.0	0	8.0
153+55	SB	DL	10	6	8	0.0	6.7	0.0	0.0	44.0	0	6.7
160+75	SB	DL	12	6	8	0.0	8.0	0.0	0.0	48.0	0	8.0
173+40	SB	DL	36	6	8	0.0	0.0	24.0	0.0	96.0	18	24.0
174+85	SB	DL	10	12	8	0.0	13.3	0.0	0.0	68.0	0	13.3
175+00	SB	DL	6	6	8	4.0	0.0	0.0	0.0	36.0	0	4.0
183+20	SB	DL	8	12	8	0.0	10.7	0.0	0.0	64.0	0	10.7
210+75	SB	DL	10	12	8	0.0	13.3	0.0	0.0	68.0	0	13.3
212+00	SB	DL	8	12	8	0.0	10.7	0.0	0.0	64.0	0	10.7
215+76	SB	DL	6	6	8	4.0	0.0	0.0	0.0	36.0	0	4.0
225+00	SB	DL	38	6	8	0.0	0.0	0.0	25.3	100.0	19	25.3
225+88	SB	DL	42	6	8	0.0	0.0	0.0	28.0	108.0	21	28.0
228+70	SB	DL	245	6	8	0.0	0.0	0.0	163.3	514.0	123	163.3
239+00	SB	DL	6	6	8	4.0	0.0	0.0	0.0	36.0	0	4.0
239+95	SB	DL	12	12	8	0.0	0.0	16.0	0.0	72.0	0	16.0
263+30	SB	DL	12	12	8	0.0	0.0	16.0	0.0	72.0	0	16.0
282+15	SB	DL	6	6	8	4.0	0.0	0.0	0.0	36.0	0	4.0
289+15	SB	DL	13	6	8	0.0	8.7	0.0	0.0	50.0	0	8.7
296+83	SB	DL	6	6	8	4.0	0.0	0.0	0.0	36.0	0	4.0
297+00	SB	DL	6	6	8	4.0	0.0	0.0	0.0	36.0	0	4.0
301+75	SB	DL	30	6	8	0.0	0.0	20.0	0.0	84.0	15	20.0
302+00	SB	DL	17	12	8	0.0	0.0	22.7	0.0	82.0	0	22.7
308+08	SB	DL	12	6	8	0.0	8.0	0.0	0.0	48.0	0	8.0
310+33	SB	DL	27	6	8	0.0	0.0	18.0	0.0	78.0	14	18.0
310+68	SB	DL	16	6	8	0.0	10.7	0.0	0.0	56.0	0	10.7
349+35	SB	DL	10	6	8	0.0	6.7	0.0	0.0	44.0	0	6.7
351+80	SB	DL	6	6	8	4.0	0.0	0.0	0.0	36.0	0	4.0
352+05	SB	DL	6	6	8	4.0	0.0	0.0	0.0	36.0	0	4.0
353+00	SB	DL	100	6	8	0.0	0.0	0.0	66.7	224.0	50	66.7
356+00	SB	DL	65	6	8	0.0	0.0	0.0	43.3	154.0	33	43.3
356+70	SB	DL	17	6	8	0.0	11.3	0.0	0.0	58.0	0	11.3
357+04	SB	DL	10	6	8	0.0	6.7	0.0	0.0	44.0	0	6.7
357+61	SB	DL	10	6	8	0.0	6.7	0.0	0.0	44.0	0	6.7
359+45	SB	DL	38	6	8	0.0	0.0	0.0	25.3	100.0	19	25.3
360+00	SB	DL	6	6	8	4.0	0.0	0.0	0.0	36.0	0	4.0
360+25	SB	DL	29	6	8	0.0	0.0	19.3	0.0	82.0	15	19.3
361+59	SB	DL	8	6	8	0.0	5.3	0.0	0.0	40.0	0	5.3
362+53	SB	DL	12	6	8	0.0	8.0	0.0	0.0	48.0	0	8.0
363+18	SB	DL	10	6	8	0.0	6.7	0.0	0.0	44.0	0	6.7
363+48	SB	DL	6	6	8	4.0	0.0	0.0	0.0	36.0	0	4.0
<b>SOUTHBOUND TOTALS</b>						44.0 (sq. yd)	157.3 (sq. yd)	136.0 (sq. yd)	352.0 (sq. yd)	3102.0 (ft)	327.0 (Each)	689.3 (sq. yd)

<b>FINAL TOTALS</b>	64.0 (sq. yd)	234.0 (sq. yd)	211.3 (sq. yd)	552.0 (sq. yd)	4613.0 (ft)	482.0 (Each)	1061.3 (sq. yd)
---------------------	------------------	-------------------	-------------------	-------------------	----------------	-----------------	--------------------