

F.A.I. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
*	**	***	17	12

SCHEDULE OF QUANTITIES

CONTRACT NO. 70454
 * 57 & 74
 ** D-5 ANNUAL PATCHING 2005-3
 *** CHAMPAIGN & VERMILION

CLASS "A" PATCHES I-57 (NORTHBOUND)

TABULATION OF CLASS A PAVEMENT PATCHING

STATION	DIRECTION	LANE	LENGTH (ft)	WIDTH (ft)	DEPTH (in)	PATCH AREA				SAW CUTS 44213200 (ft)	TIE BARS Z0075300 (Each)	PATCHING REINFORCEMENT 44213000 (sq. yd)
						TYPE I (sq. yd)	TYPE II (sq. yd)	TYPE III (sq. yd)	TYPE IV (sq. yd)			
*383+161	NB	PL	6	12	13	0.0	8.0	0.0	0.0	60.0	0	8.0
*388+837	NB	PL	8	12	13	0.0	10.7	0.0	0.0	64.0	0	10.7
*389+457	NB	PL	8	12	13	0.0	10.7	0.0	0.0	64.0	0	10.7
*389+900	NB	DL	16	12	13	0.0	0.0	21.3	0.0	80.0	0	21.3
*389+900	NB	PL	16	12	13	0.0	0.0	21.3	0.0	80.0	0	21.3
*390+446	NB	PL	10	12	13	0.0	13.3	0.0	0.0	68.0	0	13.3
1014+80	NB	DL	9	12	10	0.0	12.0	0.0	0.0	66.0	0	12.0
1015+50	NB	DL	4.5	12	8	0.0	6.0	0.0	0.0	57.0	0	6.0
1015+94	NB	DL	14	12	7	0.0	0.0	18.7	0.0	76.0	0	18.7
1016+35	NB	DL	43	12	7	0.0	0.0	0.0	57.3	134.0	22	57.3
1017+25	NB	DL	34	12	7	0.0	0.0	0.0	45.3	116.0	17	45.3
1017+50	NB	PL	15	12	7	0.0	0.0	20.0	0.0	78.0	0	20.0
1017+85	NB	DL	6	12	8	0.0	8.0	0.0	0.0	60.0	0	8.0
1021+72	NB	DL	4.5	12	10	0.0	6.0	0.0	0.0	57.0	0	6.0
1022+25	NB	DL	5	12	10	0.0	6.7	0.0	0.0	58.0	0	6.7
1022+55	NB	DL	4.5	12	10	0.0	6.0	0.0	0.0	57.0	0	6.0
1030+43	NB	DL	4.5	12	10	0.0	6.0	0.0	0.0	57.0	0	6.0
1035+40	NB	DL	17	12	10	0.0	0.0	22.7	0.0	82.0	0	22.7
1040+50	NB	DL	4.5	12	10	0.0	6.0	0.0	0.0	57.0	0	6.0
1043+45	NB	DL	4.5	12	10	0.0	6.0	0.0	0.0	57.0	0	6.0
1047+70	NB	DL	16	12	10	0.0	0.0	21.3	0.0	80.0	0	21.3
1059+05	NB	DL	16	12	10	0.0	0.0	21.3	0.0	80.0	0	21.3
1065+00	NB	DL	9	12	10	0.0	12.0	0.0	0.0	66.0	0	12.0
1069+26	NB	PL	4.5	12	10	0.0	6.0	0.0	0.0	57.0	0	6.0
1074+19	NB	DL	14	12	10	0.0	0.0	18.7	0.0	76.0	0	18.7
1076+56	NB	DL	4.5	12	10	0.0	6.0	0.0	0.0	57.0	0	6.0
1081+76	NB	DL	12	12	10	0.0	0.0	16.0	0.0	72.0	0	16.0
1088+53	NB	DL	4.5	12	10	0.0	6.0	0.0	0.0	57.0	0	6.0
1090+00	NB	DL	15	12	10	0.0	0.0	20.0	0.0	78.0	0	20.0
1112+90	NB	DL	4.5	12	10	0.0	6.0	0.0	0.0	57.0	0	6.0
1124+04	NB	DL	4.5	12	10	0.0	6.0	0.0	0.0	57.0	0	6.0
1166+60	NB	DL	6	12	10	0.0	8.0	0.0	0.0	60.0	0	8.0
1176+82	NB	DL	4.5	12	10	0.0	6.0	0.0	0.0	57.0	0	6.0
1249+38	NB	DL	4.5	12	10	0.0	6.0	0.0	0.0	57.0	0	6.0
NORTHBOUND TOTALS						0.0 (sq. yd)	167.3 (sq. yd)	201.3 (sq. yd)	102.7 (sq. yd)	2339.0 (ft)	39.0 (Each)	471.3 (sq. yd)

*METRIC STATIONING (ENGLISH QUANTITIES)