

F.A.I. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
*	**	***	17	13

CONTRACT NO. 70454
 * 57 & 74
 ** D-5 ANNUAL PATCHING 2005-3
 *** CHAMPAIGN & VERMILION

SCHEDULE OF QUANTITIES

CLASS "A" PATCHES I-57 (SOUTHBOUND)

TABULATION OF CLASS A PAVEMENT PATCHING

STATION	DIRECTION	LANE	LENGTH (ft)	WIDTH (ft)	DEPTH (in)	PATCH AREA				SAW CUTS 44213200 (ft)	TIE BARS Z0075300 (Each)	PATCHING REINFORCEMENT 44213000 (sq. yd)
						TYPE I (sq. yd)	TYPE II (sq. yd)	TYPE III (sq. yd)	TYPE IV (sq. yd)			
*382+621	SB	DL	9	12	8.0	0.0	12.0	0.0	0.0	66.0	0	12.0
*391+190	SB	DL	8	12	13.0	0.0	10.7	0.0	0.0	64.0	0	10.7
*391+190	SB	PL	22	12	12.0	0.0	0.0	0.0	29.3	92.0	11	29.3
1018+10	SB	DL	5	12	8.0	0.0	6.7	0.0	0.0	58.0	0	6.7
1108+18	SB	DL	6	12	10.0	0.0	8.0	0.0	0.0	60.0	0	8.0
1112+45	SB	DL	4.5	12	10.0	0.0	6.0	0.0	0.0	57.0	0	6.0
1156+24	SB	DL	6	12	10.0	0.0	8.0	0.0	0.0	60.0	0	8.0
1191+04	SB	DL	8	12	10.0	0.0	10.7	0.0	0.0	64.0	0	10.7
1246+03	SB	DL	12	12	10.0	0.0	0.0	16.0	0.0	72.0	0	16.0
1246+40	SB	DL	4.5	12	10.0	0.0	6.0	0.0	0.0	57.0	0	6.0
SOUTHBOUND TOTALS						0.0 (sq. yd)	68.0 (sq. yd)	16.0 (sq. yd)	29.3 (sq. yd)	650.0 (ft)	11.0 (Each)	113.3 (sq. yd)
FINAL TOTALS						0.0 (sq. yd)	235.3 (sq. yd)	217.3 (sq. yd)	132.0 (sq. yd)	2989.0 (ft)	50.0 (Each)	584.7 (sq. yd)

*METRIC STATIONING (ENGLISH QUANTITIES)