

F.A.I. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
*	**	***	17	14

SCHEDULE OF QUANTITIES

CONTRACT NO.70454
 * 57 & 74
 ** D-5 ANNUAL PATCHING 2005-3
 *** CHAMPAIGN & VERMILION

TABULATION OF CLASS B PAVEMENT PATCHING

STATION	DIRECTION	LANE	LENGTH (ft)	WIDTH (ft)	DEPTH (in)	TYPE I (sq. yd)	PATCH AREA			DOWEL BARS Z0017100 (Each)	SAW CUTS 44213200 (ft)	TIE BARS Z0075300 (Each)	PAVEMENT FABRIC 42001200 (sq. yd)
							TYPE II (sq. yd)	TYPE III (sq. yd)	TYPE IV (sq. yd)				
*382+291	I-57 NB	DL	6	12	15	0.0	8.0	0.0	0.0	20	48.0	0	0.0
*382+291	NB	RAMP	6	8	15	0.0	5.3	0.0	0.0	12	36.0	0	0.0
900+06	I-74 EB	DL	16	12	11	0.0	0.0	21.3	0.0	20	68.0	8	21.3
901+01	EB	PL	46	12	10	0.0	0.0	0.0	61.3	20	128.0	23	61.3
999+26	EB	DL	35	12	12	0.0	0.0	0.0	46.7	20	106.0	18	46.7
1001+84	EB	DL	6	12	10	0.0	8.0	0.0	0.0	20	48.0	0	0.0
1001+84	EB	PL	6	12	10	0.0	8.0	0.0	0.0	20	48.0	0	0.0
1161+69	EB	DL	13.5	12	12	0.0	0.0	18.0	0.0	20	63.0	0	18.0
1161+88	EB	DL	6	12	12	0.0	8.0	0.0	0.0	20	48.0	0	0.0
1239+51	EB	DL	10	12	12	0.0	13.3	0.0	0.0	20	56.0	0	0.0
1242+40	EB	PL	56.5	12	10.75	0.0	0.0	0.0	75.3	20	149.0	28	75.3
1319+14	EB	DL	13	12	12	0.0	0.0	17.3	0.0	20	62.0	0	17.3
1322+39	EB	DL	12	12	12	0.0	0.0	16.0	0.0	20	60.0	0	16.0
1412+00	EB	DL	6	12	12	0.0	8.0	0.0	0.0	20	48.0	0	0.0
1413+64	EB	DL	180	12	10	0.0	0.0	0.0	240.0	20	396.0	90	240.0
1413+64	EB	PL	180	12	10	0.0	0.0	0.0	240.0	20	396.0	90	240.0
901+19	WB	DL	10	12	10	0.0	13.3	0.0	0.0	20	56.0	0	0.0
902+24	WB	DL	10	12	10	0.0	13.3	0.0	0.0	20	56.0	0	0.0
903+02	WB	DL	6	12	12	0.0	8.0	0.0	0.0	20	48.0	0	0.0
1000+95	WB	DL	65	12	10	0.0	0.0	0.0	86.7	20	166.0	33	86.7
1051+00	WB	DL	6	12	15	0.0	8.0	0.0	0.0	20	48.0	0	0.0
1105+93	WB	DL	6	12	11	0.0	8.0	0.0	0.0	20	48.0	0	0.0
1105+93	WB	PL	6	12	11	0.0	8.0	0.0	0.0	20	48.0	0	0.0
1108+95	WB	DL	6	12	12	0.0	8.0	0.0	0.0	20	48.0	0	0.0
1158+70	WB	PL	6	12	11	0.0	8.0	0.0	0.0	20	48.0	0	0.0
1160+55	WB	DL	10	12	10	0.0	13.3	0.0	0.0	20	56.0	0	0.0
1161+31	WB	DL	31	12	10.75	0.0	0.0	0.0	41.3	20	98.0	16	41.3
1239+92	WB	DL	6	12	11	0.0	8.0	0.0	0.0	20	48.0	0	0.0
1241+49	WB	DL	6	12	10	0.0	8.0	0.0	0.0	20	48.0	0	0.0
1242+44	WB	DL	6	12	11	0.0	8.0	0.0	0.0	20	48.0	0	0.0
1242+44	WB	PL	6	12	11	0.0	8.0	0.0	0.0	20	48.0	0	0.0
1319+88	WB	DL	8	12	10	0.0	10.7	0.0	0.0	20	52.0	0	0.0
1413+64	WB	DL	194	12	10	0.0	0.0	0.0	258.7	20	424.0	97	258.7
1413+64	WB	PL	194	12	10	0.0	0.0	0.0	258.7	20	424.0	97	258.7
FINAL TOTALS						0.0 (sq. yd)	189.3 (sq. yd)	72.7 (sq. yd)	1308.7 (sq. yd)	672.0 (Each)	3572.0 (ft)	500.0 (Each)	1381.3 (sq. yd)

* METRIC STATIONING (ENGLISH QUANTITIES)