

### SUMMARY OF QUANTITIES

F.A.I. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
57	*	**	6	4

CONTRACT NO. 70456  
\* D-5 ANNUAL PATCHING 2005-5  
\*\* COLES AND DOUGLAS

COLES COUNTY STATION 1386+01 TO STATION 1386+91 RURAL 100% STATE J000	DOUGLAS COUNTY STATION 1386+91 TO STATION 1387+81 RURAL 100% STATE J000
--	--

CONSTRUCTION TYPE CODE:

CODE NO	ITEM	UNIT	TOTAL QUANTITY	COLES COUNTY	DOUGLAS COUNTY
44200523	CLASS A PATCHES, TYPE IV, 7"	SQ. YD.	960.0	480.0	480.0
44213000	PATCHING REINFORCEMENT	SQ. YD.	960.0	480.0	480.0
44213200	SAW CUTS	FOOT	1,632.0	816.0	816.0
67100100	MOBILIZATION	L. SUM	1.0	0.5	0.5
70100207	TRAFFIC CONTROL & PROTECTION STANDARD 701402	EACH	4.0	2.0	2.0
70100305	TRAFFIC CONTROL & PROTECTION STANDARD 701400	L. SUM	1.0	0.5	0.5
70400100	TEMPORARY CONCRETE BARRIER	FOOT	576.0	288.0	288.0
70400200	RELOCATE TEMPORARY CONCRETE BARRIER	FOOT	576.0	288.0	288.0
*78001110	PAINT PAVEMENT MARKING - LINE 4"	FOOT	810.0	405.0	405.0
X7015005	CHANGEABLE MESSAGE SIGN	CAL. DAY	28.0	14.0	14.0
△ Z0030250	IMPACT ATTENUATOR TEMPORARY, NON-REDIRECTIVE, TEST LEVEL 3	EACH	2.0	1.0	1.0
△ Z0030350	IMPACT ATTENUATOR RELOCATE, NON-REDIRECTIVE, TEST LEVEL 3	EACH	2.0	1.0	1.0
Z0075300	TIE BARS	EACH	360.0	180.0	180.0

\* SPECIALITY ITEMS

△ SFTY-3N