

SUMMARY OF QUANTITIES

URBAN  
80% FED.  
20% STATE  
1000

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
71	(3R)RS-5	SANGAMON	25	3
STA.		TO STA.		
FED. ROAD DIST. NO.	ILLINOIS	FED. AID PROJECT		
<b>CONTRACT NO. 72614</b>				

CODE NO.	ITEM	UNIT	TOTAL QUANTITY	MAINLINE ROADWAY
< COL2 >	< COL3 >	< COL4 >	< COL5 >	< COL6 >
20200200	EARTH EXCAVATION	CU YD	243	243
20200500	EARTH EXCAVATION (WIDENING)	CU YD	2014.8	2014.8
* 25000200	SEEDING, CLASS 2	ACRE	0.46	0.46
* 25000400	NITROGEN FERTILIZER NUTRIENT	POUND	42	42
* 25000500	PHOSPHORUS FERTILIZER NUTRIENT	POUND	42	42
* 25000600	POTASSIUM FERTILIZER NUTRIENT	POUND	42	42
* 25100115	MULCH, METHOD 2	ACRE	0.46	0.46
* 25100630	EROSION CONTROL BLANKET	SQ YD	2210	2210
28000200	EARTH EXCAVATION FOR EROSION CONTROL	CU YD	1.2	1.2
28000250	TEMPORARY EROSION CONTROL SEEDING	POUND	46	46
28000300	TEMPORARY DITCH CHECKS	EACH	3	3
35800100	PREPARATION OF BASE	SQ YD	2664.9	2664.9
40200800	AGGREGATE SURFACE COURSE, TYPE B	TON	26.6	26.6
40600200	BITUMINOUS MATERIALS (PRIME COAT)	TON	34.1	34.1
40600300	AGGREGATE (PRIME COAT)	TON	277.2	277.2
40600895	CONSTRUCTING TEST STRIP	EACH	1	1
40600980	BITUMINOUS SURFACE REMOVAL - BUTT JOINT	SQ YD	1978.8	1978.8
40600985	PORTLAND CEMENT CONCRETE SURFACE REMOVAL - BUTT JOINT	SQ YD	218.9	218.9
40600990	TEMPORARY RAMP	SQ YD	805.2	805.2
40800020	BITUMINOUS MATERIALS (PRIME COAT)	TON	0.61	0.61
40800030	AGGREGATE (PRIME COAT)	TON	2.99	2.99
44000006	BITUMINOUS SURFACE REMOVAL 1 1/2"	SQ YD	2864	2864
44000030	BITUMINOUS SURFACE REMOVAL (VARIABLE DEPTH)	SQ YD	65705.9	65705.9
44000100	PAVEMENT REMOVAL	SQ YD	172	172
44200168	PAVEMENT PATCHING, TYPE II, 14 INCH	SQ YD	2000	2000
44200172	PAVEMENT PATCHING, TYPE III, 14 INCH	SQ YD	250	250
44200174	PAVEMENT PATCHING, TYPE IV, 14 INCH	SQ YD	250	250
48101200	AGGREGATE SHOULDERS, TYPE B	TON	1686.6	1686.6
48202400	BITUMINOUS SHOULDERS SUPERPAVE 6"	SQ YD	125	125
50105220	PIPE CULVERT REMOVAL	FOOT	44	44
54200220	PIPE CULVERTS, CLASS D, TYPE 1 15"	FOOT	190	190
54213450	END SECTIONS 15"	EACH	6	6
60500060	REMOVING INLETS	EACH	8	8
67000400	ENGINEER'S FIELD OFFICE, TYPE A	CAL MO	5	5
67100100	MOBILIZATION	L SUM	1	1
70100450	TRAFFIC CONTROL AND PROTECTION, STANDARD 701201	L SUM	1	1
70100460	TRAFFIC CONTROL AND PROTECTION, STANDARD 701306	L SUM	1	1
70100500	TRAFFIC CONTROL AND PROTECTION, STANDARD 701326	L SUM	1	1
70103815	TRAFFIC CONTROL SURVEILLANCE	CAL DA	5	5
70300100	SHORT-TERM PAVEMENT MARKING	FOOT	8292	8292
70300230	TEMPORARY PAVEMENT MARKING - LINE 5"	FOOT	68505	68505
70300260	TEMPORARY PAVEMENT MARKING - LINE 12"	FOOT	255	255
70301000	WORK ZONE PAVEMENT MARKING REMOVAL	SQ FT	29720	29720
* 72000100	SIGN PANEL - TYPE 1	SQ FT	7.5	7.5
* 72500100	OBJECT MARKER - TYPE 1	EACH	2	2
* 73000100	WOOD SIGN SUPPORT	FOOT	36	36
* 78001120	PAINT PAVEMENT MARKING - LINE 5"	FOOT	43745	43745
78003100	PREFORMED PLASTIC PAVEMENT MARKING, TYPE B - LETTERS AND SYMBOLS	SQ FT	15.6	15.6
78003120	PREFORMED PLASTIC PAVEMENT MARKING, TYPE B - LINE 5"	FOOT	2070	2070
78003150	PREFORMED PLASTIC PAVEMENT MARKING, TYPE B - LINE 12"	FOOT	255	255
* 78008220	POLYUREA PAVEMENT MARKING TYPE I - LINE 5"	FOOT	22650	22650
* 78008230	POLYUREA PAVEMENT MARKING TYPE I - LINE 6"	FOOT	40	40
* 78100100	RAISED REFLECTIVE PAVEMENT MARKER	EACH	378	378
78300200	RAISED REFLECTIVE PAVEMENT MARKER REMOVAL	EACH	378	378

\*SPECIALTY ITEMS

REVISIONS	
NAME	DATE
GUARDRAIL/TMJ	02-07-05

ILLINOIS DEPARTMENT OF TRANSPORTATION  
**SUMMARY OF QUANTITIES**  
 SHEET 1 OF 2  
 FAP 71 (IL 54)  
 SECTION (3R)J-1  
 SANGAMON COUNTY  
 SCALE: VERT.  
 HORIZ.  
 DATE 02-07-05  
 DRAWN BY TMJ  
 CHECKED BY MEB

ca:\projects\ed52901\jdg-fina.l12-20-04\020705summqty.dgn  
 2/10/2005  
 \*REF01