

ITEM NO. 44000100 PAVEMENT REMOVAL

LOCATION	SQ. YD.
SCHNEIDER (RT. STA. 223+50)	172
TOTAL = 172	

ITEM NO. 44200168 PAVEMENT PATCHING, TYPE II, 14 INCH
2000 SQ. YD. (QTY. PROVIDED BY THE DISTRICT)

ITEM NO. 44200172 PAVEMENT PATCHING, TYPE III, 14 INCH
250 SQ. YD. (QTY. PROVIDED BY THE DISTRICT)

ITEM NO. 44200174 PAVEMENT PATCHING, TYPE IV, 14 INCH
250 SQ. YD. (QTY. PROVIDED BY THE DISTRICT)

ITEM NO. 48101200 AGGREGATE SHOULDERS, TYPE B

LOCATION	TON
STA. 64+69.41 TO STA. 105+83.21 (N.B.)	273.3
STA. 66+90.50 TO STA. 68+00.00 (S.B.)	7.3
STA. 68+00.00 TO STA. 117+68.70 (S.B.)	299.4
STA. 105+83.21 TO STA. 111+32.58 (N.B.)	18.2
STA. 111+32.58 TO STA. 117+07.41 (N.B.)	19.1
STA. 117+68.70 TO STA. 118+28.70 (S.B.)	4.0
EQUATION	
STA. 98+15.41 TO STA. 179+97.59	503.1
BRIDGE OMISSION	
STA. 189+09.27 TO STA. 265+05.65	468.4
EQUATION	
STA. 40+88.70 TO STA. 55+00.00	93.8
TOTAL = 1686.6	

ITEM NO. 48202400 BITUMINOUS SHOULDERS SUPERPAVE 6"

LOCATION	SQ YD
INTERSECTION OF IL 54 & S. ALLEN DR. (STA. 225+21.85)	125
TOTAL = 125	

ITEM NO. 50105220 PIPE CULVERT REMOVAL

LOCATION	TYPE	FOOT
RT. STA. 220+73	15" CMP	44
TOTAL = 44		

ITEM NO. 542D0220 PIPE CULVERTS, CLASS D, TYPE 1 15"

LOCATION	FOOT
31' RT. STA. 220+73	50
36' RT. STA. 222+29	50
38' RT. STA. 225+00	90
TOTAL = 190	

ITEM NO. 54213450 END SECTIONS 15"

LOCATION	EACH
31' RT. STA. 220+73	2
36' RT. STA. 222+29	2
38' RT. STA. 225+00	2
TOTAL = 6	

ITEM NO. 60500060 REMOVING INLETS

LOCATION (ALL LOCATED IN THE SHOULDER)	EACH
RT. STA. 157+52	1
LT. STA. 158+15	1
RT. STA. 160+15	1
LT. STA. 161+18	1
RT. STA. 163+16	1
LT. STA. 164+34	1
RT. STA. 166+16	1
LT. STA. 167+39	1
TOTAL = 8	

ITEM NO. 67000400 ENGINEER'S FIELD OFFICE, TYPE A
5 CAL. MO.

ITEM NO. 67100100 MOBILIZATION
1 LUMP SUM

ITEM NO. 70100450 TRAFFIC CONTROL AND PROTECTION, STANDARD 701201
1 LUMP SUM

ITEM NO. 70100460 TRAFFIC CONTROL AND PROTECTION, STANDARD 701306
1 LUMP SUM

ITEM NO. 70100500 TRAFFIC CONTROL AND PROTECTION, STANDARD 701326
1 LUMP SUM

ITEM NO. 70103815 TRAFFIC CONTROL SURVEILLANCE
5 CAL. DA.

REVISIONS	
NAME	DATE
GUARDRAIL/TMJ	02-08-05

ILLINOIS DEPARTMENT OF TRANSPORTATION
SCHEDULE OF QUANTITIES

SCALE: VERT. DRAWN BY TMJ
 HORIZ. CHECKED BY MEB
 DATE 02-08-05

c:\projects\ed52901\jda_fm\12-20-04_schedules.dgn
 2/10/2005
 *REF01