

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
*	**	BROWN	89	3
STA.		TO STA.		
FED. ROAD DIST. NO.	ILLINOIS	FED. AID PROJECT		
* D6 WETLAND MITIGATION NO. 1				
** LA GRANGE WETLAND BANK				

SUMMARY OF QUANTITIES		UNITS	TOTAL QUANTITY	CONSTR. CODE
PAY CODE NUMBER	PAY ITEM DESCRIPTION		Y077 100% STATE	
X2010510	CLEARING AND GRUBBING	L SUM	1	1
20200100	EARTH EXCAVATION	CU YD	46039	46039
25000350	SEEDING, CLASS 7	ACRE	9.7	9.7
28000250	TEMPORARY EROSION CONTROL SEEDING	POUND	2700	2700
50105200	REMOVE EXISTING CULVERTS	EACH	1	1
54200643	PIPE CULVERTS, TYPE 1, CORRUGATED STEEL OR ALUMINUM CULVERT PIPE 18"	FOOT	152	152
54201483	PIPE CULVERTS, TYPE 2, CORRUGATED STEEL OR ALUMINUM CULVERT PIPE 18"	FOOT	216	216
54215553	METAL END SECTIONS 18"	EACH	16	16
61100500	EXPLORATION TRENCH 52" DEPTH	FOOT	17400	17400
63500105	DELINEATORS	EACH	8	8
67100100	MOBILIZATION	L SUM	1	1
67000400	ENGINEER'S FIELD OFFICE, TYPE A	CAL MO	6	6
70101830	TRAFFIC CONTROL AND PROTECTION, STANDARD BLR 21	L SUM	1	1
X0301280	PLUG EXISTING DRAINS	EACH	72	72
X6110075	FIELD TILE DEACTIVATION AND REMOVAL	FOOT	3600	3600

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION

SUMMARY OF QUANTITIES

SCALE: VERT. DATE
HORIZ. DATE

DRAWN BY BDK
CHECKED BY JCN

PLOT DATE = 2/19/2008
FILE NAME = c:\p\2008\15\1864337.dgn
PLOT SCALE = 1/8"=1'-0"
REFERENCE = SHEET

Rev.