

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
662		SANGAMON	18	7
STA.		TO STA.		
FED. ROAD DIST. NO.	ILLINOIS	FED. AID PROJECT		
• D6 MEDIAN REPAIR 2005				

LOCATION NO. 3 (IL 54 @ SANGAMON AVE.)

PAY CODE #	ITEM	UNITS	Median A	Median B	Island C	TOTAL
44000500	COMBINATION CURB & GUTTER REMOVAL	FOOT	268	54	133	455
44002020	CONCRETE MEDIAN SURFACE REMOVAL	SQ. FT	1521	229	995	2745
60603600	COMBINATION CONCRETE CURB & GUTTER, TY M-6.06	FOOT			133	133
60618300	CONCRETE MEDIAN SURFACE, 4 INCH	SQ. FT			995	995
60622400	CONCRETE MEDIAN, TYPE SM-6.06	SQ. FT	1834	264		2098
60625900	PC. C. RAMPED MEDIAN TERMINAL	EACH		1		1

LOCATION NO. 4 (IL 29 IN ROCHESTER)

PAY CODE #	ITEM	UNITS	QUANTITY
20201500	SUB-BASE GRANULAR MATERIAL, TY B	TON	10
42000400	PCC PAVEMENT, 9"	SQ. YD	25
60260300	INLETS TO BE ADJUSTED WITH NEW TYPE 1 FRAME, OPEN LID	EACH	1
44000500	COMBINATION CURB & GUTTER REMOVAL	FOOT	1593
44002020	CONCRETE MEDIAN SURFACE REMOVAL	SQ. FT.	2079
60605900	COMBINATION CONCRETE CURB AND GUTTER, TY B-9.12	FOOT	906
60620800	CONCRETE MEDIAN, TYPE SB-9.12	SQ. FT	2495
60625900	PC. C. RAMPED MEDIAN TERMINAL	EACH	4

PLOT DATE = 2/10/2005  
 FILE NAME = C:\A\1105050905\attached\plan.dgn  
 PLOT SCALE = 1/8"=1'-0"  
 REFERENCE = #REF#

REVISIONS	
NAME	DATE

*Rev.*

ILLINOIS DEPARTMENT OF TRANSPORTATION

**SCHEDULE OF QUANTITIES**

SCALE: VERT. \_\_\_\_\_  
 HORIZ. \_\_\_\_\_  
 DATE \_\_\_\_\_

DRAWN BY BDK  
 CHECKED BY \_\_\_\_\_