

SUMMARY OF QUANTITIES

FAP ROUTE	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
785	132-31, 133RS-5	MADISON	29	5
STA.		TO STA.		
CONTRACT NO.: 76796				

SUMMARY OF QUANTITIES			LOCATION 1 IL 111 @ FOSTERBURG RD URBAN		LOCATION 2 IL 140 @ PRAIRIE ST URBAN		
CODE NO	ITEM	UNIT	TOTAL QUANTITIES	J000-2A 90% FEDERAL, 10% STATE	Y031-1F 90% FEDERAL, 5% STATE 5% CITY	J000-2A 90% FEDERAL, 10% STATE	Y031-1F 90% FEDERAL, 10% STATE
81012600	CONDUIT IN TRENCH, 2" DIA., PVC	FOOT	40		40		
81400100	HANDHOLE	EACH	1	1			
81500200	TRENCH AND BACKFILL FOR ELECTRICAL WORK	FOOT	46		46		
87301215	ELECTRIC CABLE IN CONDUIT, SIGNAL NO. 14 2C	FOOT	233		233		
87301245	ELECTRIC CABLE IN CONDUIT, SIGNAL NO. 14 5C	FOOT	256		256		
87301255	ELECTRIC CABLE IN CONDUIT, SIGNAL NO. 14 7C	FOOT	152		152		
87301305	ELECTRIC CABLE IN CONDUIT, LEAD-IN, NO. 14 1 PAIR	FOOT	189		189		
87502680	TRAFFIC SIGNAL POST, ALUMINUM 14 FT.	EACH	1		1		
87700320	STEEL MAST ARM ASSEMBLY AND POLE, 55 FT.	EACH	1		1		
87800100	CONCRETE FOUNDATION, TYPE A	FOOT	3		3		
87800415	CONCRETE FOUNDATION, TYPE E 36-INCH DIAMETER	FOOT	15		15		
87900100	DRILL EXISTING FOUNDATION	EACH	1		1		
88200100	TRAFFIC SIGNAL BACKPLATE	EACH	2		2		
* 88600100	DETECTOR LOOP, TYPE I	FOOT	1080		348		732
89502300	REMOVE ELECTRIC CABLE FROM CONDUIT	FOOT	1188		1188		
89502350	REMOVE AND REINSTALL ELECTRIC CABLE FROM CONDUIT	FOOT	158		158		
89502375	REMOVE EXISTING TRAFFIC SIGNAL EQUIPMENT	EACH	1		1		
89502385	REMOVE EXISTING CONCRETE FOUNDATION	EACH	5		5		
X4066548	POLYMERIZED BITUMINOUS CONCRETE SURFACE COURSE, SUPERPAVE, MIX "F", N90	TON	255	92		163	
X4066775	LEVELING BINDER (MACHINE METHOD), SUPERPAVE N90	TON	109			109	
X4069105	BITUMINOUS CONCRETE BINDER COURSE, SUPERPAVE, IL-19.0, N90 9"	SO YD	146	146			
X4402810	ISLAND SURFACE REMOVAL AND REPLACEMENT	SO FT	581		581		
* X8801300	SIGNAL HEAD ,POLYCARBONATE, LED, 1-FACE, 3-SECTION, BRACKET MOUNTED	EACH	2		2		
X8801310	SIGNAL HEAD ,POLYCARBONATE, LED, 1-FACE, 3-SECTION, MAST ARM MOUNTED	EACH	1		1		
X8801400	SIGNAL HEAD ,POLYCARBONATE, LED, 1-FACE, 5-SECTION, MAST ARM MOUNTED	EACH	1		1		

* SPECIALTY ITEMS

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION
SUMMARY OF QUANTITIES
 FAP ROUTE 785
 SECTION 132-31, 133RS-5
 MADISON COUNTY
 DRAWN BY:

2/7/2005 Wednesday February 09, 2005 @ 3:32:00 PM
 c:\projects\ad5784\ad5784\ad5784.dgn LV11-03