

FAP ROUTE	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
785	132-31, 133RS-5	MADISON	29	7
STA. TO STA.				
CONTRACT NO.: 76796				

**EARTHWORK SCHEDULE**

LOCATION			EARTH EXCAVATION (WIDENING)	EARTH EXCAVATION (WIDENING) ADJUSTED FOR SHRINKAGE	EARTH EXCAVATION	EARTH EXCAVATION ADJUSTED FOR SHRINKAGE	EMBANKMENT	EARTHWORK BALANCE WASTE (+) OR SHORTAGE (-)
STA	TO	STA						
LOCATION 1								
IL 111/140			CUBIC YARD	CUBIC YARD	CUBIC YARD	CUBIC YARD	CUBIC YARD	CUBIC YARD
94+00	TO	94+25	0.51	0.38	1.69	1.27	1.44	0.22
94+25	TO	94+50	1.21	0.90	3.09	2.32	4.12	-0.90
94+50	TO	94+75	1.55	1.16	2.78	2.09	6.15	-2.90
94+75	TO	95+00	2.02	1.52	3.12	2.34	8.41	-4.55
95+00	TO	95+25	2.16	1.62	2.66	1.99	10.99	-7.38
95+25	TO	95+50	2.01	1.51	1.25	0.94	12.66	-10.21
95+50	TO	95+75	2.05	1.53	0.32	0.24	13.80	-12.02
95+75	TO	96+00	2.09	1.56	0.00	0.00	16.61	-15.05
96+00	TO	96+25	2.59	1.95	0.00	0.00	19.40	-17.46
96+25	TO	96+50	3.03	2.27	0.00	0.00	49.35	-47.09
96+50	TO	96+75	3.09	2.32	0.00	0.00	76.67	-74.35
96+75	TO	97+00	3.06	2.29	0.07	0.05	48.46	-46.12
97+00	TO	97+25	2.69	2.01	0.80	0.60	21.46	-18.84
97+25	TO	97+50	2.30	1.73	12.21	9.16	16.57	-5.68
97+50	TO	97+75	2.08	1.56	28.11	21.08	13.39	9.25
97+75	TO	98+00	2.19	1.64	26.50	19.87	15.36	6.16
98+00	TO	98+25	2.61	1.95	10.15	7.61	26.74	-17.17
98+25	TO	98+50	2.88	2.16	0.55	0.41	37.15	-34.57
98+50	TO	98+75	2.67	2.00	0.27	0.20	38.43	-36.23
98+75	TO	99+00	2.29	1.72	0.04	0.03	41.84	-40.09
99+00	TO	99+25	2.65	1.98	0.06	0.05	42.84	-40.82
99+25	TO	99+50	2.73	2.05	0.49	0.36	36.89	-34.47
99+50	TO	99+75	3.45	2.59	7.09	5.32	17.05	-9.14
99+75	TO	100+00	5.38	4.04	7.43	5.57	0.94	8.67
100+00	TO	100+25	3.10	2.32	0.77	0.57	0.00	2.90
FOSTERBURG ROAD								
18+75	TO	19+00	1.48	1.11	0.00	0.00	0.00	1.11
192+00	TO	19+25	3.12	2.34	0.00	0.00	0.00	2.34
TOTAL			66.98	50.23	109.46	82.09	576.71	-444.38

LOCATION	PIPE UNDERDRAINS, 4"	PIPE UNDERDRAINS (SPECIAL)	CONCRETE HEADWALL FOR PIPE DRAINS
STA TO STA	FOOT	FOOT	EACH
LOCATION 1			
IL 111/140			
94+14. TO 98+00.	389	20	1
98+00. TO 99+41.	142		
TOTAL	531	20	1

LOCATION	OFFSET	TREE REMOVAL (6 TO 15 UNITS DIAMETER)
STATION	FOOT	UNIT
LOCATION 1		
IL 111/140		
96+98.3	101.5 (LT)	6
97+05.1	107.6 (LT)	13
TOTAL		19

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION  
**MISCELLANEOUS SCHEDULES**  
**LOCATIONS 1 & 2**

FAP ROUTE 785  
SECTION 132-31, 133RS-5  
MADISON COUNTY

DRAWN BY:

PLOT DATE: Tuesday February 08, 2005 @ 11:24:40 AM

PLAN	DATE
BY	
DATE	
BY	
DATE	
BY	
DATE	
BY	
DATE	