



Illinois Department of Transportation

2300 South Dirksen Parkway / Springfield, Illinois / 62764

April 14, 2005

SUBJECT: FAU Route 2661
Hunt Club Road
Project BRM-7003(873)
Section 00-00095-11-BR
Lake County
Contract No 83789
Item 71 A
April 29, 2005 Letting

TO PROSPECTIVE BIDDERS:

To clarify information it is necessary to revise the following:

Proposal- Revised page 36 of the special provisions. Revised pages 1-6 of the Schedule of Prices.

Plans- Revised Summary of quantities to reflect removal of pay item on sheet 3.

Prime contractors must utilize the enclosed material when preparing their bid and must include any Schedule of Prices changes in their bidding proposal. Bidders using computer-generated bids are cautioned to reflect any and all Schedule of Prices changes, if involved, into their computer programs.

Since the proposal sheets are printed back to back, bidders are cautioned to exercise care when inserting revised and/or added special provisions into their proposals.

Please call 217-782-7806 if any of the above-described material is not included in this transmittal.

Very truly yours,

Michael L. Hine
Engineer of Design
and Environment

A handwritten signature in black ink, appearing to read 'Ted B. Walschleger' followed by 'P.E.' in a smaller font.

By: Ted B. Walschleger, P. E.
Engineer of Project Management

deducted from any compensation due, or which may become due the Contractor under this contract.

-- The price for this item is established by LCDOT, based on the Engineer's Estimate and the following formula.

Contract Pay Item	Per Cent of Bid Item
Temporary Ditch Checks (Special)	20%
Perimeter Erosion Barrier	100%
Inlet Protection (Special)	60%
Seeding, Sodding or Sodding (complete) *	20%

* if more than one of these items is included in the pay items then the sum is used.

MAINTENANCE OF TEMPORARY EROSION CONTROL SYSTEMS will be paid for on a force account basis per article 109.04.

AGGREGATE FOR TEMPORARY ACCESS

The Contractor shall maintain ingress and egress to all abutting properties during construction operations. Temporary driveways and temporary roads shall be constructed of aggregate to the dimensions determined by the Engineer.

This work shall be done in accordance with Article 301.04 and Article 1004.04 of the "Standard Specifications" with the exception that the materials shall be limited to crushed gravel, crushed stone or crushed concrete. The plasticity index requirements and the requirements for adding water at the central mixing plant will be waived.

After the temporary driveways and temporary roads have served their purpose, the suitable aggregate shall be removed, and, at the direction and approval of the Engineer, utilized for other purposes, such as embankment construction or other driveway aprons.

This work will be paid for at the contract unit price per ton for AGGREGATE FOR TEMPORARY ACCESS, which price shall be payment in full for furnishing, transporting, placing, maintaining and removing, reusing or disposing of the aggregate, as herein specified and as directed by the Engineer.

STATE JOB # - C-91-169-00
 PPS NBR - 1-10088-0000

COUNTY NAME	CODE	DIST	SECTION NUMBER	PROJECT NUMBER	ROUTE
LAKE	097	01	00-00095-11-BR	BRM-7003/873/000	FAU 2661

ITEM NUMBER	PAY ITEM DESCRIPTION	UNIT OF MEASURE	QUANTITY	UNIT PRICE		TOTAL PRICE	
				DOLLARS	CENTS	DOLLARS	CTS
A2004216	T-FRAX PENN SUM 2	EACH	3.000 X	=		=	
A2006716	T-QUERCUS MACR 2	EACH	3.000 X	=		=	
XX001302	ENERGY DISSIPATOR SPL	EACH	4.000 X	=		=	
XX006128	TRAF BAR TRM TI SP	EACH	4.000 X	=		=	
X4066426	BC SC SUPER "D" N70	TON	174.000 X	=		=	
X4066616	BCBC SUP IL-19.0 N70	TON	741.000 X	=		=	
X4066770	LEV BIND MM SUPER N70	TON	20.000 X	=		=	
X6700405	ENGR FLD OFF A MOD	CAL MO	8.000 X	=		=	
X7015050	PORT CHANGE MESS SIGN	CAL MO	8.000 X	=		=	
Z0000990	AGG FOR TEMP ACCESS	TON	7.000 X	=		=	
Z0002600	BAR SPLICERS	EACH	333.000 X	=		=	
Z0013798	CONSTRUCTION LAYOUT	L SUM	1.000 X	=		=	
20100110	TREE REMOV 6-15	UNIT	38.000 X	=		=	
20100210	TREE REMOV OVER 15	UNIT	58.000 X	=		=	
20200100	EARTH EXCAVATION	CU YD	268.000 X	=		=	

*

* Removed Pay Item
 Revised 4/14/05

FAU 2661
 00-00095-11-BR
 LAKE

ILLINOIS DEPARTMENT OF TRANSPORTATION
 SCHEDULE OF PRICES
 CONTRACT NUMBER - 83789

ECMS002 DTGECM03 ECMR003 PAGE 2
 RUN DATE - 04/14/05
 RUN TIME - 183426

ITEM NUMBER	PAY ITEM DESCRIPTION	UNIT OF MEASURE	QUANTITY	UNIT PRICE		TOTAL PRICE	
				DOLLARS	CENTS	DOLLARS	CTS
20201200	REM & DISP UNS MATL	CU YD	223.000 X	-	-	-	-
20300100	CHANNEL EXCAV	CU YD	898.000 X	-	-	-	-
20400800	FURNISHED EXCAV	CU YD	431.000 X	-	-	-	-
20700220	POROUS GRAN EMBANK	CU YD	189.000 X	-	-	-	-
21101615	TOPSOIL F & P 4	SQ YD	1,829.000 X	-	-	-	-
25000210	SEEDING CL 2A	ACRE	0.070 X	-	-	-	-
25000300	SEEDING CL 3	ACRE	0.270 X	-	-	-	-
25000400	NITROGEN FERT NUTR	POUND	34.000 X	-	-	-	-
25000500	PHOSPHORUS FERT NUTR	POUND	34.000 X	-	-	-	-
25000600	POTASSIUM FERT NUTR	POUND	34.000 X	-	-	-	-
25100120	MULCH METHOD 2	TON	0.140 X	-	-	-	-
25100640	EROSION CONTR FABRIC	SQ YD	1,262.000 X	-	-	-	-
25200200	SUPPLE WATERING	UNIT	11.000 X	-	-	-	-
28000300	TEMP DITCH CHECKS	EACH	5.000 X	-	-	-	-
28000400	PERIMETER EROS BAR	FOOT	1,142.000 X	-	-	-	-

Revised
 4-14-05

FAU 2661
 00-00095-11-BR
 LAKE

ILLINOIS DEPARTMENT OF TRANSPORTATION
 SCHEDULE OF PRICES
 CONTRACT NUMBER - 83789

ECMS002 DTGECM03 ECMR003 PAGE 3
 RUN DATE - 04/14/05
 RUN TIME - 183426

ITEM NUMBER	PAY ITEM DESCRIPTION	UNIT OF MEASURE	QUANTITY	UNIT PRICE		TOTAL PRICE	
				DOLLARS	CENTS	DOLLARS	CTS
28100107	STONE RIPRAP CL A4	SQ YD	506.000 X	=		=	
28200100	FILTER FAB FOR RIPRAP	SQ YD	527.000 X	=		=	
28400100	GABIONS	CU YD	21.000 X	=		=	
40600100	BIT MATLS PR CT	GALLON	1,640.000 X	=		=	
42001165	BR APPR PAVT	SQ YD	302.000 X	=		=	
44000006	BIT SURF REM 1 1/2	SQ YD	413.000 X	=		=	
44201761	CL D PATCH T1 10	SQ YD	3.000 X	=		=	
44201765	CL D PATCH T2 10	SQ YD	4.000 X	=		=	
44201769	CL D PATCH T3 10	SQ YD	10.000 X	=		=	
44201771	CL D PATCH T4 10	SQ YD	7.000 X	=		=	
44300100	AREA REF CR CON TREAT	SQ YD	558.000 X	=		=	
48100100	AGGREGATE SHLDS A	TON	55.000 X	=		=	
48200400	BIT SHOULDERS 6	SQ YD	799.000 X	=		=	
50100100	REM EXIST STRUCT	EACH	1.000 X	=		=	
50200100	STRUCTURE EXCAVATION	CU YD	225.000 X	=		=	

Revised
 4-14-05

FAU 2661
 00-00095-11-BR
 LAKE

ILLINOIS DEPARTMENT OF TRANSPORTATION
 SCHEDULE OF PRICES
 CONTRACT NUMBER - 83789

ECMS002 DTGECM03 ECMR003 PAGE 4
 RUN DATE - 04/14/05
 RUN TIME - 183426

ITEM NUMBER	PAY ITEM DESCRIPTION	UNIT OF MEASURE	QUANTITY	UNIT PRICE		TOTAL PRICE	
				DOLLARS	CENTS	DOLLARS	CTS
50300225	CONC STRUCT	CU YD	36.000 X				
50300255	CONC SUP-STR	CU YD	113.000 X				
50300260	BR DECK GROOVING	SQ YD	325.000 X				
50300275	CONCRETE HANDRAIL	CU YD	16.000 X				
50300300	PROTECTIVE COAT	SQ YD	419.000 X				
50500105	F & E STRUCT STEEL	L SUM	1.000 X				
50500505	STUD SHEAR CONNECTORS	EACH	1,134.000 X				
50800205	REINF BARS, EPOXY CTD	POUND	28,690.000 X				
51201600	FUR STL PILE HP12X53	FOOT	864.000 X				
51202700	DRIVE STL PILE	FOOT	864.000 X				
51203600	TEST PILE ST HP12X53	EACH	2.000 X				
51205200	TEMP SHT PILING	SQ FT	1,578.000 X				
51500100	NAME PLATES	EACH	1.000 X				
54200640	P CUL 1 CS/A CP 15	FOOT	27.000 X				
54213867	STEEL END SEC 12	EACH	2.000 X				

Revised
 4-14-05

FAU 2661
 00-00095-11-BR
 LAKE

ILLINOIS DEPARTMENT OF TRANSPORTATION
 SCHEDULE OF PRICES
 CONTRACT NUMBER - 83789

ECMS002 DTGECM03 ECMR003 PAGE 5
 RUN DATE - 04/14/05
 RUN TIME - 183426

ITEM NUMBER	PAY ITEM DESCRIPTION	UNIT OF MEASURE	QUANTITY	UNIT PRICE		TOTAL PRICE	
				DOLLARS	CENTS	DOLLARS	CTS
54213870	STEEL END SEC 15	EACH	2.000 X	=	=	=	=
60103500	PIPE DRAINS CS 12	FOOT	35.000 X	=	=	=	=
60900315	TY D INLET BOX 609006	EACH	2.000 X	=	=	=	=
60900515	CONC THRUST BLOCKS	EACH	2.000 X	=	=	=	=
63000000	SPBGR TY A	FOOT	405.000 X	=	=	=	=
63100070	TRAF BAR TERM T5	EACH	4.000 X	=	=	=	=
63200310	GUARDRAIL REMOV	FOOT	456.000 X	=	=	=	=
66410410	CH LK FENCE RELOC	FOOT	184.000 X	=	=	=	=
70101700	TRAF CONT & PROT	L SUM	1.000 X	=	=	=	=
70106500	TEMP BR TRAF SIGNALS	EACH	4.000 X	=	=	=	=
70300100	SHORT-TERM PAVT MKING	FOOT	124.000 X	=	=	=	=
70300625	TEMP PT PVT M LINE 4	FOOT	2,476.000 X	=	=	=	=
70301000	WORK ZONE PAVT MK REM	SQ FT	2,600.000 X	=	=	=	=
70400100	TEMP CONC BARRIER	FOOT	414.000 X	=	=	=	=
70400200	REL TEMP CONC BARRIER	FOOT	414.000 X	=	=	=	=

Revised

FAU 2661
 00-00095-11-BR
 LAKE

ILLINOIS DEPARTMENT OF TRANSPORTATION
 SCHEDULE OF PRICES
 CONTRACT NUMBER - 83789

ECMS002 DTGECM03 ECMR003 PAGE 6
 RUN DATE - 04/14/05
 RUN TIME - 183426

ITEM NUMBER	PAY ITEM DESCRIPTION	UNIT OF MEASURE	QUANTITY	UNIT PRICE		TOTAL PRICE	
				DOLLARS	CENTS	DOLLARS	CTS
78000200	THPL PVT MK LINE 4	FOOT	964.000 X	=			
78000300	THPL PVT MK LINE 5	FOOT	964.000 X	=			
78001110	PAINT PVT MK LINE 4	FOOT	274.000 X	=			
78001120	PAINT PVT MK LINE 5	FOOT	274.000 X	=			
78200400	GUARDRAIL REFLECTORS	EACH	17.000 X	=			

TOTAL \$

- NOTE:
1. EACH PAY ITEM SHOULD HAVE A UNIT PRICE AND A TOTAL PRICE.
 2. THE UNIT PRICE SHALL GOVERN IF NO TOTAL PRICE IS SHOWN OR IF THERE IS A DISCREPANCY BETWEEN THE PRODUCT OF THE UNIT PRICE MULTIPLIED BY THE QUANTITY.
 3. IF A UNIT PRICE IS OMITTED, THE TOTAL PRICE WILL BE DIVIDED BY THE QUANTITY IN ORDER TO ESTABLISH A UNIT PRICE.
 4. A BID MAY BE DECLARED UNACCEPTABLE IF NEITHER A UNIT PRICE NOR A TOTAL PRICE IS SHOWN.

Revised
 A-14-05