

ROUTE NO.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
355	03-00201-03-FP	LIVINGSTON	5	5

PROJECT NO. SR-355(119)

SCHEDULE OF RESURFACING QUANTITIES

Unit weight Constant = 112.0 lbs./s.y./inch

LOCATION (QUANTITY)	LENGTH	AREA (SQ YD)	BIT SURF REMOVAL VAR DEPTH (SQ YD)	SHORT- TERM PAVT MARKING (FOOT)	WORK ZONE PAVT MK REM (SQ FT)	PAINT PVT MARKING LINE, 4" (FOOT)	BIT MATLS PR CT RC-70 (GALLON)	BIT MATLS PR CT MC-30 (GALLON)	AGG PR CT (TON)	CEMENT (100 WT)	BIT MATL BSE CSE (GALLON)	PROCESS STAB BSE CSE (SQ YD)	WATERPRF MEMBRANE SYSTEM (SQ YD)	BINDER CSE SUPER, IL-19.0 N50 (TON)	BIT CONC SC, SUPER "C" N50 (TON)	INCIDENTAL BIT SURF (TON)	AGG SHLDS TYPE B (TON)
MAINLINE																	
0+33 to 1+33	100	244	-	(3 Apps.) 30	(1 App.) 3	25	17	-	-	37	610	267	-	31	17	-	9
1+33 to 23+56	2223	5434	-	666	74	556	380	-	11	815	13585	5928	-	685	380	-	197
23+56 to 24+46 (TAPER)	90	220	-	27	3	23	15	-	-	33	550	240	-	23	15	-	
24+46 to 25+01 (SURFACE)	55	134	-	18	2	14	9	-	-	-	335	-	-	-	9	-	5
25+01 to 25+67 (053-3448)	66	161	-	21	2	17	11	-	-	-	403	-	220	-	11	-	6
25+67 to 26+07 (SURFACE)	40	98	-	12	1	10	7	-	-	-	245	-	-	-	7	-	4
26+07 to 26+97 (TAPER)	90	220	-	27	3	23	15	-	-	33	550	240	-	23	15	-	8
26+97 to 163+81	13684	33450	-	4104	456	3421	2342	-	67	5018	83625	36491	-	4215	2342	-	1212
163+81 to 164+71 (TAPER)	90	220	-	27	3	23	15	-	-	33	550	240	-	23	15	-	8
164+71 to 165+31 (SURFACE)	60	147	-	18	2	15	10	-	-	-	368	-	-	-	10	-	5
165+31 to 165+67 (053-4054)	36	88	-	12	1	9	6	-	-	-	220	-	144	-	6	-	3
165+67 to 167+17 (TAPER)	150	367	86	45	5	38	26	-	-	-	918	-	-	-	26	-	13
TOTAL JOB LENGTH OR MAINLINE QUANTITY	16684	40783	86	5007	555	4171	2855		78	5968	101959	43406	364	5000	2853		1470
MISCELLANEOUS																	
PRIVATE ENTRANCES (5)	-	-	-	-	-	-	-	53.0	-	-	-	-	-	-	-	30.0	-
SIDEROAD INTERSECTIONS (6)	-	-	-	-	-	-	54.0	-	-	-	-	-	-	-	-	90.0	-
M.B.T.O.'s (5)	-	-	-	-	-	-	-	5.0	-	-	-	-	-	-	12	-	-
TOTALS OF MAINLINE & MISC.	16,684	40,783	86	5,007	555	4,171	2,907	58	78	5,968	101,959	43,406	364	5,000	2,865	120	1,470

Z:\COWORK\ROAD Projects\00201FP3-KangleyPlans\EstCost-ResurfSched-KangleyRd.xls\SchedResurfQys