

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
749	122RS-3	*	54	22
STA.		TO STA.		
FED. ROAD DIST. NO.		ILLINOIS FED. AID PROJECT		
* DOUGLAS, COLES & EDGAR CONTRACT NO. 50769				

SCHEDULES OF QUANTITIES

78100100 RAISED REFLECTIVE MARKER (CRYSTAL MONODIRECTIONAL) (40' CTS)

STATION	TO	STATION	EACH
<u>EDGAR COUNTY</u>			
1071+50		1073+22	4
1074+00		1075+50	4
SUB-TOTAL =			8 EACH
<u>IL RTE. 49</u>			
43+00		44+50	4
45+55		47+10	4
SUB-TOTAL =			8 EACH
TOTAL =			16 EACH

78100100 RAISED REFLECTIVE MARKER (AMBER BIDIRECTIONAL) (40' CTS)

STATION	TO	STATION	EACH
<u>EDGAR COUNTY</u>			
1071+00		1073+30	12
1074+00		1076+00	10
1080+00		1084+41.82	22
SUB-TOTAL =			44 EACH
<u>IL RTE. 49</u>			
43+00		44+72.53	9
45+32.58		47+25	10
53+00		59+50.66	8
31+19		37+00	7
SUB-TOTAL =			34 EACH
TOTAL =			78 EACH

X4032500 BITUMINOUS MATERIALS COVER & SEAL COAT (SPECIAL)

STATION	GALLONS
**	2011.0
TOTAL = 2011.0	

X4040100 SEAL COAT AGGREGATE (SPECIAL)

STATION	TON
**	30
TOTAL = 30	

** PLAN LOCATIONS FOR BITUMINOUS MATERIALS COVER & SEAL COAT (SPECIAL), AND SEAL COAT AGGREGATE (SPECIAL) SHALL BE COORDINATED BY THE ENGINEER WITH BUREAU OF MATERIALS UPON COMPLETION OF BITUMINOUS SURFACE REMOVAL 3/4"

Z0010900 COLD MILLING, SPECIAL

STATION	TO	STATION	FOOT
<u>COLES COUNTY</u>			
RT 811+09		RT 821+30.5	1022
TOTAL =			1022 FOOT