

GENERAL NOTES (Cont'd)

F.A.I. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
72		MACON	135	4

• 158-62,58-62-1,58-63RS
CONTRACT NO. 90879

EARTHWORK ANALYSIS

LOCATION	EARTH EXCAVATION CU YD	EARTH EXCAVATION ADJUSTED FOR SHRINKAGE CU YD	EMBANKMENT CU YD	FURNISHED EXCAVATION CU YD
RURAL				
WIDENING FOR TERMINALS				
4 TBT T1 SPECIAL FLARED	0.0	0.0	43.2	- 43.2
0 TBT T1 SPECIAL TANGENT	0.0	0.0	0.0	0.0
TOTALS =	0.0	0.0	43.2	- 43.2
URBAN				
MEDIAN CROSS-OVERS				
STA 555+53.00	113.1	84.8	1.9	+ 82.9
STA 546+00.00	9.2	8.5	128.3	- 119.8
WIDENING FOR TERMINALS				
14 TBT T1 SPECIAL FLARED	0.0	0.0	151.2	- 151.2
4 TBT T1 SPECIAL TANGENT	0.0	0.0	10.4	- 10.4
IMPACT ATTENUATOR				
SN 058-0076	13.0	9.8	599.0	- 589.2
WIDENING FOR TERMINALS @ DUAL STRUCTURES				
6 TBT T1 SPECIAL FLARED	0.0	0.0	844.8	- 844.8
**WIDENING FOR TERMINALS @ OVERHEADS				
12 TBT T1 SPECIAL FLARED	0.0	0.0	260.4	- 260.4
GORE AREAS FOR STAGING				
SN 058-0069	0.4	0.3	0.0	+ 0.3
SN 058-0074	10.5	7.9	0.0	+ 7.9
SN 058-0075	3.0	2.3	0.0	+ 2.3
TOTALS =	149.2	113.6	2039.2	- 1925.6
FINAL TOTALS =	149.0	144.0	2039.0	- 1926.0

FURNISHED EXCAVATION = ADJUSTED EARTH EXCAVATION (CUYD) - EMBANKMENT

EARTH EXCAVATION = 149.0 CU YD
FURNISHED EXCAVATION = 1926.0 CU YD

** S.N. 058-0072, 058-0073, AND 058-0076