

## SUMMARY OF QUANTITIES

F.A.I. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
72	*	MACON	135	5

\* (58-62,58-62-1,58-63)RS  
CONTRACT NO. 90879

LOCATION OF WORK: FAI ROUTE 72 (I-72)  
SECTION ( 58-62, 58-62-1, 58-63)RS  
MACON COUNTY

	FAI-72 Macon County	FAI-72 Macon County	FAI-72 Macon County	FAI-72 Macon County	FAI-72 Macon County	FAI-72 Macon County	FAI 72 IL 121 Macon County
Sta 415+07.22	Sta 468+58.30	to	Impact	SN 058-0068 & SN 058-0069	SN 058-0070 & SN 058-0071	SN 058-0074 & SN 058-0075	Sta 878+24.32
to	to	to	Attenuators	SN 058-0071	SN 058-0075	to	Sta 920+60.90
Sta 468+58.30	Sta 861+36.68	Rural	Urban	Urban	Urban	Urban	Urban
90% FED	90% FED	90% FED	90% FED	90% FED	90% FED	90% FED	90% FED
10% STATE	10% STATE	10% STATE	10% STATE	10% STATE	10% STATE	10% STATE	10% STATE
I000	I000	SFTY-3N	SFTY-2A	SFTY-2A	SFTY-2A	SFTY-2A	I000

CODE NO	ITEM	CONSTRUCTION TYPE CODE:	UNIT	TOTAL QUANTITY	I000	I000	SFTY-3N	SFTY-2A	SFTY-2A	SFTY-2A	I000
70100815	TRAFFIC CONTROL AND PROTECTION, STANDARD 701446		L SUM	1.0	0.5	0.5	0.0	0.0	0.0	0.0	0.0
<del>20006150</del>	BRIDGE DECK HYDRO-SCARIFICATION		SQ YD	8630.0	0.0	0.0	0.0	2867.0	2096.0	3667.0	0.0
20200100	EARTH EXCAVATION		CU YD	149.0	0.0	149.0	0.0	0.0	0.0	0.0	0.0
20400800	FURNISHED EXCAVATION		CU YD	1926.0	0.0	1926.0	0.0	0.0	0.0	0.0	0.0
21400100	GRADING AND SHAPING DITCHES		FOOT	830.0	0.0	830.0	0.0	0.0	0.0	0.0	0.0
25000210	SEEDING, CLASS 2A		ACRE	3.6	0.1	3.5	0.0	0.0	0.0	0.0	0.0
25000400	NITROGEN FERTILIZER NUTRIENT		POUND	364.0	9.0	355.0	0.0	0.0	0.0	0.0	0.0
25000500	PHOSPHORUS FERTILIZER NUTRIENT		POUND	364.0	9.0	355.0	0.0	0.0	0.0	0.0	0.0
25000600	POTASSIUM FERTILIZER NUTRIENT		POUND	364.0	9.0	355.0	0.0	0.0	0.0	0.0	0.0
25100115	MULCH, METHOD 2		ACRE	3.6	0.1	3.5	0.0	0.0	0.0	0.0	0.0
28000250	TEMPORARY EROSION CONTROL SEEDING		POUND	373.0	10.0	363.0	0.0	0.0	0.0	0.0	0.0
28000300	TEMPORARY DITCH CHECKS		EACH	2.0	0.0	2.0	0.0	0.0	0.0	0.0	0.0
28000500	INLET AND PIPE PROTECTION		EACH	1.0	0.0	1.0	0.0	0.0	0.0	0.0	0.0
35100700	AGGREGATE BASE COURSE, TYPE A 8"		SQ YD	297.0	0.0	297.0	0.0	0.0	0.0	0.0	0.0
40200800	AGGREGATE SURFACE COURSE, TYPE B		TON	130.0	42.0	88.0	0.0	0.0	0.0	0.0	0.0
40600100	BITUMINOUS MATERIALS (PRIME COAT)		GALLON	24,495.0	3028.0	21667.0	0.0	0.0	0.0	0.0	0.0
40600105	BITUMINOUS MATERIALS (PRIME COAT), SPECIAL		GALLON	47,455.0	6635.0	40820.0	0.0	0.0	0.0	0.0	0.0
40600300	AGGREGATE (PRIME COAT)		TON	1,442.0	194.0	1248.0	0.0	0.0	0.0	0.0	0.0
40600895	CONSTRUCTING TEST STRIP		EACH	2.0	0.0	2.0	0.0	0.0	0.0	0.0	0.0
40600980	BITUMINOUS SURFACE REMOVAL - BUTT JOINT		SQ YD	11,387.0	1019.0	10368.0	0.0	0.0	0.0	0.0	0.0
40600985	PORTLAND CEMENT CONCRETE SURFACE REMOVAL - BUTT JOINT		SQ YD	1,232.0	240.0	992.0	0.0	0.0	0.0	0.0	0.0
40600990	TEMPORARY RAMP		SQ YD	2,396.0	467.0	1929.0	0.0	0.0	0.0	0.0	0.0
40800010	BITUMINOUS MATERIALS (PRIME COAT)		GALLON	22.0	0.0	22.0	0.0	0.0	0.0	0.0	0.0
40800030	AGGREGATE (PRIME COAT)		TON	1.0	0.0	1.0	0.0	0.0	0.0	0.0	0.0
40800040	INCIDENTAL BITUMINOUS SURFACING		TON	52.0	0.0	52.0	0.0	0.0	0.0	0.0	141.0
42001300	PROTECTIVE COAT		SQ YD	152.0	0.0	152.0	0.0	0.0	0.0	0.0	0.0
44000006	BITUMINOUS SURFACE REMOVAL 1 1/2"		SQ YD	1556.0	0.0	1556.0	0.0	0.0	0.0	0.0	0.0
44000300	CURB REMOVAL		FOOT	42.0	0.0	42.0	0.0	0.0	0.0	0.0	0.0