F.A.I. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
72	*	MACON	135	6

* (58-62,58-62-1,58-63)RS
CONTRACT NO. 90879

SUMMARY OF QUANTITIES (Cont'd)

LOCATION OF WORK: FAI ROUTE 72 (I-72)
SECTION (58-62, 58-62-1, 58-63)RS
MACON COUNTY

FAI 72
(61)

CONSTRUCTION TYPE CODE:				FAI-72 Macon County Sta 415+07.22 to Sta 468+58.30	FAI-72 Macon County Sta 468+58.30 to Sta 861+36.68	FAI-72 Macon County Impact Attenuators	FAI-72 Macon County SN 058-0068 & SN 058-0069	FAI-72 Macon County SN 058-0070 & SN 058-0071	FAI-72 Macon County SN 058-0074 & SN 058-0075	IL 121 Macon County Sta 878+24.32 to Sta 920+60.90
				Rural	Urban	Urban	Urban	Urban	Urban	Urban
				90% FED 10% STATE	90% FED 10% STATE	90% FED 10% STATE	90% FED 10% STATE	90% FED 10% STATE	90% FED 10% STATE	90% FED 10% STATE
				I000	I000	SFTY-3N	SFTY-2A	SFTY-2A	SFTY-2A	I000
CODE NO	ITEM	UNIT	TOTAL QUANTITY							
44000910	BITUMINOUS CONCRETE REMOVAL (DECK)	SQ YD	12884.0	0.0	0.0	0.0	4225.0	3095.0	5564.0	0.0
44004250	PAVED SHOULDER REMOVAL	SQ YD	13253.0	0.0	13253.0	0.0	0.0	0.0	0.0	0.0
44004400	PAVEMENT REMOVAL, (SPECIAL)	SQ YD	1000.0	1000.0	0.0	0.0	0.0	0.0	0.0	0.0
44200525	CLASS A PATCHES, TYPE I, 8 INCH	SQ YD	23.0	15.0	8.0	0.0	0.0	0.0	0.0	0.0
44200529	CLASS A PATCHES, TYPE II, 8 INCH	SQ YD	1741.0	464.0	1277.0	0.0	0.0	0.0	0.0	0.0
44200533	CLASS A PATCHES, TYPE III, 8 INCH	SQ YD	178.0	16.0	162.0	0.0	0.0	0.0	0.0	0.0
44200535	CLASS A PATCHES, TYPE IV, 8 INCH	SQ YD	320.0	40.0	280.0	0.0	0.0	0.0	0.0	0.0
44201741	CLASS D PATCHES, TYPE II, 8 INCH	SQ YD	128	48.0	80.0	0.0	0.0	0.0	0.0	0.0
44201765	CLASS D PATCHES, TYPE II, 10 INCH	SQ YD	365.0	0.0	365.0	0.0	0.0	0.0	0.0	
44201769	CLASS D PATCHES, TYPE III, 10 INCH	SQ YD	39.0	0.0	39.0	0.0	0.0	0.0	0.0	0.0
44213000	PATCHING REINFORCEMENT	SQ YD	2261.0	535.0	1726.0	0.0	0.0	0.0	0.0	0.0
44213200	SAW CUTS	FOOT	16969.0	4314.0	12655.0	0.0	0.0	0.0	0.0	0.0
44400100	FIBER GLASS FABRIC REPAIR SYSTEM	SQ YD	141.0	0.0	141.0	0.0	0.0	0.0	0.0	0.0
48101200	AGGREGATE SHOULDERS, TYPE B	TON	10716.0	1316.0	9400.0	0.0	0.0	0.0	0.0	
48202000	BITUMINOUS SHOULDERS SUPERPAVE	TON	33720.0	4230.0	29490.0	0.0	0.0	0.0	0.0	
50102400	CONCRETE REMOVAL	CU YD	34.8	0.0	0.0	0.0	0.0	0.0	34.8	0.0
50104000	BRIDGE RAIL REMOVAL	FOOT	149.0	0.0	149.0	0.0	0.0	0.0	0.0	0.0
50300100	FLOOR DRAINS	EACH	24.0	0.0	0.0	0.0	0.0	24.0	0.0	0.0
50300255	CONCRETE SUPERSTRUCTURE	CU YD	40.6	0.0	3.8	0.0	0.9	0.9	35.0	0.0
50300260	BRIDGE DECK GROOVING	SQ YD	8324.0	0.0	0.0	0.0	2773.0	2002.0	3549.0	0.0
50300310	ELASTOMERIC BEARING ASSEMBLY, TYPE I	EACH	19.0	0.0	0.0	0.0	0.0	0.0	19.0	0.0
50500405	FURNISHING AND ERECTING STRUCTURAL STEEL	POUND	4450.0	0.0	0.0	0.0	0.0	0.0	4450.0	0.0
50500715	JACK AND REMOVE EXISTING BEARINGS	EACH	19.0	0.0	0.0	0.0	0.0	0.0	19.0	0.0
50501130	STRUCTURAL STEEL REPAIR	POUND	270.0	0.0	0.0	0.0	0.0	0.0	270.0	0.0
50800205	REINFORCEMENT BARS, EPOXY COATED	POUND	5206.0	0.0	1246.0	0.0	0.0	0.0	3960.0	0.0
60100060	CONCRETE HEADWALL FOR PIPE DRAINS	EACH	2.0	0.0	2.0	0.0	0.0	0.0	0.0	0.0