

SUMMARY OF QUANTITIES (Cont'd)

F.A.I. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
72	*	MACON	135	9

* (58-62,58-62-1,58-63)RS
CONTRACT NO. 90879

LOCATION OF WORK: FAI ROUTE 72 (I-72)
SECTION (58-62, 58-62-1, 58-63)RS
MACON COUNTY

	FAI-72 Macon County	FAI-72 Macon County	FAI-72 Macon County	FAI-72 Macon County	FAI-72 Macon County	FAI-72 Macon County	FAI-72 IL 121 Macon County
Sta 415+07.22	to Sta 468+58.30	Sta 468+58.30	to Sta 861+36.68	Impact Attenuators	SN 058-0068 & SN 058-0069	SN 058-0070 & SN 058-0071	SN 058-0074 & SN 058-0075
Rural	Urban	Urban	Urban	Urban	Urban	Urban	Urban
90% FED 10% STATE	90% FED 10% STATE	90% FED 10% STATE	90% FED 10% STATE	90% FED 10% STATE	90% FED 10% STATE	90% FED 10% STATE	90% FED 10% STATE
I000	I000	SFTY-3N	SFTY-2A	SFTY-2A	SFTY-2A	SFTY-2A	I000

CODE NO	ITEM	CONSTRUCTION TYPE CODE:	UNIT	TOTAL QUANTITY	I000	I000	SFTY-3N	SFTY-2A	SFTY-2A	SFTY-2A	I000
X0322729	MATERIAL TRANSFER DEVICE		TON	60887.0	9079.0	51808.0	0.0	0.0	0.0	0.0	0.0
X0324158	COMPUTERIZED GRADE CONTROL SYSTEM		L SUM	1.0	0.5	0.5	0.0	0.0	0.0	0.0	0.0
X4066528	POLYMERIZED BITUMINOUS CONCRETE SURFACE COURSE, SUPERPAVE, MIX "D", N90		TON	26486.0	3663.0	22823.0	0.0	0.0	0.0	0.0	0.0
X4066658	POLYMERIZED BITUMINOUS CONCRETE BINDER COURSE, SUPERPAVE, IL-19.0, N90		TON	36454.0	5417.0	31037.0	0.0	0.0	0.0	0.0	0.0
X4066915	POLYMERIZED LEVELING BINDER (MACHINE METHOD), SUPERPAVE N90		TON	718.0	0.0	718.0	0.0	0.0	0.0	0.0	0.0
X4430200	REFLECTIVE CRACK CONTROL TREATMENT (SPECIAL)		FOOT	400.0	0.0	400.0	0.0	0.0	0.0	0.0	0.0
X5012650	CONCRETE HEADWALL REMOVAL SPECIAL		EACH	2.0	0.0	2.0	0.0	0.0	0.0	0.0	0.0
X7015005	CHANGEABLE MESSAGE SIGN		CAL DAY	40.0	14.0	26.0	0.0	0.0	0.0	0.0	0.0
XX002909	CLASS SI CONCRETE		CU YD	2.3	0.0	2.3	0.0	0.0	0.0	0.0	0.0
XZ193500	BRIDGE DECK MICROSILICA CONCRETE OVERLAY 2 1/4"		SQ YD	8630.0	0.0	0.0	0.0	2867.0	2096.0	3667.0	0.0
Z0001800	APPROACH SLAB REPAIR (PARTIAL DEPTH)		SQ YD	27.0	0.0	0.0	0.0	18.0	9.0	0.0	0.0
Z0002600	BAR SPLICERS		EACH	50.0	0.0	0.0	0.0	0.0	0.0	50.0	0.0
Z0002900	BASE COURSE (OPTION)		SQ YD	13253.0	0.0	13253.0	0.0	0.0	0.0	0.0	0.0
Z0004800	BITUMINOUS MIX FOR PATCHING		TON	168.0	168.0	0.0	0.0	0.0	0.0	0.0	0.0
Z0006150	BRIDGE DECK HYDRO-SCARIFICATION		SQ YD	8630.0	0.0	0.0	0.0	2867.0	2096.0	3667.0	0.0
Z0016001	DECK SLAB REPAIR (FULL DEPTH, TYPE I)		SQ YD	19.0	0.0	0.0	0.0	4.0	12.0	3.0	0.0
Z0016002	DECK SLAB REPAIR (FULL DEPTH, TYPE II)		SQ YD	197.0	0.0	0.0	0.0	36.0	17.0	144.0	0.0
Z0030150	IMPACT ATTENUATORS (NON-REDIRECTIVE), TEST LEVEL 3		EACH	2.0	0.0	0.0	2.0	0.0	0.0	0.0	0.0
Z0030250	IMPACT ATTENUATORS, TEMPORARY (NON- REDIRECTIVE), TEST LEVEL 3		EACH	7.0	0.0	0.0	7.0	0.0	0.0	0.0	0.0
Z0030350	IMPACT ATTENUATORS, RELOCATE (NON- REDIRECTIVE), TEST LEVEL 3		EACH	5.0	0.0	0.0	5.0	0.0	0.0	0.0	0.0
Z0047300	PROTECTIVE SHIELD		SQ YD	2913.0	0.0	0.0	0.0	1147.0	410.0	1356.0	0.0
Z0048665	RAILROAD PROTECTIVE LIABILITY INSURANCE		L SUM	1.0	0.0	1.0	0.0	0.0	0.0	0.0	0.0
Z0066800	STABILIZED SHOULDERS (REPAIR)		SQ YD	6607.0	1628.0	4979.0	0.0	0.0	0.0	0.0	0.0
Z0075300	TIE BARS		EACH	552.0	55.0	497.0	0.0	0.0	0.0	0.0	0.0
Z0076600	TRAINNEES		Hour	1,000		1,000					
	SPECIALTY ITEMS										
	0 4080										

REVISION
3-1-05