

F.A.I. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
72	*	MACON	135	19

• (58-62.58-62-1.58-63)RS
CONTRACT NO. 90879

SCHEDULE OF QUANTITIES

BITUMINOUS SHOULDER CURB - 66101120				
LOCATION	STATION	TO	STATION	LENGTH
S. N. 058-0066	RT.	473+72.00	473+78.00	6.0
	LT.	473+72.00	473+78.00	6.0
	RT.	476+38.00	476+44.00	6.0
	LT.	476+38.00	476+44.00	6.0
S. N. 058-0067	RT.	489+82.00	489+88.00	6.0
	LT.	489+82.00	489+88.00	6.0
	RT.	492+32.00	492+38.00	6.0
	LT.	492+32.00	492+38.00	6.0
S. N. 058-0068	RT.	304+01.00	304+07.00	6.0
	LT.	304+01.00	304+07.00	6.0
	RT.	306+21.00	306+27.00	6.0
	LT.	306+21.00	306+27.00	6.0
S. N. 058-0069	RT.	507+79.00	507+85.00	6.0
	LT.	507+79.00	507+85.00	6.0
	RT.	509+96.00	510+02.00	6.0
	LT.	509+96.00	510+02.00	6.0
S. N. 058-0070	RT.	533+84.00	533+90.00	6.0
	LT.	533+84.00	533+90.00	6.0
	RT.	536+01.00	536+07.00	6.0
	LT.	536+01.00	536+07.00	6.0
S. N. 058-0071	RT.	533+86.00	533+92.00	6.0
	LT.	533+86.00	533+92.00	6.0
	RT.	536+04.00	536+10.00	6.0
	LT.	536+04.00	536+10.00	6.0
S. N. 058-0074	RT.	722+63.00	722+69.00	6.0
	LT.	722+71.00	722+77.00	6.0
	RT.	725+61.00	725+67.00	6.0
	LT.	725+70.00	725+76.00	6.0
S. N. 058-0075	RT.	722+46.00	722+52.00	6.0
	LT.	722+55.00	722+61.00	6.0
	RT.	725+44.00	725+50.00	6.0
	LT.	725+54.00	725+60.00	6.0
FINAL TOTAL = 192.0 FEET				

CONNECTION TO EXISTING PIPE UNDERDRAIN - X0321962		
STATION	EACH	
RT MED 831+50.00	1.0	
RT MED 2833+00.00	1.0	
FINAL TOTAL = 2.0 EACH		

REFLECTIVE CRACK CONTROL TREATMENT, SPECIAL - #5000628			
LOCATION	STATION	TO	STATION
VARIATIONS ON MAINLINE I-72			400.0
FINAL TOTAL = 400.0 FEET			

CONCRETE HEADWALL REMOVAL, SPECAIL - X5012650		
STATION	EACH	
RT MED 831+50.00	1.0	
RT MED 2833+00.00	1.0	
FINAL TOTAL = 2.0 EACH		

TABULATION OF JOINT PATCHING

STATION	TO	STATION	LANE	LENGTH (FT)	WIDTH (FT)	DEPTH (IN)	PAVEMENT REMOVAL (SPECIAL) (SQ YD)	BITUMINOUS MIX FOR PATCHING (TON)
321+00	---	325+00	WB	400	3	3	133.3	22.4
308+00		319+00	WB	1100	3	3	366.7	61.6
418+00		423+00	EB	500	3	3	166.7	28.0
430+00		435+00	EB	500	3	3	166.7	28.0
450+00		455+00	EB	500	3	3	166.7	28.0
TOTAL =							1000.0	168.0

POLYUREA PAVEMENT MARKING - LETTERS AND SYMBOLS - 78008100

WHITE QUANTITY = 110.0 FEET
YELLOW QUANTITY = 0.0 FEET

TOTAL QUANTITY = 110.0 FEET

POLYUREA PAVEMENT MARKING - 4" - 78008310

WHITE QUANTITY = 78875.0 FEET
YELLOW QUANTITY = 81227.0 FEET

TOTAL QUANTITY = 160,102.0 FEET

POLYUREA PAVEMENT MARKING - 6" - 78008330

WHITE QUANTITY = 327.0 FEET
YELLOW QUANTITY = 0.0 FEET

TOTAL QUANTITY = 327.0 FEET

POLYUREA PAVEMENT MARKING - 8" - 78008340

WHITE QUANTITY = 3322.0 FEET
YELLOW QUANTITY = 0.0 FEET

TOTAL QUANTITY = 3322.0 FEET

POLYUREA PAVEMENT MARKING - 12" - 78008350

WHITE QUANTITY = 215.0 FEET
YELLOW QUANTITY = 0.0 FEET

TOTAL QUANTITY = 215.0 FEET

POLYUREA PAVEMENT MARKING - 24" - 78008370

WHITE QUANTITY = 72.0 FEET
YELLOW QUANTITY = 0.0 FEET

TOTAL QUANTITY = 72.0 FEET

PREFORMED PLASTIC PAVEMENT MARKING - 4" - 78003110

WHITE QUANTITY = 27187.0 FEET
YELLOW QUANTITY = 0.0 FEET

TOTAL QUANTITY = 27187.0 FEET

EPOXY PAVEMENT MARKING - 4" - 78005110

WHITE QUANTITY = 2632.0 FEET
YELLOW QUANTITY = 1830.0 FEET

TOTAL QUANTITY = 4462.0 FEET

REVISED JMS
3-25-05