

SCHEDULE OF QUANTITIES

F.A.I. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
72	*	MACON	135	22

• (58-62,58-62-1,58-63)RS
CONTRACT NO. 90879

TABULATION OF CLASS A PAVEMENT PATCHING I-72 WESTBOUND - 8" (CONT'D)

STATION	DIRECTION	LANE	LENGTH (FT)	WIDTH (FT)	PATCH AREA				SAW CUTS 44213200 (FT)	TIE BARS Z0075300 (EACH)	PATCHING REINFORCEMENT 44213000 (SQ YD)	STAB SHLDR REPAIR Z0066800 (SQ YD)
					TYPE I 44200525 (SQ YD)	TYPE II 44200529 (SQ YD)	TYPE III 44200533 (SQ YD)	TYPE IV 44200535 (SQ YD)				
626+00	WB	DL	6.0	12.0		8.0			60.0	0.0	8.0	18.7
623+00	WB	DL	4.5	12.0		6.0			57.0	0.0	6.0	18.2
621+00	WB	DL	4.5	12.0		6.0			57.0	0.0	6.0	18.2
618+50	WB	DL	35.0	6.0			23.3		94.0	35.0	23.3	28.3
592+40	WB	DL	6.0	12.0		8.0			60.0	0.0	8.0	18.7
577+40	WB	DL	4.5	12.0		6.0			57.0	0.0	6.0	18.2
572+75	WB	PL	4.5	12.0		6.0			57.0	0.0	6.0	18.2
572+30	WB	DL	4.5	12.0		6.0			57.0	0.0	6.0	18.2
569+00	WB	PL	4.5	12.0		6.0			57.0	0.0	6.0	18.2
569+00	WB	DL	4.5	12.0		6.0			57.0	0.0	6.0	18.2
567+00	WB	DL	4.5	12.0		6.0			57.0	0.0	6.0	18.2
566+90	WB	PL	4.5	12.0		6.0			57.0	0.0	6.0	18.2
564+90	WB	DL	4.5	12.0		6.0			57.0	0.0	6.0	18.2
563+50	WB	DL	4.5	12.0		6.0			57.0	0.0	6.0	18.2
563+00	WB	DL	25.0	6.0			16.7		74.0	25.0	16.7	25.0
562+25	WB	DL	4.5	12.0		6.0			57.0	0.0	6.0	18.2
561+00	WB	DL	4.5	12.0		6.0			57.0	0.0	6.0	18.2
543+00	WB	DL	12.0	6.0		8.0			48.0	0.0	8.0	20.7
542+50	WB	DL	8.0	12.0		10.7			64.0	0.0	10.7	19.3
542+40	WB	DL	25.0	12.0				33.3	98.0	25.0	33.3	25.0
540+25	WB	DL	30.0	6.0			20.0		84.0	30.0	20.0	26.7
532+00	WB	DL	4.5	12.0		6.0			57.0	0.0	6.0	18.2
532+00	WB	PL	4.5	12.0		6.0			57.0	0.0	6.0	18.2
532+00	WB	ML	4.5	12.0		6.0			57.0	0.0	6.0	18.2
321+00	WB	RL	25.0	6.0			16.7		74.0	25.0	16.7	25.0
316+00	WB	RL	4.5	12.0		6.0			57.0	0.0	6.0	18.2
316+00	WB	ML	4.5	12.0		6.0			57.0	0.0	6.0	18.2
314+10	WB	RL	4.5	12.0		6.0			57.0	0.0	6.0	18.2
312+45	WB	RL	4.5	12.0		6.0			57.0	0.0	6.0	18.2
311+50	WB	RL	4.5	12.0		6.0			57.0	0.0	6.0	18.2
311+40	WB	ML	4.5	12.0		6.0			57.0	0.0	6.0	18.2
310+20	WB	RL	4.5	12.0		6.0			57.0	0.0	6.0	18.2
309+75	WB	RL	4.5	12.0		6.0			57.0	0.0	6.0	18.2
309+50	WB	RL	4.5	12.0		6.0			57.0	0.0	6.0	18.2
301+50	WB	RL	4.5	12.0		6.0			57.0	0.0	6.0	18.2
300+75	WB	LL	4.5	12.0		6.0			57.0	0.0	6.0	18.2
300+25	WB	LL	4.5	12.0		6.0			57.0	0.0	6.0	18.2
298+50	WB	LL	4.5	12.0		6.0			57.0	0.0	6.0	18.2
296+50	WB	RL	4.5	12.0		6.0			57.0	0.0	6.0	18.2
281+50	WB	PL	6.0	6.0	4.0				36.0	0.0	4.0	18.7
281+40	WB	DL	8.0	6.0		5.3			40.0	0.0	5.3	19.3
269+50	WB	DL	4.5	12.0		6.0			57.0	0.0	6.0	18.2
265+00	WB	DL	4.5	12.0		6.0			57.0	0.0	6.0	18.2
262+60	WB	DL	4.5	12.0		6.0			57.0	0.0	6.0	18.2
262+60	WB	PL	4.5	12.0		6.0			57.0	0.0	6.0	18.2
260+25	WB	RL	4.5	12.0		6.0			57.0	0.0	6.0	18.2
258+50	WB	RL	12.0	6.0		8.0			48.0	0.0	8.0	20.7
254+00	WB	LL	4.5	12.0		6.0			57.0	0.0	6.0	18.2
253+30	WB	LL	4.5	12.0		6.0			57.0	0.0	6.0	18.2
230+50	WB	PL	4.5	12.0		6.0			57.0	0.0	6.0	18.2
229+60	WB	DL	4.5	12.0		6.0			57.0	0.0	6.0	18.2
229+50	WB	DL	4.5	12.0		6.0			57.0	0.0	6.0	18.2
SHEET TOTALS =					4.0	288.0	76.7	33.3	3060.0	140.0	402.0	992.7
WESTBOUND FINAL TOTAL =					8.0	817.7	118.0	246.7	8605.0	407.0	1190.3	2742.5

REVISED JMS
3-25-05