

# SCHEDULE OF QUANTITIES

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
716	130(R,R-1)RS	MACON	36	21

CONTRACT NO. 90929

## COMBINATION CURB & GUTTER REMOVE & REPLACE

<u>LOCATION</u>	<u>LENGTH (LIN FT)</u>
SOUTH CUSHING NB	50'
58+40 S. TO KING STREET	200'
KING STREET N. TO 58+40	200'
* KING STREET DISTANCES ARE APPROXIMATES. INTERMITTENT REPAIR THROUGH OUT THAT SECTION*	
<b>TOTAL QUANTITIES</b>	<b>450.0 LIN FT</b>

## MEDIAN REMOVAL PARTIAL DEPTH

<u>STA.</u>	<u>TO</u>	<u>STA.</u>	<u>SQ. FT.</u>
108+73		110+79.8	2176
111+48.16		115+00	2150
115+00		117+95.6	1425
118+64.63		121+02	2603
128+75.31		130+38.5	1686
133+31.47		133+98	382
150+91		152+89.5	3734
153+92		154+50	330

**TOTAL QUANTITIES**                      **14486.0**  
(SQ FT)

**TOTAL MEDIAN REMOVAL (PD)**                      **63005.0**  
(SQ FT)

## MEDIAN REMOVAL PARTIAL DEPTH

<u>STA.</u>	<u>TO</u>	<u>STA.</u>	<u>SQ. FT.</u>
92+33		97+00	6538
97+00		97+81	1134
98+81		103+00	5866
103+00		104+39	1946
105+39		109+00	4916
109+00		110+00	407
121+00		124+25	4550
125+25		127+00	2450
127+00		128+15	1610
136+82.8		139+00	3041
139+00		143+44	6216
144+00		145+00	784
145+00		151+00	9061

**TOTAL QUANTITIES**                      **48519.0**  
(SQ FT)

## TEMPORARY RAMP BITUMINOUS

57+07 START OF JOB  
5' X 48' / 9 = 26.7 SQYD

INTERSECTION OF GRAND AVENUE  
5' X 110' / 9 61.1 SQYD X 2 = 122.2 SQYD

INTERSECTION OF RAVINA PARK ROAD  
5' X 110' / 9 = 61.1 SQYD

RT 131+00 RAILROAD OVERHEAD  
5' X 24' / 9 = 13.3 SQYD

LT 131+45 RAILROAD OVERHEAD  
5' X 24' / 9 = 13.3 SQYD

RT 132+15 RAILROAD OVERHEAD  
5' X 24' / 9 = 13.3 SQYD

## TEMPORARY RAMP BITUMINOUS (Cont' d)

LT 132+50 RAILROAD OVERHEAD  
5' X 24' / 9 = 13.3 SQYD

134+71.20 MAINLINE BRIDGE  
5' X 48' / 9 = 26.7 SQYD

136+82.80 MAINLINE BRIDGE  
5' X 48' / 9 = 26.7 SQYD

157+37.70 END OF JOB  
5' X 48' / 9 = 26.7 SQYD

**TOTAL QUANTITY**                      **344.0 SQYD**