

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
716	130(R,R-1)RS	MACON	36	28

CONTRACT NO. 90929

SCHEDULE OF QUANTITIES

CLASS D PATCHES

STA	DIR	LANE	LENGTH (ft)	WIDTH (ft)	DEPTH (in)	TYPE I (sq. yd)	TYPE II (sq. yd)	TYPE IV (sq. yd)
58+46	NB	PASS	8	12	10"	0.0	10.7	0.0
58+86	NB	PASS	4	10	10"	4.4	0.0	0.0
58+86	NB	DRIV	4	6	10"	2.7	0.0	0.0
59+11	NB	PASS	10	12	10"	0.0	13.3	0.0
59+11	NB	DRIV	6	6	10"	4.0	0.0	0.0
59+36	NB	PASS	6	12	10"	0.0	8.0	0.0
77+10	NB	DRIV	40	12	10"	0.0	0.0	53.3

TOTAL	11.1	32.0	53.3
	(sq. yd)	(sq. yd)	(sq. yd)
USE	12.0	32.0	54.0

DETECTOR LOOP, TYPE I LOOP SIZE 6' x 6'

W. B. GRAND AVE.

7 LOOPS X 24' = 168 FT
HOME RUN LENGTH = 150 FT
TOTAL = 318 FT

E. B. GRAND AVE.

7 LOOPS X 24' = 168 FT
HOME RUN LENGTH = 150 FT
TOTAL = 318 FT

N. B. ILL RTE. 48

5 LOOPS X 24' = 120 FT
HOME RUN LENGTH = 90 FT
TOTAL = 210 FT

S. B. ILL RTE. 48

5 LOOPS X 24' = 120 FT
HOME RUN LENGTH = 90 FT
TOTAL = 210 FT

TOTAL = 1056 FT

CONCRETE MEDIAN TSM-6 (DOWELLED) MARIETTA STREET

59+87.50 22.3 SQ FT
60+63.50 22.3 SQ FT

WILDER AVENUE

66+00 22.3 SQ FT
66+81 22.3 SQ FT

LEAFLAND / UNIVERSITY AVENUE

72+06.50 22.3 SQ FT
72+50.50 22.3 SQ FT

OAKLAND AVENUE

81+61 22.3 SQ FT
81+98 22.3 SQ FT
82+00 22.3 SQ FT
82+36.40 22.3 SQ FT
82+66 22.3 SQ FT

WEST CENTER STREET

N. SIDE OF INTERSECTION
22.3 SQ FT

RAIL-ROAD OVERHEAD

N. AND S. ENDS 44.6 SQ FT

TOTAL QUANTITY 312.2 SQ FT