

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
774	*	EFFINGHAM	273	6
FED. ROAD DIST. NO. 7		ILLINOIS	FED. AID PROJECT	

*107WRS-1, 107BY, 107BY-1 & 107B-2
CONTRACT NO. 94827

SUMMARY OF QUANTITIES				CONSTRUCTION TYPE CODE						
PAY CODE NUMBER	ITEM	UNIT	TOTAL QUANTITY	1000-2A		X071-2A		X080-2A	Y007	
				RURAL	URBAN	RURAL	URBAN	RURAL	RURAL	URBAN
51202700	DRIVING STEEL PILES	FOOT	1,422			448	294	680		
51203400	TEST PILE STEEL HP 10x42	EACH	2			2				
51203500	TEST PILE STEEL HP 10x57	EACH	2				2			
51203600	TEST PILE STEEL HP 12x53	EACH	2					2		
51204315	CONCRETE ENCASMENT	CU YD	31.4					31.4		
51205200	TEMPORARY SHEET PILING	SQ FT	1,240			900	340			
51500100	NAME PLATES	EACH	3			1	1	1		
54001001	BOX CULVERT END SECTION, CULVERT NO. 1	EACH	2	2						
54001002	BOX CULVERT END SECTION, CULVERT NO. 2	EACH	1		1					
54001003	BOX CULVERT END SECTION, CULVERT NO. 3	EACH	1		1					
54002020	EXPANSION BOLTS 3/4 INCH	EACH	50	20	30					
54010202	PRECAST CONCRETE BOX CULVERT 2' X 2'	FOOT	45		45					
54010303	PRECAST CONCRETE BOX CULVERT 3' X 3'	FOOT	30		30					
54010403	PRECAST CONCRETE BOX CULVERT 4' X 3'	FOOT	133	48	85					
542A0223	PIPE CULVERTS, CLASS A, TYPE 1 18"	FOOT	236	200	36					
542A0241	PIPE CULVERTS, CLASS A, TYPE 1 36"	FOOT	12		12					
542D0220	PIPE CULVERTS, CLASS D, TYPE 1 15"	FOOT	391	280	111					
542D0223	PIPE CULVERTS, CLASS D, TYPE 1 18"	FOOT	76	32	44					
542D0226	PIPE CULVERTS, CLASS D, TYPE 1 21"	FOOT	58	58						
542D0229	PIPE CULVERTS, CLASS D, TYPE 1 24"	FOOT	159	121	38					
542D0235	PIPE CULVERTS, CLASS D, TYPE 1 30"	FOOT	55	55						
542D1066	PIPE CULVERTS, CLASS D, TYPE 2 21"	FOOT	80	80						
542D1075	PIPE CULVERTS, CLASS D, TYPE 2 30"	FOOT	166	166						
542D5470	PIPE CULVERTS, CLASS D, TYPE 1, EQUIVALENT ROUND-SIZE 15"	FOOT	225	225						
542JA030	PIPE CULVERTS, CLASS A 30" (JACKED)	FOOT	182	182						
54213447	END SECTIONS 12"	EACH	4	2	2					
54213450	END SECTIONS 15"	EACH	16	12	4					
54213453	END SECTIONS 18"	EACH	4	2	2					
54213456	END SECTIONS 21"	EACH	4	4						
54213459	END SECTIONS 24"	EACH	6	4	2					
54213465	END SECTIONS 30"	EACH	6	6						
54213663	PRECAST REINFORCED CONCRETE FLARED END SECTIONS 18"	EACH	3	3						
54213669	PRECAST REINFORCED CONCRETE FLARED END SECTIONS 24"	EACH	3		3					
54213675	PRECAST REINFORCED CONCRETE FLARED END SECTIONS 30"	EACH	4	4						
54213681	PRECAST REINFORCED CONCRETE FLARED END SECTIONS 36"	EACH	2		2					
54214290	END SECTIONS, EQUIVALENT ROUND-SIZE 15"	EACH	10	10						
54216930	REINFORCED CONCRETE PIPE TEE, 18" PIPE WITH 18" RISER	EACH	1	1						
54217680	REINFORCED CONCRETE PIPE TEE, 24" PIPE WITH 24" RISER	EACH	1		1					
550A0070	STORM SEWERS, CLASS A, TYPE 1 15"	FOOT	15		15					
550A0120	STORM SEWERS, CLASS A, TYPE 1 24"	FOOT	685		685					
550A0160	STORM SEWERS, CLASS A, TYPE 1 36"	FOOT	276		276					

NOTE:
RURAL STA. 942+50.00 TO STA. 1016+00.00
URBAN STA. 1016+00.00 TO STA. 46+80.05
*DENOTES SPECIALTY ITEM

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION

SUMMARY OF QUANTITIES
SHEET 3 OF 6

DRAWN BY ASB
CHECKED BY SJK
DATE 8/02