| F.A.P. RTE. | SECTION | COUNTY | TOTAL SHEETS | SHEET NO. |
|---|---|---|---|---|
| 774 | * | EFFINGHAM | 273 | 25 |
| FED. ROAD DIST. NO. 7 | ILLINOIS | FED. AID PROJECT | | |

*107WRS-1, 107BY, 107BY-1 & 107B-2

**CONTRACT NO. 94827**

## ENTRANCE CULVERT SCHEDULE

| PROPOSED MATERIAL | TYPE | SIDE/ STATION | EXISTING CULVERT SIZE | PIPE CULVERT, CLASS D | | | | | | | END SECTIONS | | | | | |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| | | | | TYPE I | | | | | TYPE II | | | | | | | |
| | | | | 15" | 18" | 21" | 24" | 15" EQ RND | 21" | 30" | 15" | 18" | 21" | 24" | 30" | 15" EQ RND |
| | | | | FT | FT | FT | FT | FT | FT | FT | EACH | EACH | EACH | EACH | EACH | EACH |
| AGG | CE | LT/ 953+15.73 | 18"Ø | | | 58 | | | | | | | 2 | | | |
| AGG | PE | RT/ 967+27.95 | 12"Ø | 31 | | | | | | | 2 | | | | | |
| BIT | PE | RT/ 970+42.68 | 12"Ø | 36 | | | | | | | 2 | | | | | |
| CONC | PE | RT/ 972+37.06 | 12"Ø | | | | | 30 | | | | | | | | 2 |
| CONC | PE | RT/ 977+48.03 | 15"Ø | | 32 | | | | | | | 2 | | | | |
| AGG | FE | LT/ 1001+08.52 | 21"Ø | | | | | | | 81 | | | | | 2 | |
| AGG | FE | RT/ 1002+39.03 | 24"Ø | | | | | | | 85 | | | | | 2 | |
| BIT | CE | RT/ 1021+73.10 | 24"Ø | | | | 38 | | | | | | | 2 | | |
| CONC | PE | LT/ 1022+11.30 | 15"Ø | 74 | | | | | | | 2 | | | | | |
| AGG | CE | RT/ 1024+56.23 | 15"Ø | | 44 | | | | | | | 2 | | | | |
| BIT | PE | LT/ 1034+14.52 | 12"Ø | 37 | | | | | | | 2 | | | | | |
| AGG | CE | LT/ 241+31.00 WEBB ST | 12"Ø | | | | | 62 | | | | | | | | 2 |
| AGG | CE | RT/ 241+31.00 WEBB ST | 12"Ø | | | | | 46 | | | | | | | | 2 |
| AGG | FE | RT/ 203+00.00 1200TH ST | N/A | | | | | | 80 | | | | 2 | | | |
| TOTAL | | | | 178 | 76 | 58 | 38 | 138 | 80 | 166 | 8 | 4 | 4 | 2 | 4 | 6 |

## PUBLIC ROAD CULVERT SCHEDULE

| PUBLIC ROAD/ SIDE/ STATION | EXISTING CULVERT SIZE | PIPE CULVERT, CLASS A, TYPE I | PIPE CULVERT, CLASS D, TYPE I | | | | PRC FLARED END SECTIONS | END SECTIONS | | | |
|---|---|---|---|---|---|---|---|---|---|---|---|
| | | 18" | 15" | 24" | 30" | 15" EQUIV ROUND | 18" | 15" | 24" | 30" | 15" EQUIV ROUND |
| | | FT | FT | FT | FT | FT | EACH | EACH | EACH | EACH | EACH |
| NAZARENE RD RT/955+28.27 | 18"Ø | 130 | | | | | 3 | | | | |
| WEBB ST LT/958+10.00 | 15"Ø | | 47 | | | | | 2 | | | |
| BRIARWOOD DR LT/969+63.16 | 15"Ø | | 50 | | | | | 2 | | | |
| LYNN ACRES DR RT/974+61.71 | 12"Ø | | | | | 47 | | | | | 2 |
| CTRY ESTS RD LT/977+46.69 | 15"Ø | | | | | 40 | | | | | 2 |
| LEPRECHAUN LN LT/982+15.24 | 18"Ø | | | 65 | | | | | 2 | | |
| IRISH HILL LT/991+30.47 | 24"Ø | | | 56 | | | | | 2 | | |
| WBSH RIVER HILL RT/991+35.27 | 24"Ø | | | | 55 | | | | | 2 | |
| LAKE RD LT/1023+77.06 | 15"Ø | | 51 | | | | | 2 | | | |
| WOOD BIRD 309+76.00 | N/A | | 65 | | | | | 2 | | | |
| | TOTAL | 130 | 213 | 121 | 55 | 87 | 3 | 8 | 4 | 2 | 4 |

NOTE: SEE PLAN AND PROFILES FOR ADDITIONAL DETAILS

*DGN-SPEC*
*DATE*

| REVISIONS NAME | DATE |
|---|---|
| | |

ILLINOIS DEPARTMENT OF TRANSPORTATION

ENTRANCE PIPE CULVERT SCHEDULES

DRAWN BY MLO

DATE 8/02 CHECKED BY SJK