


SUMMARY OF QUANTITIES

FINAL SURVEYED	BY	DATE
SURVEY PLOTTED		
NOTE BOOK TEMPLATE		
AREAS CHECKED		
NO.		

ORIGINAL SURVEYED	BY	DATE
SURVEY PLOTTED		
NOTE BOOK TEMPLATE		
AREAS CHECKED		
NO.		

SUMMARY OF QUANTITIES			
I000-2A			
CODE NO.	ITEM DESCRIPTION	UNIT	TOTAL QUANTITY
31100300	SUB-BASE GRANULAR MATERIAL, TYPE A 4"	SQ YD	163
35300100	PORTLAND CEMENT CONCRETE BASE COURSE 6"	SQ YD	163
40600100	BITUMINOUS MATERIALS (PRIME COAT)	GALLON	4951
40600980	BITUMINOUS SURFACE REMOVAL - BUTT JOINT	SQ YD	1973
40600985	PORTLAND CEMENT CONCRETE SURFACE REMOVAL - BUTT JOINT	SQ YD	327
40600990	TEMPORARY RAMP	SQ YD	2120
40600300	AGGREGATE (PRIME COAT)	TON	142
42300300	PORTLAND CEMENT CONCRETE DRIVEWAY PAVEMENT, 7 INCH	SQ YD	392
42400100	PORTLAND CEMENT CONCRETE SIDEWALK 4"	SQ FT	4071
44000030	BITUMINOUS SURFACE REMOVAL (VARIABLE DEPTH)	SQ YD	32281
44000100	PAVEMENT REMOVAL	SQ YD	56
44000200	DRIVEWAY PAVEMENT REMOVAL	SQ YD	116
44000300	CURB REMOVAL	FOOT	251
44000500	COMBINATION CURB AND GUTTER REMOVAL	FOOT	1969
44000600	SIDEWALK REMOVAL	SQ FT	6234
44003100	MEDIAN REMOVAL	SQ FT	1469
44003510	MEDIAN REMOVAL PARTIAL DEPTH	SQ FT	16163
44200974	CLASS B PATCHES, TYPE III, 10 INCH	SQ YD	812
44300200	STRIP REFLECTIVE CRACK CONTROL TREATMENT	FT	10331
60605000	COMBINATION CONCRETE CURB AND GUTTER, TYPE B-6.24	FOOT	2220
67000400	ENGINEER'S FIELD OFFICE, TYPE A	CAL MO	3
67100100	MOBILIZATION	L SUM	1
70101700	TRAFFIC CONTROL AND PROTECTION	L SUM	1
70300100	SHORT-TERM PAVEMENT MARKING	FOOT	1866
70300210	TEMPORARY PAVEMENT MARKING-LETTERS AND SYMBOLS	SQ FT	250

SUMMARY OF QUANTITIES			
I000-2A			
CODE NO.	ITEM DESCRIPTION	UNIT	TOTAL QUANTITY
70300220	TEMPORARY PAVEMENT MARKING-LINE 4"	FOOT	17135
70300240	TEMPORARY PAVEMENT MARKING-LINE 6"	FOOT	2569
70300260	TEMPORARY PAVEMENT MARKING-LINE 12"	FOOT	592
70300280	TEMPORARY PAVEMENT MARKING-LINE 24"	FOOT	93
70301000	WORK ZONE PAVEMENT MARKING REMOVAL	SQ FT	156
72000100	SIGN PANEL - TYPE 1	SQ FT	14
72800100	TELESCOPING STEEL SIGN SUPPORT	FOOT	20
73100100	BASE FOR TELESCOPING STEEL SIGN SUPPORT	EACH	2
78000100	THERMOPLASTIC PAVEMENT MARKING - LETTERS & SYMBOLS	SQ FT	250
78000200	THERMOPLASTIC PAVEMENT MARKING-LINE 4"	FOOT	17135
78000400	THERMOPLASTIC PAVEMENT MARKING-LINE 6"	FOOT	2569
78000650	THERMOPLASTIC PAVEMENT MARKING-LINE 24"	FOOT	93
78002150	PREFORMED PLASTIC PAVEMENT MARKING, TYPE-A - LINE 12"	FOOT	592
X4066428	BITUMINOUS CONCRETE SURFACE COURSE, SUPERPAVE, MIX "D", N90	TON	3067
X4066775	LEVELING BINDER (MACHINE METHOD) SUPERPAVE N90	TON	1516
Z0000990	AGGREGATE FOR TEMPORARY ACCESS	TON	500
Z0048665	RAILROAD PROTECTIVE LIABILITY INSURANCE	L SUM	1
X0006125	REMOVE AND REPLACE CONCRETE INLET LID	EACH	16

 Juneau Associates, Inc. P.C. <small>CONSULTING ENGINEERS AND LAND SURVEYORS</small> 2100 State Street, P.O. Box 1325 Grand Rapids, MI 49501-1325 Phone: (616) 771-1400 / (616) 442-5253 Fax: (616) 771-5541		SUMMARY OF QUANTITIES F.A.U. ROUTE 9097 MADISON AVENUE MADISON, ILLINOIS SECTION No. 02-00051-00-RS	
REVISIONS NO. DATE BY REMARKS		SCALE: NOT TO SCALE	
DSN BY: BFK DATE: 10/15/04		SHEET: 3	
DWN BY: WRC DATE: 10/15/04		CHK'D: BFK DATE: 10/15/04	
DWG. NO.		JOB NO. E031013 DGN. NAME: SIMOTY OF 56 SHTS	