

DETAIL "A"
SCALE: 1" = 10'

FENCE REMOVAL NOTES:
THE EXISTING FENCE WILL BE REMOVED ALONG THE LIMITS OF THE PROPOSED FENCE. THE POST, FABRIC, BARBED WIRE WILL BE REMOVED. THE SALVAGED MATERIALS WILL BE TURNED OVER TO THE AIRPORT MANAGER AND STORED AT A LOCATION HE SELECTS. PROVIDING THAT THE AIRPORT MANAGER DOES NOT WANT THE SALVAGED MATERIALS, THE CONTRACTOR WILL DISPOSED OF THE MATERIALS OFF SITE.

THE REMOVAL OF THE CLASS "E" FENCE WILL BE PAID FOR BY ITEM:
AR162900 "REMOVE CLASS E FENCE" - 360 L.F.

FENCING NOTES:
THE PROPOSED CLASS "E" FENCE (8' HIGH) WITH 3 STRANDS OF BARBED WIRE WILL BE INSTALLED AT THE LOCATIONS SHOWN ON THIS SHEET AND IN ACCORDING WITH THE DETAILS SHOWN ON THIS SHEET AND IN THE SPECIAL PROVISIONS.


THE PROPOSED CLASS "E" FENCE WILL BE PAID FOR BY ITEM:
AR162508 "CLASS E FENCE 8" - 303 L.F.

THE 5' CLASS "E" GATE WILL BE PAID FOR BY ITEM:
AR162605 "CLASS E GATE-5" - 1 EACH

THE 24' ELECTRIC GATE WILL BE PAID FOR BY ITEM:
AR162724 "ELECTRIC GATE-24" - 1 EACH

THE EXISTING FENCE WILL BE CONNECTED TO THE PROPOSED END POST.

AIRPORT SECURITY NOTES:
AIRPORT SECURITY IS TO BE MAINTAINED DURING THE FENCE REMOVAL CONSTRUCTION STAGE. THE CONTRACTOR WILL REMOVE ONLY THAT LENGTH OF FENCE EACH DAY THAT WILL BE REPLACED BY NEW FENCE OR SECURED WITH TEMPORARY FENCING PROVIDING SECURITY. THE AIRPORT MANAGER WILL DETERMINE THE ACCEPTABILITY OF TEMPORARY FENCING.



LEGEND

	PROPOSED PAVEMENT
	PROPOSED 4' SIDEWALK
	EXISTING FENCE
	PROPOSED FENCE REMOVAL AND REPLACEMENT

DATE	REVISION	BY

ST. LOUIS REGIONAL AIRPORT
St. Louis Regional
 AIRPORT
 EAST ALTON, ILLINOIS
 ILL. PROJ.: ALN-3355

FILE	DATE	BY	REVIEWED
HEL Project No. 837-04RDD	03/08/04	JAC	WJM
Filename R-171FEN.DWG	03/08/04	JAC	WJM
Scale 1"=30'	03/08/04	JAC	WJM
Date 03/08/04	06/23/04	JAC	WJM

HANSON
 Hanson Professional Services Inc.
 1525 South Sixth Street
 Springfield, IL 62766
 Offices Nationwide

CONSTRUCT T-HANGAR
 ACCESS ROAD
 PROPOSED FENCING PLAN