



NOTE:
SEE PAGE 84 FOR OAK FLATS ROAD QUANTITIES

MATCH EXISTING ELEVATION

20' TAPER AGG. SURFACE COURSE
2"=4"

SURFACE REMOVAL 2", SPECIAL
STA. 188+62 LT. TO STA. 189+04 LT., 60.8 SQ. YD.

GATE REMOVAL
STA. 188+37, 14.24 LT., 1 EACH

MATCH TO SHEET 84
OAK FLATS ROAD

P.C.C. SIDEWALK, 5"
STA. 191+13 TO STA. 191+21 LT., 45.0 SQ. FT.

SIDEWALK REMOVAL
STA. 191+13 TO STA. 191+21 LT., 45.0 SQ. FT.

P.C.C. SIDEWALK, 5"
STA. 191+30 TO STA. 191+37 LT., 45.0 SQ. FT.

SIDEWALK REMOVAL
STA. 191+30 TO STA. 191+37 LT., 45.0 SQ. FT.

WOOD SIGN SUPPORT
STA. 191+26, 23.80' LT., 14 FOOT

SIGN PANEL TYPE 1, (NOTE "A")
STA. 191+26, 23.80' LT., 1 SQ. FT.

CONTROL POINT #58
STA. 191+38.91, 19.80' LT.
N 1379546.43
E 2125415.43
ELEV.= 695.64

EXIST. CURVE C69
PI STA. = 188+71.66
 $\Delta = 55^\circ 04' 28''$ (RT)
D = 45° 50' 12"
R = 125.00'
T = 65.17'
L = 120.15'
E = 15.97'
P.C. STA. = 188+06.49
P.T. STA. = 189+26.64

MATCHLINE 187+50

STA. 191+71.44, 37.55' RT.
25' R

55' CAMPER PAD

EXIST. CURVE C70
PI STA. = 191+89.82
 $\Delta = 49^\circ 19' 37''$ (RT)
D = 34° 43' 29"
R = 165.00'
T = 75.76'
L = 142.05'
E = 16.56'
P.C. STA. = 191+14.06
P.T. STA. = 192+56.11

STA. 192+89.29, 17.33' RT.
5' R

56' CAMPER PAD

EXCAVATION - (SPECIAL)
STA. 191+84 TO STA. 192+37.5 RT., 34.1 CU. YDS.

INSTALL PARKING BLOCKS
STA. 191+96.83, 1 EACH

STA. 192+18.08, 18.76' RT.
5' R

STA. 192+51.35, 39.42' RT.
25' R

EXCAVATION - (SPECIAL)
STA. 192+77 TO STA. 193+07 RT., 33 CU YDS

INSTALL PARKING BLOCKS
STA. 192+66.32, 1 EACH

MATCHLINE 193+75

TREE REMOVAL		
STA.	OFFSET	SIZE
187+57.62RT	13'	25"
188+41.10RT	19'	14"
188+44.04RT	12'	34"
188+50.14RT	12'	34"
188+65.39RT	12'	35"

- GATE REMOVAL
- REMOVE AND REPLACE SIDEWALK
- SURFACE REMOVAL
- SCARIFY SURFACE

NOTE "A": NOT A HANDICAP ACCESSIBLE ROUTE

FILE NAME =	USER NAME = #USER#	DESIGNED - R.H.D.	REVISED -	STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION	ARGYLE LAKE STATE PARK MAIN ROAD			F.A. RTEL.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
#FILE#		DRAWN - J.T.T.	REVISED -		SCALE: 1" = 20'	SHEET NO. 52 OF 162 SHEETS	STA. 187+50 TO STA. 193+75	ARGYLE LAKE STATE PARK	MCDONOUGH	162	52	
		CHECKED - T.T.P.	REVISED -					CONTRACT NO. 46158				
		DATE - 12/09/10	REVISED -					FED. ROAD DIST. NO. ILLINOIS FED. AID PROJECT				