

SUMMARY OF QUANTITIES

100% STATE
0005

CODE NO.	ITEM	UNIT	TOTAL
20200100	EARTH EXCAVATION	CU YD	3,180
* 20200200	ROCK EXCAVATION	CU YD	125
21101505	TOPSOIL EXCAVATION AND PLACEMENT	CU YD	255
25000100	SEEDING, CLASS 1	ACRE	2.1
25000400	NITROGEN FERTILIZER NUTRIENTS	POUND	195
25000500	PHOSPHORUS FERTILIZER NUTRIENTS	POUND	195
25000600	POTASSIUM FERTILIZER NUTRIENTS	POUND	195
25100630	EROSION CONTROL BLANKET	SQ YD	10,400
25100635	HEAVY DUTY EROSION CONTROL BLANKET	SQ YD	400
28000250	TEMPORARY EROSION CONTROL SEEDING	POUND	1,300
28000305	TEMPORARY DITCH CHECKS	FOOT	280
28000400	PERIMETER EROSION BARRIER	FOOT	1,528
28000500	INLET AND PIPE PROTECTION	EACH	5
28100105	STONE RIPRAP, CLASS A3	SQ YD	21
28100107	STONE RIPRAP, CLASS A4	SQ YD	114
28200200	FILTER FABRIC	SQ YD	114
31101100	SUBBASE GRANULAR MATERIAL, TYPE B	CU YD	3,015
35800100	PREPARATION OF BASE	SQ YD	1,000
35800200	AGGREGATE BASE REPAIR	TON	100
40200800	AGGREGATE SURFACE COURSE, TYPE B	TON	495
40600200	BITUMINOUS MATERIALS (PRIME COAT)	TON	17
40600990	TEMPORARY RAMP	SQ YD	145
40603080	HOT-MIX ASPHALT BINDER COURSE, IL-19.0, N50	TON	1,115
40603310	HOT-MIX ASPHALT SURFACE COURSE, MIX "C", N50	TON	895
42400100	PORTLAND CEMENT CONCRETE SIDEWALK 4 INCH	SQ FT	82
44000157	HOT-MIX ASPHALT SURFACE REMOVAL, 2"	SQ YD	1,880
44000500	COMBINATION CURB AND GUTTER REMOVAL	FOOT	40
44000600	SIDEWALK REMOVAL	SQ FT	1,242
44201709	CLASS D PATCHES, TYPE III, 5 INCH	SQ YD	34
44300200	STRIP REFLECTIVE CRACK CONTROL TREATMENT	FOOT	92
50105220	PIPE CULVERT REMOVAL	FOOT	104
542A0223	PIPE CULVERTS, CLASS A, TYPE 1 18"	FOOT	26
542A1063	PIPE CULVERTS, CLASS A, TYPE 2 18"	FOOT	36
542A1075	PIPE CULVERTS, CLASS A, TYPE 2 30"	FOOT	146
542A5485	PIPE CULVERTS, CLASS A, TYPE 1 EQUIVALENT ROUND-SIZE 30"	FOOT	38
542D0253	PIPE CULVERTS, CLASS D, TYPE 1 48"	FOOT	10
542D015	PIPE CULVERTS, CLASS D, TYPE 1 15" (TEMPORARY)	FOOT	80

* SPECIALTY ITEM

SUMMARY OF QUANTITIES

100% STATE
0005

CODE NO.	ITEM	UNIT	TOTAL
54213663	PRECAST REINFORCED CONCRETE FLARED END SECTIONS 18"	EACH	3
54213675	PRECAST REINFORCED CONCRETE FLARED END SECTIONS 30"	EACH	1
54214725	PRECAST REINFORCED CONCRETE FLARED END SECTIONS-ELLIPTICAL, EQUIVALENT ROUND-SIZE 30"	EACH	2
60602500	CONCRETE GUTTER, TYPE A	FOOT	160
60603300	GUTTER OUL TET	EACH	1
60603400	GUTTER OUTLET (SPECIAL)	EACH	2
60603450	GUTTER INLET (SPECIAL)	EACH	2
60605000	COMBINATION CONCRETE CURB AND GUTTER, TYPE B-6.24	FOOT	40
63200310	GUARDRAIL REMOVAL	FOOT	680
63301000	REMOVE AND RE ERECT STEEL PLATE BEAM GUARDRAIL	FOOT	25
66300105	CALCIUM CHORLIDE APPLIED	TON	10
67000400	ENGINEER'S FIELD OFFICE, TYPE A	CAL MO	4
67100100	MOBILIZATION	L SUM	1
70100450	TRAFFIC CONTROL AND PROTECTION, STANDARD 701201	L SUM	1
70102635	TRAFFIC CONTROL AND PROTECTION, STANDARD 701701	L SUM	1
* 72000100	SIGN PANEL-TYPE 1	SQ FT	6
* 72800100	TELESCOPING STEEL SIGN SUPPORT	FOOT	36
* 78001100	PAINT PAVEMENT MARKING - LETTERS AND SYMBOLS	SQ FT	61
* 78001110	PAINT PAVEMENT MARKING - LINE 4"	FOOT	2,900
* 78001180	PAINT PAVEMENT MARKING - LINE 24"	FOOT	30
Z0013798	CONSTRUCTION LAYOUT	L SUM	1
Z0019600	DUST CONTROL WATERING	UNIT	15
Z0028415	GEOTECHNICAL REINFORCEMENT	SQ YD	6,700
Z0077740	WOOD GUARD RAIL	FOOT	590
X0301339	REMOVE EXISTING PARKING BLOCKS	EACH	30
X0301797	GATE REMOVAL	EACH	1
X0323378	CONCRETE PARKING BLOCKS	EACH	39
X0325418	GATE, SPECIAL 28'	EACH	2
X4240430	PORTLAND CEMENT CONCRETE SIDEWALK 5 INCH, SPECIAL	SQ FT	1,160
X6024502	INLETS, TYPE B, WITH SPECIAL FRAME AND GRATE	EACH	1
X6062700	CONCRETE GUTTER, TYPE A (SPECIAL)	FOOT	313
X0327233	CURED-IN-PLACE PIPE LINER, 48"	FOOT	121
X0327232	GATE, SPECIAL 24'	EACH	1
G0221700	MANHOLES, TYPE A, 5'-DIAMETER, TYPE B GRATE	EACH	1
X7010216	TRAFFIC CONTROL AND PROTECTION, (SPECIAL)	L SUM	1

* SPECIALTY ITEM

DESIGNED - LAW	REVISED - 01/14/11
DRAWN - DRR	REVISED -
CHECKED - PJM	REVISED -
DATE - 10/29/10	REVISED -

STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION
DIVISION OF HIGHWAYS

SUMMARY OF QUANTITIES

SCALE: SHEET NO. 2 OF 36 SHEETS STA. TO STA.

IDOT/IDNR STATEWIDE
MISSISSIPPI PALISADES STATE PARK
SOUTH SLOPE ROAD

F.A.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
	SOUTH SLOPE ROAD	CARROLL	36	2
CONTRACT NO. 46166				
FED. ROAD DIST. NO. ILLINOIS FED. AID PROJECT				

FARNSWORTH GROUP, INC.

CONSULTING ENGINEERS - 2709 MCGRAW DRIVE BLOOMINGTON, ILLINOIS 61704 (309) 663-8435 / (309) 663-1571 FAX

REVISED 02/09/10 DRR; 01/27/11 DRR 24-8373