

COMBINATION CONCRETE CURB & GUTTER REMOVAL	
STATION	FOOT
STA 8+71, LT	20
STA 8+79, RT	20
TOTAL	40

COMBINATION CONCRETE CURB & GUTTER TYPE B-6.24	
STATION	FOOT
STA 8+71, LT	20
STA 8+79, RT	20
TOTAL	40

CONCRETE GUTTER, TYPE A		
STATION	TO STATION	FOOT
STA 25+83, LT	STA 27+40, LT	160
TOTAL		160

CONCRETE GUTTER, TYPE A (SPECIAL)		
STATION	TO STATION	FOOT
STA 22+05, RT	STA 23+53, RT	151
STA 23+91, RT	STA 25+50, RT	162
TOTAL		313

GUTTER OUTLET	
STATION	EACH
STA 25+83, LT	1
TOTAL	1

GUTTER OUTLET (SPECIAL)	
STATION	EACH
STA 22+05, RT	1
STA 23+53, RT	1
TOTAL	2

GUTTER INLET (SPECIAL)	
STATION	EACH
STA 25+50, RT	1
STA 27+40, LT	1
TOTAL	2

REMOVE AND RE-ERECT STEEL PLATE BEAM GUARDRAIL		
STATION	TO STATION	FOOT
STA 20+87, RT	STA 21+03, RT	25
TOTAL		25

GUARDRAIL REMOVAL			
STATION	TO	STATION	FOOT
STA 13+28, RT		STA 13+81, RT	103
STA 21+80, RT		STA 25+43, RT	363
STA 23+09, LT		STA 25+21, LT	214
TOTAL			680

PAINT PAVEMENT MARKING - LETTERS & SYMBOLS	
STATION	SQ FT
IL RTE 84 RIGHT TURN ARROWS	46.8
STA 12+00, RT (PARKING LOT) HC SYMBOLS	4.6
STA 16+70, RT (PARKING LOT) HC SYMBOLS	4.6
STA 19+20, RT (PARKING LOT) HC SYMBOLS	4.6
TOTAL	60.6

PAINT PAVEMENT MARKING - LINE 4"			
STATION	TO	STATION	FOOT
STA 7+84.80, LT (CURB ISLAND)			45
STA 7+84.80, RT (PAINTED ISLAND)			119
STA 7+84.80		STA 10+54.59	524
STA 10+20, RT		STA 10+54.59, RT	43
STA 10+54.59		STA 41+00	780
STA 12+00, RT (PARKING AREA)			511
STA 16+70, RT (PARKING AREA)			387
STA 19+20, RT (PARKING AREA)			491
TOTAL			2,900

PAINT PAVEMENT MARKING - LINE 24"	
STATION	FOOT
STA 7+95, LT	12
STA 7+97, LT (RIGHT TURN LANE)	18
TOTAL	30

GEOTECHNICAL REINFORCEMENT			
STATION	TO	STATION	SQ YD
STA 10+54.59, LT & RT		STA 39+15, LT & RT	6,700
TOTAL			6,700

CONCRETE PARKING BLOCKS	
STATION	EACH
STA 12+00, RT (PARKING LOT)	11
STA 16+70, RT (PARKING LOT)	11
STA 19+20, RT (PARKING LOT)	17
TOTAL	39

REMOVE EXISTING PARKING BLOCKS	
STATION	EACH
STA 12+00, RT (PARKING LOT)	1
STA 16+70, RT (PARKING LOT)	10
STA 19+20, RT (PARKING LOT)	19
TOTAL	30

WOOD GUARD RAIL			
STATION	TO	STATION	FOOT
STA 21+80, RT		STA 25+45, RT	370
STA 23+09, LT		STA 25+21, LT	220
TOTAL			590

GATE, SPECIAL 24'	
STATION	EACH
STA 20+55	1
TOTAL	1

GATE, SPECIAL 28'	
STATION	EACH
STA 86+27 (NORTH SLOPE ROAD)	1
TOTAL	1

DESIGNED - LAW	REVISED - 01/14/11
DRAWN - DRR	REVISED -
CHECKED - PJM	REVISED -
DATE - 10/29/10	REVISED -

**STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION
DIVISION OF HIGHWAYS**

SCHEDULE OF QUANTITIES

SCALE: SHEET NO. 6 OF 36 SHEETS STA. TO STA.

**IDOT/IDNR STATEWIDE
MISSISSIPPI PALISADES STATE PARK
SOUTH SLOPE ROAD**

F.A.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
	SOUTH SLOPE ROAD	CARROLL	36	6
CONTRACT NO. 46166				
FED. ROAD DIST. NO. ILLINOIS FED. AID PROJECT				
REVISED 01/25/11 DRR				