

ACIM
 ROADWAY
 URBAN 90% FED 10% STATE
 RETAINING WALLS
 ACBRE
 WEST FRONTAGE
 SB CONNECTOR
 SN 099-0347
 SB EXIT RAMP
 OVER I-55
 SN 099-0348
 ACIM
 ELECTRICAL
 TRAFFIC SURVEILLANCE
 ACIM
 TRAFFIC SIGNALS

CODE NUMBER	PAY ITEM	UNIT	TOTAL QUANTITY	CONSTRUCTION TYPE CODES					0021	0021
				0001	0040	0010	0008	0008		
78300100	PAVEMENT MARKING REMOVAL	SQ FT	19,742	19,742						
* 80400100	ELECTRIC SERVICE INSTALLATION	EACH	2					2		
* 80400200	ELECTRIC UTILITY SERVICE CONNECTION	L SUM	1.0					1.0		
81000600	CONDUIT IN TRENCH, 2" DIA., GALVANIZED STEEL	FOOT	1,469					925	544	
81000700	CONDUIT IN TRENCH, 2 1/2" DIA., GALVANIZED STEEL	FOOT	164						164	
81000800	CONDUIT IN TRENCH, 3" DIA., GALVANIZED STEEL	FOOT	22						22	
81000900	CONDUIT IN TRENCH, 3 1/2" DIA., GALVANIZED STEEL	FOOT	19						19	
81001000	CONDUIT IN TRENCH, 4" DIA., GALVANIZED STEEL	FOOT	2,037					2,017	20	
81018500	CONDUIT PUSHED, 2" DIA., GALVANIZED STEEL	FOOT	2,032					1,940	92	
81018900	CONDUIT PUSHED, 4" DIA., GALVANIZED STEEL	FOOT	2,987					2,757	230	
81100320	CONDUIT ATTACHED TO STRUCTURE, 1" DIA., PVC COATED GALVANIZED STEEL	FOOT	414					414		
81101000	CONDUIT ATTACHED TO STRUCTURE, 4" DIA., GALVANIZED STEEL	FOOT	5,102					5,102		
81300220	JUNCTION BOX, STAINLESS STEEL, ATTACHED TO STRUCTURE, 6" X 6" X 4"	EACH	10					10		
81300530	JUNCTION BOX, STAINLESS STEEL, ATTACHED TO STRUCTURE, 12" X 10" X 6"	EACH	2					2		
81300960	JUNCTION BOX, STAINLESS STEEL, ATTACHED TO STRUCTURE, 42" X 36" X 12"	EACH	2					2		
81400100	HANDHOLE	EACH	5						5	
81400200	HEAVY-DUTY HANDHOLE	EACH	25					23	2	
81400300	DOUBLE HANDHOLE	EACH	1						1	
* 81603203	UNIT DUCT, 600V, 3-1C NO.2, 1/C NO.4 GROUND, (EPR-TYPE RHW), 1 1/2" DIA. POLYETHYLENE	FOOT	32,673					32,673		
* 81700110	ELECTRIC CABLE IN CONDUIT, 600V (EPR-TYPE RHW) 1/C NO. 10	FOOT	1,752					1,752		
* 81701385	ELECTRIC CABLE IN CONDUIT, 600V (EPR-TYPE USE) 3-1/C 350MCM	FOOT	144					144		
* 81800320	AERIAL CABLE, 3-1/C NO. 4 WITH MESSENGER WIRE	FOOT	8,333					8,333		
* 81900200	TRENCH AND BACKFILL FOR ELECTRICAL WORK	FOOT	47,276					46,507	769	
* 82105700	LUMINAIRE, SODIUM VAPOR, HIGH MAST, HORIZONTAL MOUNT, 750 WATT	EACH	198					198		
* 83057515	LIGHT POLE, WOOD, 100 FOOT, CLASS 1, WITH 15FT MAST ARM	EACH	11					11		
* 83504700	LIGHT TOWER, 120 FT. MOUNTING HEIGHT, LUMINAIRE MT. - 12	EACH	48					48		
* 83505700	LIGHT TOWER, 130 FT. MOUNTING HEIGHT, LUMINAIRE MT. - 12	EACH	33					33		
* 83700350	LIGHT TOWER FOUNDATION, 54" DIAMETER	FOOT	1,372.67					1,372.67		
* 84200804	REMOVAL OF POLE FOUNDATION	EACH	64					64		
* X0440116	RELOCATE EXISTING LIGHTING UNIT, SPECIAL	EACH	10					10		
* 84500110	REMOVAL OF LIGHTING CONTROLLER	EACH	2					2		
* 84500120	REMOVAL OF ELECTRIC SERVICE INSTALLATION	EACH	2					2		
* 84500130	REMOVAL OF LIGHTING CONTROLLER FOUNDATION	EACH	1					1		
* 85000300	MAINTENANCE OF EXISTING TRAFFIC SIGNAL INSTALLATION	L SUM	1						1	
* 85700200	FULL-ACTUATED CONTROLLER AND TYPE IV CABINET	EACH	1						1	
* 86200200	UNINTERRUPTIBLE POWER SUPPLY, STANDARD	EACH	1						1	

* DENOTES SPECIALTY ITEM

FILE NAME = D160F12-SHT-S0007.dgn	USER NAME = TKIuegel	DESIGNED - MJT	REVISED -	STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION	SUMMARY OF QUANTITIES				F.A.I RTE. 55	SECTION 99-2HB-2B-1	COUNTY WILL	TOTAL SHEETS 756	SHEET NO. 11
PLOT SCALE = 1:50	CHECKED - DLT	REVISED -	REVISED -		SCALE: NONE	SHEET NO. 7 OF 11 SHEETS	STA.	TO STA.	CONTRACT NO. 60F12				
PLOT DATE = 2/4/2011	DATE - 2/4/11	REVISED -	REVISED -		FED. ROAD DIST. NO. 1 ILLINOIS FED. AID PROJECT								
Rev.													