

ACIM  
ACBRF  
ACIM  
ROADWAY  
URBAN  
90% FED.  
10% STATE  
RETAINING WALLS  
WEST FRONTAGE  
OVERPASS  
SN 095-0347  
SB EXIT RAMP  
OVER I-55  
SN 095-0348  
ELECTRICAL  
SURVEILLANCE

CODE NUMBER	PAY ITEM	UNIT	TOTAL QUANTITY	CONSTRUCTION TYPE CODES				
				0001	0040	0010	0008	0021
X2800305	REMOVE TEMPORARY DITCH CHECKS	FOOT	3,045	3,045				
X2800310	REMOVE PERIMETER EROSION BARRIER	FOOT	40,470	40,470				
X2800320	REMOVE INLET AND PIPE PROTECTION	EACH	31	31				
X2800315	REMOVE INLET FILTERS	EACH	15	15				
X0327213	REMOVE TEMPORARY PIPE SLOPE DRAIN	EACH	13	13				
X6370279	CONCRETE BARRIER, SINGLE FACE, 42 INCH HEIGHT (SPECIAL)	FOOT	5,147	5,147				
63700175	CONCRETE BARRIER, SINGLE FACE, 42 INCH HEIGHT	FOOT	7,979	7,979				
	<del>CONCRETE BARRIER BASE FOR SINGLE FACE, 6" TOP, 42 INCH HEIGHT</del>	<del>FOOT</del>	<del>5,147</del>	<del>5,147</del>				
	<del>CONCRETE BARRIER BASE FOR SINGLE FACE, 9" TOP, 42 INCH HEIGHT</del>	<del>FOOT</del>	<del>7,979</del>	<del>7,979</del>				
60107700	PIPE UNDERDRAINS 6"	FOOT	32,564	32,564				
60108200	PIPE UNDERDRAINS 6" (SPECIAL)	FOOT	1,852	1,852				
X7010240	TRAFFIC CONTROL SURVEILLANCE (SPECIAL)	CAL DA	345	345				
<del>X7040600</del>	<del>FURNISH TEMPORARY CONCRETE BARRIER</del>	<del>FOOT</del>	<del>2,999</del>	<del>2,999</del>				
* X8710036	FIBER OPTIC CABLE 12 FIBERS, SINGLE MODE	FOOT	2,095					2,095
* X0327214	REMOVAL OF TEMPORARY WOOD POLES AND FIBER OPTIC CABLE	L SUM	1					1
* X0327215	MAINTAIN TEMPORARY FIBER OPTIC CABLE	CAL MO	12					12
* X0326503	CCTV SYSTEM	L SUM	1					1
* X0327217	REMOVAL OF TEMPORARY STORM SEWER PLUGS	EACH	1	1				
* X8300005	LIGHT POLE, WOOD, 60 FOOT, CLASS 4, SPECIAL	EACH	33					33
* 84200600	REMOVAL OF LIGHTING UNIT, SALVAGE	EACH	54					54
* 87001170	ELECTRIC CABLE ASSEMBLY IN TRENCH, 600V (EPR-TYPE TC) 3/C NO. 2 AND NO. 4 GROUND	FOOT	650					650
* 81017525	CONDUIT IN TRENCH, 2" DIA., COILABLE NONMETALLIC CONDUIT	FOOT	1,445					1,445
* X8730312	ELECTRIC CABLE IN CONDUIT, LEAD-IN, No. 18 4/C, TWISTED, SHIELDED	FOOT	4,460					4,460
* 87301900	ELECTRIC CABLE IN CONDUIT, EQUIPMENT GROUNDING, NO. 6 1 C	FOOT	1,130					1,130
* X8730250	ELECTRIC CABLE IN CONDUIT NO. 20 3/C, TWISTED, SHIELDED	FOOT	538					538
* 87702596	STEEL MAST ARM ASSEMBLY AND POLE WITH DUAL MAST ARMS, 38 FT. AND 40 FT.	EACH	1					1
* X7830072	GROOVING FOR RECESSED PAVEMENT MARKING 6"	FOOT	4,780	4,780				
* X7830076	GROOVING FOR RECESSED PAVEMENT MARKING 9"	FOOT	1,324	1,324				

\* DENOTES SPECIALTY ITEM

FILE NAME = D:\60F12-SHT-S0011.dgn	USER NAME = TKLuegel	DESIGNED - MJT	REVISED -	<b>STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION</b>	<b>SUMMARY OF QUANTITIES</b>			F.A.T. RTE. 55	SECTION 99-2HB-2B-1	COUNTY WILL	TOTAL SHEETS 756	SHEET NO. 15
PLOT SCALE = 1:500	CHECKED - DLT	REVISED -	CONTRACT NO. 60F12									
PLOT DATE = 2/4/2011	DATE - 2/4/11	REVISED -	ILLINOIS FED. AID PROJECT									
								SCALE: NONE SHEET NO. 11 OF 11 SHEETS STA. TO STA.				