

EARTHWORK SCHEDULE RAMP C

BEGIN STATION	END STATION	EARTH EXCAVATION	TOPSOIL / UNSUITABLE EXCAVATION	EXCAVATION TO BE USED IN EMBANKMENT ADJUSTED FOR SHRINKAGE*	EMBANKMENT	EARTHWORK BALANCE WASTE (+) OR SHORTAGE (-)	POROUS GRANULAR EMBANKMENT, SUBGRADE	ROCK EXCAVATION
		CU. YD.	CU. YD.	CU. YD.	CU. YD.	CU. YD.	CU. YD.	CU. YD.
2000+00.00	2001+00.00	115	0	98	12	86	0	0
2001+00.00	2002+00.00	110	0	94	17	77	0	0
2002+00.00	2003+00.00	115	0	98	19	79	0	0
2003+00.00	2004+00.00	143	0	122	10	112	0	0
2004+00.00	2005+00.00	163	0	139	13	126	0	0
2005+00.00	2006+00.00	171	0	145	13	132	0	0
2006+00.00	2007+00.00	139	0	118	10	108	0	0
2007+00.00	2008+00.00	88	0	75	23	52	0	0
2008+00.00	2009+00.00	88	0	75	34	41	38	0
2009+00.00	2010+00.00	106	0	90	25	65	82	0
2010+00.00	2011+00.00	108	0	92	15	77	88	0
2011+00.00	2012+00.00	125	0	106	13	93	110	0
2012+00.00	2013+00.00	123	0	105	13	92	123	0
2013+00.00	2014+00.00	106	0	90	17	73	56	0
2014+00.00	2015+00.00	110	0	94	17	77	34	0
2015+00.00	2016+00.00	108	0	92	15	77	34	0
2016+00.00	2017+00.00	112	0	95	15	80	0	0
2017+00.00	2018+00.00	97	0	82	19	63	0	0
2018+00.00	2019+00.00	99	0	84	23	61	0	0
2019+00.00	2020+00.00	106	0	90	23	67	0	0
2020+00.00	2021+00.00	93	0	79	23	56	0	0
2021+00.00	2022+00.00	93	0	79	23	56	0	0
2022+00.00	2023+00.00	93	0	79	23	56	0	0
2023+00.00	2024+00.00	95	0	81	23	58	0	0
2024+00.00	2025+00.00	91	0	77	23	54	0	0
2025+00.00	2026+00.00	89	0	76	21	55	0	0
2026+00.00	2027+00.00	88	0	75	36	39	0	0
2027+00.00	2027+25.00	21	0	18	13	5	0	0
2027+25.00	2028+00.00	63	0	54	62	-8	0	0
2028+00.00	2029+00.00	43	0	37	56	-19	0	0
2029+00.00	2030+00.00	0	0	0	0	0	0	0
2030+00.00	2031+00.00	43	0	37	152	-115	0	0
2031+00.00	2032+00.00	102	0	87	182	-95	0	0
2032+00.00	2033+00.00	112	0	95	76	19	0	0
2033+00.00	2034+00.00	106	0	90	54	36	0	0
2034+00.00	2035+00.00	125	0	106	36	70	0	0
2035+00.00	2036+00.00	156	0	133	54	79	0	0
2036+00.00	2037+00.00	100	0	85	199	-114	0	0
2037+00.00	2038+00.00	45	0	38	204	-166	0	0
SUB TOTAL		3,890	0	3,310	1,606	1,704	565	0

EARTHWORK SCHEDULE I-55

BEGIN STATION	END STATION	EARTH EXCAVATION	TOPSOIL / UNSUITABLE EXCAVATION	EXCAVATION TO BE USED IN EMBANKMENT ADJUSTED FOR SHRINKAGE*	EMBANKMENT	EARTHWORK BALANCE WASTE (+) OR SHORTAGE (-)	POROUS GRANULAR EMBANKMENT, SUBGRADE	ROCK EXCAVATION
		CU. YD.	CU. YD.	CU. YD.	CU. YD.	CU. YD.	CU. YD.	CU. YD.
1059+00.00	1060+00.00	88	58	75	34	41	0	0
1060+00.00	1061+00.00	91	60	77	28	49	0	0
1061+00.00	1062+00.00	93	62	79	28	51	0	0
1062+00.00	1063+00.00	91	60	77	26	51	0	0
1063+00.00	1064+00.00	86	60	73	28	45	0	0
1064+00.00	1065+00.00	80	58	68	30	38	0	0
1065+00.00	1066+00.00	78	56	66	28	38	0	0
1066+00.00	1067+00.00	76	54	65	23	42	58	0
1067+00.00	1068+00.00	73	54	62	25	37	115	0
1068+00.00	1069+00.00	71	58	60	45	15	58	0
1069+00.00	1070+00.00	71	62	60	63	-3	0	0
1070+00.00	1071+00.00	71	63	60	67	-7	0	0
1071+00.00	1072+00.00	73	62	62	63	-1	0	0
1072+00.00	1073+00.00	73	60	62	54	8	49	0
1073+00.00	1074+00.00	69	58	59	45	14	104	0
1074+00.00	1075+00.00	69	41	59	50	9	100	0
1075+00.00	1076+00.00	69	28	59	65	-6	84	0
1076+00.00	1077+00.00	63	30	54	50	4	58	0
1077+00.00	1078+00.00	60	28	51	32	19	43	0
1078+00.00	1079+00.00	60	25	51	32	19	43	0
1079+00.00	1080+00.00	60	23	51	30	21	41	0
1080+00.00	1081+00.00	60	23	51	32	19	45	0
1081+00.00	1082+00.00	60	25	51	36	15	52	0
1082+00.00	1083+00.00	62	30	53	36	17	30	0
1083+00.00	1084+00.00	63	34	54	30	24	0	0
1084+00.00	1085+00.00	63	32	54	26	28	0	0

\* ASSUME 15% FOR SHRINKAGE

McDonough Associates Inc.  
 Engineers / Architects  
 130 East Randolph Street, Chicago, Illinois 60601

FILE NAME = D:\60F12-SHT-SCHEDULE05.dgn	USER NAME = TKIuegal	DESIGNED - TRK	REVISED -	<b>STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION</b>	<b>SCHEDULE OF QUANTITIES</b>			F.A.I. RTE. 55	SECTION 99-2HB-2B-1	COUNTY WILL	TOTAL SHEETS 756	SHEET NO. 30
PLOT SCALE = 1/50	CHECKED - DLT	DRAWN - TRK	REVISED -		SCALE: NONE	SHEET NO. 4 OF 8 SHEETS	STA. TO STA.	CONTRACT NO. 60F12				
PLOT DATE = 2/3/2011	DATE - 2/4/11	REVISOR -	REVISED -		FED. ROAD DIST. NO. 1 ILLINOIS FED. AID PROJECT							