PROPOSED SIGNING SCHEDULE

STATION	OFFSET LT/RT	SIGN TYPE	SIGN SIZE WIDTH (INCHES)	SIGN SIZE DEPTH (INCHES)	NO POST	SUPPORT TYPES W10x22 (LENGTH (FT))	W8x18	W6x15	HSS3x2x1/4	HSS4x2x1/4	HSS4x3x1/4	TYPE A	TYPE B	TYPE C (EACH)	FOUNDATION WEIGHT LBS	FOUNDATION VOLUME CONC. CU YD	SUPPORT STRUCT STEEL LBS	SUPPORT WOOD FT	SIGN PANEL TYPE 1 (SQ FT)	SIGN PANEL TYPE 2 (SQ FT)	SIGN PANEL TYPE 3 (SQ FT)
1005+00	LT	M3-3	36	18	2B								42.6						4.5		
		M1-1	36	36															9.0		
NB I-55	RT	GS-GM	180	108	2W		42.0								175.5	1.57	755.7				135.0
NB I-55	RT	GS-GM	180	108	2W		42.0								175.5	1.57	755.7				135.0
NB I-55	RT	GS-GM	180	108	2W		42.0								175.5	1.57	755.7				135.0
NB I-55	RT	GS-GM	168	90	2W		39.2								175.5	1.57	705.3				105.0
NB I-55	RT	GS-GM	120	72	2W			35.5							175.5	1.57	532.3				60.0
7002+81	RT	CANTILEVER	210	78																	113.8
7004+32	RT	W13-2	48	60	2W													35.5		20.0	
7007+49	LT	GORE SIGN	96	60	2W													33.2			40.0
2036+40	RT	W4-1R	48	48	2W													30.7		16.0	
103+49	LT	W1-2L	48	48	2W													30.7		16.0	
		W13-1	30	30															6.3		
103+49	RT	W1-2L	48	48	2W													30.7		16.0	
		W13-1	30	30															6.3		
119+85	RT	W1-2R	48	48	2W													30.7		16.0	
		W13-1	30	30															6.3		
119+85	LT	W1-2R	48	48	2W													30.7		16.0	
		W13-1	30	30															6.3		
3001+66	RT	W1-8L	18	24	1A							13.1							3.0		
3002+61	RT	W1-8L	18	24	1A							14.3							3.0		
3003+57	RT	W1-8L	18	24	1A							13.9							3.0		
3004+54	RT	W1-8L	18	24	1A							13.6							3.0		
3034+25	LT	W4-1R	48	48	2W													32.7		16.0	
901+04	RT	GS-GM	72	42	2W													34.6		21.0	
901+04	RT	R5-1a	36	24															6.0		
901+33	LT	W1-2L	30	30	1B								12.9						6.3		
		W13-1	18	18															2.3		
903+18	RT	GS-GM	54	48	2W													36.3		18.0	
903+47	LT	D13-3	48	30	1W													20.8		10.0	
903+79	CL	R4-7	24	30	1A							12.5							5.0		
905+08	LT	GS-WM	156	132	2W			34.4									515.7				143.0
905+65	CL	R4-7	24	30	1W													23.8	5.0		
		R3-5L	30	36															7.5		
906+71	RT	W4-2R	36	36	1W													31.1		9.0	
907+05	LT	CANTILEVER	150	102																	106.3
919+00	LT	W4-2R	48	48	1W													23.8		16.0	
919+37	LT	GS-GM	54	24	1W													19.8	9.0		
1005+83	LT	D10-3a	12	60	1C									1					5.0		
1005+83	RT	D10-3a	12	60	1C									1					5.0		
1032+23	LT	D10-3a	12	60	1C									1					5.0		
1032+23	RT	D10-3a	12	60	1C									1					5.0		
1051+69	LT	GORE SIGN	96	60	2W													34.0			40.0
1058+63	LT	D10-3a	12	60	1C									1					5.0		
1058+63	RT	D10-3a	12	60	1C									1					5.0		
8053+02	LT	GS-GM	54	48	2W													32.6		18.0	
2002+00	RT	CANTILEVER	204	120																	170.0
1058+95	LT	W13-2	48	60	2W													35.7		20.0	
1075+00	RT	R3-8	48	48	2B								30.0							16.0	
1079+46	LT	R2-4a	48	72	1W													39.0			24.0
1085+03	LT	D10-3a	12	60	1C									1					5.0		
1085+03	RT	D10-3a	12	60	1C									1					5.0		
1111+43	LT	D10-3a	12	60	1C									1					5.0		
1111+43	RT	D10-3a	12	60	1C									1					5.0		
935+13	LT	M4-5	24	12	1B								13.2						2.0		
		M3-1	24	12															2.0		
		M1-1	24	24															4.0		
		M6-3	21	15															2.2		
									SUB-TOTAL1			68	99	10	878	8	4,021	587	152	244	1,207

PROPOSED SIGNING SCHEDULE

STATION	OFFSET LT/RT	SIGN TYPE	SIGN SIZE WIDTH (INCHES)	SIGN SIZE DEPTH (INCHES)	NO POST	SUPPORT TYPES W10x22 (LENGTH (FT))	W8x18	W6x15	HSS3x2x1/4	HSS4x2x1/4	HSS4x3x1/4	TYPE A	TYPE B	TYPE C (EACH)	FOUNDATION WEIGHT LBS	FOUNDATION VOLUME CONC. CU YD	SUPPORT STRUCT STEEL LBS	SUPPORT WOOD FT	SIGN PANEL TYPE 1 (SQ FT)	SIGN PANEL TYPE 2 (SQ FT)	SIGN PANEL TYPE 3 (SQ FT)
1086+26	LT	CANTILEVER	180	108																	135.0
1089+98	RT	M3-1	36	18	2B								34.3						4.5		
		M1-1	36	36															9.0		
1091+26	LT	GS-GM	168	90	2W		38.5								156.0	1.4	692.7				105.0
1096+28	LT	GS-GM	120	72	2W			33.8							156.0	1.4	506.8				60.0
1108+63	RT	GS-GM	144	102	2W			37.7							156.0	1.4	565.2				102.0
1117+80	RT	CANTILEVER	180	108			RE-USE EXISTING CANTILEVER TRUSS														135.0
SB I-55	RT	GS-GM	180	108			RE-USE EXISTING GM SUPPORT SYSTEM														135.0
6076+80	RT	W1-1R	30	30	2B								39.1						6.3		
		W13-1	18	18															2.3		
6080+48	LT	W1-6R	48	24	2B								31.0						8.0		
6084+00	RT	R3-5L-R	30	36	2A							31.7							7.5		
6084+51	LT	W1-6L	48	24	2B								30.6						8.0		
6086+30	RT	GS-GM	96	84	2H			38.0							92.0	1.4	570.0				56.0
6086+37	LT	W1-1L	30	30	2B								36.8						6.3		
		W13-1	18	18															2.3		
6086+80	RT	W3-3	36	36	2B								35.1						9.0		
952+24	RT	GS-GM	126	84	2W			38.1							156.0	1.4	571.3				73.5
955+00	RT	W3-3	36	36	2B								33.9						9.0		
961+21	RT	GS-GM	90	24	2W													30.2		15.0	
961+70	LT	R2-1	24	30	1B								15.3						5.0		
964+38	RT	GS-GM	156	108	2W		41.4								156.0	1.4	745.3				117.0
965+52	RT	GS-GM	156	102	2W			40.4							156.0	1.4	606.0				110.5
966+00	LT	GS-GM	156	132	2W	47.7									184.0	2.4	1049.0				143.0
970+80	LT	W3-3	36	36	2B								34.6						9.0		
975+10	LT	GS-GM	126	84	2W			37.4							156.0	1.4	561.0				73.5
978+05	LT	W1-2L	30	30	2B								38.2						6.3		
979+15	LT	GS-GM	72	66	2W													41.1			33.0
									SUB-TOTAL2			32	329	0	1,368	14	5,868	72	93	15	1,279
									TOTAL			100	428	10	2,246	22	9,889	659	245	259	2,486

TYPE C SUPPORT IS PAID FOR AS MILE POST MARKER ASSEMBLY (EACH)

TABLE USED FOR CALCULATIONS OF SIGN SUPPORT

SUPPORT SIZE	SUPPORT UNIT WEIGHT PER LIN FT	FOUNDATION BARS WEIGHT PER POST	CONCRETE PER POST
W10x22	22 LBS/FT	92 LBS	1.18 CU YD
W8x18	18 LBS/FT	78 LBS	0.7 CU YD
W6x15	15 LBS/FT	78 LBS	0.7 CU YD
HSS3x2x1/4	7.11 LBS/FT	46 LBS	0.7 CU YD
HSS4x2x1/4	8.81 LBS/FT	46 LBS	0.7 CU YD
HSS4x3x1/4	10.51 LBS/FT	46 LBS	0.7 CU YD

LEGEND:
GS-GM = GUIDE SIGN GROUND MOUNT
GS-WM = GUIDE SIGN WALL MOUNT

REFER TO BREAKAWAY WIDE FLANGE STEEL SIGNPOST STANDARDS (BAW-A) FOR DETAILS
FOR CANTILEVER SIGN SUPPORT AND DETAILS SEE CANTILEVER SIGN STRUCTURES DRAWING NOS. SD-12 TO SD-24

McDonough Associates Inc.
Engineers / Architects
130 East Randolph Street Chicago, Illinois 60601