

SUMMARY OF QUANTITIES

CODE NO.	PAY ITEM DESCRIPTION	UNIT	URBAN TOTAL QUANTITY	ROADWAY	BOX CULVERT	ROADWAY	WATER MAIN	WATER MAIN	SANITARY
				80% FED 20% STATE	80% FED, 20% STATE	LIGHTING 80% FED, 20% STATE	100% VILLAGE OF MELROSE PARK	90% STATE 10% VILLAGE OF MELROSE PARK	75% STATE 25% VILLAGE OF MELROSE PARK
				CONSTRUCTION TYPE CODE					
				0004	0011	0021	0043	0043	0043
20100110	TREE REMOVAL (6 TO 15 UNITS DIAMETER)	UNIT	101	101					
20100210	TREE REMOVAL (OVER 15 UNITS DIAMETER)	UNIT	310	310					
20200100	EARTH EXCAVATION	CU YD	1,346	1,346					
20201200	REMOVAL AND DISPOSAL OF UNSUITABLE MATERIAL	CU YD	250	250					
20300100	CHANNEL EXCAVATION	CU YD	485	485					
20700220	POROUS GRANULAR EMBANKMENT	CU YD	455		455				
20800150	TRENCH BACKFILL	CU YD	184	184					
* 21101615	TOPSOIL FURNISH AND PLACE, 4"	SQ YD	1,364	1,364					
* 25000310	SEEDING, CLASS 4	ACRE	0.25	0.25					
* 25000700	AGRICULTURAL GROUND LIMESTONE	TON	0.50	0.50					
* 25100630	EROSION CONTROL BLANKET	SQ YD	465	465					
* 25200110	SODDING, SALT TOLERANT	SQ YD	1,187	1,187					
* 25200200	SUPPLEMENTAL WATERING	UNIT	45	45					
* 28000250	TEMPORARY EROSION CONTROL SEEDING	POUND	75	75					
28000400	PERIMETER EROSION BARRIER	FOOT	553	553					
28000500	INLET AND PIPE PROTECTION	EACH	4	4					
28000510	INLET FILTERS	EACH	15	15					
28100109	STONE RIPRAP, CLASS A5	SQ YD	231		231				
28200200	FILTER FABRIC	SQ YD	231		231				
40600200	BITUMINOUS MATERIALS (PRIME COAT)	TON	0.60	0.60					
40603080	HOT-MIX ASPHALT BINDER COURSE, IL-19.0, N50	TON	370	370					
40603310	HOT-MIX ASPHALT SURFACE COURSE, MX "C", N50	TON	94	94					
40600050	INCIDENTAL HOT-MIX ASPHALT SURFACING	TON	59	59					
42000516	PORTLAND CEMENT CONCRETE PAVEMENT 10 3/4" (JOINTED)	SQ YD	7,288	7,288					
42001300	PROTECTIVE COAT	SQ YD	9,599	9,568	31				
42300400	PORTLAND CEMENT CONCRETE DRIVEWAY PAVEMENT, 8 INCH	SQ YD	155	155					
42400200	PORTLAND CEMENT CONCRETE SIDEWALK 5 INCH	SQ FT	12,386.0	12,386.0					
42400410	PORTLAND CEMENT CONCRETE SIDEWALK 8 INCH	SQ FT	1,215.5	1,215.5					
42400800	DETECTABLE WARNINGS	SQ FT	72	72					
44000100	PAVEMENT REMOVAL	SQ YD	7,500	7,500					
44000200	DRIVEWAY PAVEMENT REMOVAL	SQ YD	1,465	1,465					
44000300	CURB REMOVAL	FOOT	85	85					
44000500	COMBINATION CURB AND GUTTER REMOVAL	FOOT	2,043	2,043					
44000600	SIDEWALK REMOVAL	SQ FT	7,822	7,822					
50100100	REMOVAL OF EXISTING STRUCTURES	EACH	1		1				

* SPECIALTY ITEM

FILE NAME = G:\ENR\08-5799-17 Lake St Triple Box Culvert\CAD\Civil\Sht\016844-INT-SQP.dwg



USER NAME = *USER*	DESIGNED - KAC	REVISED -
PLOT SCALE = #SCALE#	DRAWN - TMF	REVISED -
PLOT DATE = 1/27/2011	CHECKED - KAC	REVISED -
	DATE -	REVISED -

**STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION**

SUMMARY OF QUANTITIES LAKE STREET OVER ADDISON CREEK	
SCALE: N.T.S.	SHEET NO. 1 OF 5 SHEETS

F.A.U. RTE. 3537	SECTION 3264-*	TOTAL SHEETS 110	4 60144
ILLINOIS FED. AID P#			